DOE/OR/01-2785

Technical Memorandum #1, Environmental Management Disposal Facility Phase 1 Field Sampling Results Oak Ridge, Tennessee



This document is approved for public release per review by:

Susan D. Faucher 7/2/18

ETTP Classification and Information Control Office **Date**

DOE/OR/01-2785

Technical Memorandum #1, Environmental Management Disposal Facility Phase 1 Field Sampling Results Oak Ridge, Tennessee

Date Issued—July 2018

Prepared by
Leidos
Oak Ridge, Tennessee
under subcontract SC-17-024714
under revision number 16

Prepared for the
U.S. Department of Energy
Office of Environmental Management

URS | CH2M Oak Ridge LLC
Managing and Safely Delivering the Department of Energy's Vision
for the East Tennessee Technology Park Mission
under contract DE-SC-0004645

18-012(E)/072618

CONTENTS

FIGURES vii

TABLES ix

ACRONYMS xi

EXECUTIVE SUMMARY ES-1

ES.1 SETTING ES-1
ES.2 PHASE 1 INVESTIGATION APPROACH AND RESULTS ES-1
ES.2.1 Surface Water Walkovers ES-4
ES.2.2 Locate the Maynardville Limestone ES-4
ES.2.3 Determine Surface Water Flow ES-4
ES.2.4 Drill and Install Piezometers ES-5
ES.2.5 Test Subsurface Materials ES-5
ES.3 PHASE 1 CHARACTERIZATION CONCLUSIONS ES-6

1. INTRODUCTION 1-1

2. HYDROGEOLOGIC SETTING 2-1
2.1 GENERAL SITE CONDITIONS 2-1
2.2 GEOLOGY/HYDROLOGY 2-1
2.2.1 Geology 2-1
2.2.2 Surface Water Hydrology 2-5
2.3 GROUNDWATER 2-5
2.4 SITE CONCEPTUAL MODEL 2-5

3. SURFACE WATER WALKDOWN EVALUATION 3-1
3.1 APPROACH 3-1
3.2 FINDINGS 3-1
3.2.1 Parameter Results 3-1
3.2.2 Seep Locations 3-3

4. MAYNARDVILLE CONTACT EVALUATION 4-1
4.1 APPROACH 4-1
4.2 FINDINGS 4-1

5. SURFACE WATER FLOW EVALUATION 5-1
5.1 APPROACH 5-1
5.2 FLUME DATA FINDINGS 5-1

6. GROUNDWATER EVALUATION 6-1
6.1 APPROACH 6-1
6.2 NEW PIEZOMETERS 6-4
6.3 FINDINGS 6-7
6.3.1 FLUTe™/Slug Test Results 6-7
6.3.2 Groundwater Monitoring Findings 6-12

6.3.3 Groundwater Elevation Data 6-12
6.3.4 Comparable Existing Piezometers 6-13

7. GEOTECHNICAL TEST RESULTS 7-1
7.1 APPROACH 7-1
7.2 SUMMARY OF KEY RESULTS 7-1

8. VALIDATION OF KEY ASSUMPTIONS 8-1

9. REFERENCES 9-1

APPENDIX A SURFACE WATER MEASUREMENTS A-1

APPENDIX B BORING LOGS B-1

APPENDIX C SLUG TEST DATA C-1

APPENDIX D FLUTe™ TESTS D-1

APPENDIX E GROUNDWATER ELEVATION PLOTS E-1

APPENDIX F GEOTECHNICAL LABORATORY REPORTS F-1

FIGURES

Fig. ES.1. Location of the proposed EMDF. ES-2
Fig. ES.2. Monitoring locations at EMDF. ES-3
Fig. 1.1. Location of the proposed EMDF. 1-2
Fig. 2.1. General features of the EMDF site. 2-2
Fig. 2.2. Geologic map of the EMDF and surrounding area. 2-3
Fig. 2.3. General geologic cross-section of the EMDF site. 2-4
Fig. 3.1. Surface water measurement locations in the vicinity of the EMDF. 3-2
Fig. 4.1. Monitoring locations at EMDF. 4-2
Fig. 5.1. Surface water flow measurements at EMDF weirs. 5-2
Fig. 6.1. Piezometer locations at the EMDF. 6-2
Fig. 6.2. North–south geologic cross-section of EMDF. 6-9
Fig. 6.3. East–west geologic cross-section of EMDF. 6-10
Fig. 6.4. Time trend plot of groundwater elevation, specific conductivity, and pH with daily rainfall for well pair GW-978/GW-979. 6-14
Fig. 6.5. Time trend plot of groundwater elevation, specific conductivity, and pH with daily rainfall for well pair GW-980R/GW-981. 6-15
Fig. 6.6. Time trend plot of groundwater elevation, specific conductivity, and pH with daily rainfall for well pair GW-982/GW-983. 6-16
Fig. 6.7. Time trend plot of groundwater elevation, specific conductivity, and pH with daily rainfall for well pair GW-986/GW-987. 6-17
Fig. 6.8. Time trend plot of groundwater elevation, specific conductivity, and pH with daily rainfall for well pair GW-988/GW-989. 6-18
Fig. 6.9. Time trend plot of groundwater elevation, specific conductivity, and pH with daily rainfall for well pair GW-992R/GW-993. 6-19
Fig. 6.10. Time trend plot of groundwater elevation, specific conductivity, and pH with daily rainfall for well pair GW-994/GW-995. 6-20
Fig. 6.11. Time trend plot of groundwater elevation, specific conductivity, and pH with daily rainfall for well pair GW-998/GW-999. 6-21
Fig. 6.12. Water levels at well pair GW-978/GW-979 6-22
Fig. 6.13. Water levels at well pair GW-980R/GW-981. 6-22
Fig. 6.14. Water levels at well pair GW-982/GW-983 6-23
Fig. 6.15. Water levels at well pair GW-986/GW-987 6-23
Fig. 6.16. Water levels at well pair GW-988/GW-989 6-24
Fig. 6.17. Water levels at well pair GW-992R/GW-993. 6-24
Fig. 6.18. Water levels at well pair GW-994/GW-995 6-25
Fig. 6.19. Water levels at well pair GW-998/GW-999 6-25
Fig. 6.20. Bear Creek Valley well locations 6-27
Fig. 6.21. Extrapolated water levels for GW-978. 6-29
Fig. 6.22. Extrapolated water levels for GW-979. 6-29
Fig. 6.23. Extrapolated water levels for GW-980R. 6-30
Fig. 6.24. Extrapolated water levels for GW-981. 6-30
Fig. 6.25. Extrapolated water levels for GW-982. 6-31
Fig. 6.26. Extrapolated water levels for GW-983. 6-31
Fig. 6.27. Extrapolated water levels for GW-986. 6-32
Fig. 6.28. Extrapolated water levels for GW-987. 6-32
Fig. 6.29. Extrapolated water levels for GW-988. 6-33
Fig. 6.30. Extrapolated water levels for GW-989. 6-33
Fig. 6.31. Extrapolated water levels for GW-992R. 6-34

Fig. 6.32. Extrapolated water levels for GW-993. 6-34
Fig. 6.33. Extrapolated water levels for GW-994. 6-35
Fig. 6.34. Extrapolated water levels for GW-995. 6-35
Fig. 6.35. Extrapolated water levels for GW-998. 6-36
Fig. 6.36. Extrapolated water levels for GW-999. 6-36

TABLES

Table 5.1. Minimum and maximum flow rates for EMDF flumes, April 2018 5-3
Table 6.1. Slug test results for the EMDF shallow piezometers 6-3
Table 6.2. EMDF piezometer construction summary 6-5
Table 6.3. FLUTe™ test result summary for the EMDF piezometers 6-11
Table 6.4. Vertical hydraulic gradients at EMDF, Spring 2018 6-13
Table 7.1. Summary of EMDF split-spoon and bulk sample laboratory index test results 7-2

This page intentionally left blank.

ACRONYMS

BCV	Bear Creek Valley
CBCV	Central Bear Creek Valley
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act of 1980
D	Drainage
DOE	U.S. Department of Energy
E	East
EMDF	Environmental Management Disposal Facility
EMWMF	Environmental Management Waste Management Facility
FLUTe™	Flexible Liner Underground Technologies, LLC
FSP	Field Sampling Plan
NT	North Tributary
ORNL	Oak Ridge National Laboratory
ORR	Oak Ridge Reservation
PVC	polyvinyl chloride
QAPP	Quality Assurance Project Plan
RI/FS	Remedial Investigation/Feasibility Study
T	transmissivity
TDEC	Tennessee Department of Environment and Conservation
TM	technical memorandum
UPF	Uranium Processing Facility
W	West
UCOR	URS | CH2M Oak Ridge LLC

This page intentionally left blank.

EXECUTIVE SUMMARY

An estimated 2.2 million cubic yards of landfill disposal capacity beyond what is already available in the existing Environmental Management Waste Management Facility (EMWMF) is needed for the disposal of wastes from continuing Comprehensive Environmental Response, Compensation, and Liability Act of 1980 cleanup actions on the Oak Ridge Reservation. Additional capacity will be provided by the Environmental Management Disposal Facility (EMDF), which is proposed to be located in Central Bear Creek Valley (CBCV), approximately 1.5 miles southwest of the existing EMWMF (Fig. ES.1).

Characterization of this site began in February 2018 as described in the *Phase 1 Field Sampling Plan for the Proposed Environmental Management Disposal Facility for Comprehensive Environmental Response, Compensation, and Liability Act Oak Ridge Reservation Waste Disposal, Oak Ridge, Tennessee* (Field Sampling Plan) [Department of Energy 2018]. Characterization was intended to determine if the key assumptions for groundwater and surface water conditions at the site were correct and to confirm the CBCV site was acceptable for a new, low-level waste landfill. Additional characterization is planned to develop the engineering design for the landfill.

The results of the Phase 1 data collection are contained in this Technical Memorandum (TM).

ES.1 SETTING

The CBCV site is located along Pine Ridge between two streams, North Tributary (NT)-10 and NT-11. A smaller stream at the site, Drainage (D)-10 West (W), is located just west of NT-10 (Fig. ES.2). The area is mostly forested, except for a cleared area with a large soil pile and two constructed wetlands for the Y-12 National Security Complex. The Haul Road and Bear Creek Road cross the southern edge of the site and will need to be rerouted prior to EMDF construction.

The anticipated landfill would overlie steeply angled bedrock with fine-grained shales, siltstones, and mudstones with some limestone layers. Recent stream deposits are present on the valley floors, particularly along D-10W at the eastern side of the site. Karst features, such as sinkholes, sinking streams, and resurgent springs, are not present beneath the proposed footprint of the CBCV site, but are present along Bear Creek south of the site.

Precipitation primarily runs off as surface water and shallow groundwater in the stormflow zone. During the summer/fall growing season, the streams within the CBCV site may dry up, although there is still flow during significant rainfall events. However, there is continuous surface water flow in Bear Creek.

ES.2 PHASE 1 INVESTIGATION APPROACH AND RESULTS

Bear Creek Valley (BCV) has been extensively investigated and monitored over the years, although not at the proposed EMDF location. The Phase 1 investigation provided site-specific information for the proposed EMDF site.




Fig. ES.1. Location of the proposed EMDF.




Fig. ES.2. Monitoring locations at EMDF.

The investigation approach was developed with the U.S. Environmental Protection Agency and Tennessee Department of Environment and Conservation (TDEC). The investigation consisted of the following tasks:

- Perform surface water walkovers to evaluate streams, identify seeps, springs, and other expressions of shallow groundwater.
- Locate the contact with the Maynardville Limestone, the type of bedrock most prone to contain karst features.
- Determine surface water flow by installing flumes to measure flow in NT-10, D-10W, and NT-11.
- Drill and install piezometers to measure groundwater surfaces and to obtain detailed subsurface information.
- Test subsurface materials to obtain design data to develop the engineering design for the proposed landfill.

The acquired data were used to verify the CBCV site is appropriate for siting a landfill and will be used to develop the engineering design.

ES.2.1 Surface Water Walkovers

Two detailed site walkovers were performed during the wet season (January 30, 2018, and February 27, 2018) to further characterize surface geology and hydrology; identify geotechnical areas of interest; and identify seeps, springs, and other expressions of shallow groundwater (Fig. ES.2). Two additional walkovers, representing drier conditions (May 1 and June 4, 2018) were also completed. TDEC participated in all of the walkovers.

All previously identified seeps were located except for one seep in a disturbed area. No additional seeps were identified during the site walkovers. Field data collected during the walkovers are provided in Appendix A. In general, pH and specific conductivity of the surface water in these tributaries increase from north to south. Additional dry season walkovers will be performed in the summer/fall of 2018 and will be documented in a second TM.

ES.2.2 Locate the Maynardville Limestone

The Maynardville Limestone is the type of bedrock most prone to contain karst features in BCV. The contact between the Maynardville and Nolichucky Shale was previously mapped by a regional investigation about 300 ft south of the planned landfill footprint. The January 2018 surface walkover with subject matter experts (SMEs) and TDEC geologists examined this location and revised the Maynardville Limestone contact in CBCV based on observations within NT-10 and D-10W streambeds. The contact location within the NT-11 streambed was found later by the same SME. The contact was confirmed to be approximately 50 ft further south of the proposed landfill location than was originally mapped (Fig. ES.2).

ES.2.3 Determine Surface Water Flow

Six surface water flow measurement stations were installed to determine surface water flow along the stream channels of NT-10, D-10W, and NT-11 (Fig. ES.2). These stations were placed to evaluate surface water flow, particularly close to the proposed landfill location. TDEC participated in the walkdown to determine flume placement.

Three flumes were installed along NT-11, two along D-10W, and one at NT-10 (Fig. ES-2). The flumes were sized to accommodate the reasonably expected flow rates based on historical information and additional field observations. No flume was installed at D-11E because there is no stream channel or observed surface water flow.

Flumes were equipped to measure surface water flow, pH, specific conductivity, and temperature at 30-min intervals. These data are automatically recorded and downloaded every two weeks. The surface water flow data will be used to design surface water controls for the landfill.

As expected, flow rates increase downstream, from north to south, and increase quickly in response to rainfall. April 2018 flow rates for NT-11 ranged from 22 to 700 gallons per minute (gpm). The flow rate for NT-10 during April 2018 has a similar range of 24 to 693 gpm. D-10W is a smaller stream and has a lower flow rate. The April 2018 flow rate ranged from 6 to 478 gpm. Later in the year during the dry season, there may be no flow at some of these flumes.

ES.2.4 Drill and Install Piezometers

Eight pairs of bedrock and shallow piezometers were installed within the proposed landfill area to monitor the groundwater (Fig. ES.2). First, boreholes were cored from the surface to total depth to obtain representative rock cores. These cores were photographed and described at the drill site. Next, subsurface testing was conducted in the bedrock holes to estimate the hydraulic properties. Piezometers were constructed with well screens placed to monitor groundwater bearing zones.

Following piezometer construction, the shallow piezometers were tested to estimate the hydraulic properties. After testing was completed, downhole monitors were installed to measure groundwater levels, temperature, pH, and specific conductivity at 30-min intervals. In general, the EMDF wells show typical fluctuations in specifc conductivity and pH in response to precipitation events. Groundwater levels show responses to rainfall events in most of the shallow and deep wells indicating some recharge is occurring at several locations on the site.

This TM includes data from the continuous monitoring of these 16 piezometers during the March/April time frame. Monitoring of the EMDF water levels will continue for at least one year to ensure seasonal high-water levels are captured for evaluation in the design of the EMDF, and data will be provided in the next TM.

Groundwater levels will be used to: (1) estimate the groundwater surface elevations across the entire footprint of EMDF prior to construction, and (2) provide information for the engineering design.

Continuous groundwater level monitors were installed in existing BCV groundwater wells located outside of the EMDF area in similar conditions prior to completing and instrumenting the CBCV piezometers. Data from these wells provide additional, comparable, wet season data and were used to provide the relative magnitude change in groundwater elevations during wetter periods. These data were then used to predict the February 2018 groundwater levels for each EMDF well (wet season high groundwater levels).

ES.2.5 Test Subsurface Materials

The laboratory testing program was directed toward determining the general soil classification, physical properties, shear strength, and compressibility of the soil for the engineering analysis and design of the EMDF. Limited permeability testing was also conducted on both relatively undisturbed samples (tube samples) and from recompacted bulk samples taken during piezometer drilling. All laboratory testing was performed in accordance with applicable American Society for Testing and Materials Standards. In total,

18 thin-walled (i.e., Shelby tube) samples, 69 split-spoon soil samples, 10 bulk soil samples, and 10 rock core samples were shipped to laboratories for testing. Appendix F provides the laboratory reports for geotechnical laboratory testing. The collected data will be used to develop the engineering design.

ES.3 PHASE 1 CHARACTERIZATION CONCLUSIONS

Results of the Phase 1 site characterization confirm the acceptability of the CBCV site for a new, low-level waste landfill and support final site selection based on the following conclusions.

Walkovers confirmed the location of existing seeps and did not locate additional seeps in the EMDF area. The contact with the Maynardville Limestone is located approximately 50 ft further south of the currently proposed EMDF footprint than previously mapped.

Precipitation primarily runs off as surface water and as shallow groundwater in the stormflow zone. Site walkovers found numerous cases where surface water entered and exited the soil through decayed trees and other types of features. Flumes record higher stream flows following precipitation, indicating that precipitation is running off as stormwater. Flow rates rapidly decrease when precipitation is over, indicating a smaller influence from groundwater.

Core drilling for the EMDF piezometers confirmed the presence of typical BCV geologic structures in the subsurface, including steeply dipping beds; interbedded shales siltstones and some limestone; and the presence of joints and fractures in bedrock.

Groundwater elevations are typical of other BCV wells in similar settings and were similar to the groundwater elevations predicted in the Remedial Investigation/Feasibility Study (RI/FS). Groundwater levels measured in both deep and shallow piezometers during the Phase 1 characterization confirmed that groundwater discharges as seeps in the valleys and drainages, and mirroring topography, is higher topographically beneath knolls/ridges. The elevation beneath the largest knoll in the site is lower topographically than predicted in the RI/FS. Groundwater levels respond to rainfall events, indicating minor recharge is occurring on the site.

1. INTRODUCTION

The mission of the U.S. Department of Energy (DOE) Oak Ridge Office of Environmental Management is to decommission and demolish numerous facilities and conduct remedial actions under the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (CERCLA) on the Oak Ridge Reservation (ORR) in Oak Ridge, Tennessee. This effort requires an estimated 2.2 million cubic yards of landfill disposal capacity beyond what is available in the existing Environmental Management Waste Management Facility (EMWMF) for the disposal of wastes from CERCLA cleanup actions. The *Remedial Investigation/Feasibility Study for the Comprehensive Environmental Response, Compensation, and Liability Act Oak Ridge Reservation Waste Disposal, Oak Ridge, Tennessee* (RI/FS) [DOE 2017], evaluated several alternatives for the disposal of this waste, including no action, off-site disposal, and on-site disposal.

The proposed Environmental Management Disposal Facility (EMDF) site on the ORR, located in Central Bear Creek Valley (CBCV), is approximately 1.5 miles southwest of the existing EMWMF. The approximately 70-acre tract was identified as the best alternative for development of the disposal facility based on available capacity and location (Fig. 1.1). The Phase 1 site characterization activities were focused on the CBCV site.

The Phase 1 site characterization activities began in January 2018. All activities were conducted in accordance with the *Phase 1 Field Sampling Plan for the Proposed Environmental Management Disposal Facility for Comprehensive Environmental Response, Compensation, and Liability Act Oak Ridge Reservation Waste Disposal, Oak Ridge, Tennessee* (Field Sampling Plan [FSP]) [DOE 2018], which included the project-specific Quality Assurance Project Plan (QAPP) for the Proposed EMDF Design Investigation. The QAPP identifies the procedures that are to be followed in the collection, custody, sample handling, data management, and quality control activities for all anticipated EMDF investigation activities.

The objective of Phase 1 site characterization of the proposed EMDF site was to validate key assumptions regarding the hydrogeologic setting (groundwater and surface water conditions) at the site. These key assumptions will be used to confirm the acceptability of the CBCV for a new, low-level waste landfill and to support a final site selection. The key assumptions for the Phase 1 characterization are:

- Geology is typical of Bear Creek Valley (BCV) with steeply dipping, fractured bedrock, and there are no major karstic features in the Maryville, Nolichucky, or Rogersville formations underlying the CBCV site.
- The contact with the Maynardville Limestone is located south of the currently proposed EMDF footprint.
- Precipitation primarily runs off as surface water and shallow groundwater in the stormflow zone.
- Groundwater elevations are typical of other BCV wells in similar settings.

This Technical Memorandum (TM) #1 presents the data collected during the Phase 1 site characterization, the analysis of the data in relation to the geologic and hydrologic properties, and an evaluation of the key assumptions associated with the EMDF site.




Fig. 1.1. Location of the proposed EMDF.

2. HYDROGEOLOGIC SETTING

2.1 GENERAL SITE CONDITIONS

The CBCV site is situated within an upland area located between north–south trending valleys of North Tributary (NT)-10 and NT-11. The site and surrounding areas are forested, except for areas along the south side between the Haul Road and Bear Creek Road, where the area has been cleared. The cleared area includes a recent soil staging area along the southern margin and two wetland basins completed in 2015 for the Y-12 National Security Complex compensatory wetland mitigation. The Haul Road and Bear Creek Road are located at the southern edge of the site and will need to be rerouted prior to EMDF construction.

The larger surface water conveyances within the site are Drainage (D)-10 West (W), parallel to and just west of NT-10, and D-11 East (E), an east–west trending feature that drains westward into NT-11 near the center of the site (Fig. 2.1). An additional shallow east–west trending drainage was present in the southern part of the area prior to construction of the Uranium Processing Facility (UPF) wet spoils pile. This drainage was noted as dry when previously observed and is now covered by the UPF wet spoils pile; however, there was a seep within this drainage area downgradient of the wet spoils pile that is now covered by a sediment basin.

The BCV has been extensively investigated over the years. Geologic, hydrogeologic, and groundwater contamination conditions have been characterized, and there is routine monitoring of surface water conditions and groundwater conditions in specific areas. In addition, other investigations have been conducted to identify wetlands, ecological species of concern, and cultural resources. This Phase 1 site characterization provides additional site-specific hydrogeologic information for the proposed EMDF site.

2.2 GEOLOGY/HYDROLOGY

The available hydrogeologic data for various potential EMDF sites in BCV are described in the RI/FS (DOE 2017). The general subsurface hydrogeological conditions at the CBCV site are known from previous characterization performed of the BCV watershed summarized in the *Groundwater Strategy for the U.S. Department of Energy, Oak Ridge Reservation, Oak Ridge, Tennessee* (DOE 2014).

2.2.1 Geology

The anticipated waste footprint at the CBCV site predominantly overlies bedrock of the Conasauga Group (Fig. 2.2), including the Maryville Formation, and Nolichucky Shale. Recent alluvium is present on the valley floor along D-10W (eastern side of the site).

These formations are predominantly shales, siltstones, and mudstones, with some interbedded limestone. There is little limestone present in the bedrock underlying the proposed disposal cells, even in the Maryville Formation. The crest of the knoll below the north center of the footprint is underlain by the erosion-resistant Dismal Gap/Maryville Formation. The typical weathering profile of topsoil, silty/clayey soil residuum, saprolite, and fractured bedrock occupy the undisturbed site areas.

In BCV, the average dip of the formations is 45° southeast (Fig. 2.3). Some microfolds to mesofolds are present. Fractures are present within the bedrock and exert substantial control on the location of the tributaries. These fractures and macro/micropores within the remaining soils/saprolite and bedrock provide the primary routes for groundwater flow (and contaminant transport) as documented in the *2016 Remediation Effectiveness Report for the U.S. Department of Energy Oak Ridge Reservation, Oak Ridge, Tennessee* (DOE 2016). A key assumption is that the geology is typical of BCV with steeply dipping,




Fig. 2.1. General features of the EMDF site.





Fig. 2.2. Geologic map of the EMDF and surrounding area.



Cra/Crs – Lower Cambrian Rome Formation; Apison Shale Member and Sandstone Member.
Ccu – Middle Cambrian Conasauga Shale Undivided (including the Nolichucky Shale).
Cmn – Upper Cambrian Maynardville Limestone.
Ccr – Upper Cambrian Copper Ridge Dolomite.

Fig. 2.3. General geologic cross-section of the EMDF site.

fractured bedrock, and there are no major karstic features in the Maryville, Nolichucky, or Rogersville formations underlying the CBCV site.

Thin layers of alluvial and colluvial soils may be present along streams, drainage ways, and the base of steeper slopes. These soils may be looser, more compressible, and more permeable than the underlying residual soils or saprolite. As noted in *Geology of the West Bear Creek Site* (Oak Ridge National Laboratory [ORNL] 1989):

> "The soils are underlain by a comparatively thick saprolite zone which varies from 10 to 20 ft thick. The saprolite is composed of weathered bedrock which has lost its rock cement but retained its bedding features. Its upper portions can be readily penetrated with a hand auger. The saprolite/bedrock contact is gradational due to decreasing weathering with depth but is typically defined as the depth of machine auger refusal."

Karst features such as sinkholes, sinking streams, and resurgent springs have not been documented within the formations underlying the proposed footprint of the CBCV site. Karst features are documented within the Maynardville outcrop belt south of the CBCV site. A key assumption is that the contact with the Maynardville Limestone is located south of the currently proposed EMDF footprint.

2.2.2 Surface Water Hydrology

The CBCV site surface water systems are fed by precipitation, surface runoff and shallow stormflow, and both shallow and deeper groundwater that discharges via springs and seeps. In areas underlain by Conasauga Group shales, as much as 90% of the water entering the groundwater system flows rapidly through highly porous, shallow soil. In areas underlain by soluble, massive carbonate bedrock of the Maynardville Limestone, a larger fraction of the water enters the groundwater system by conduit flow through deeper flow pathways (DOE 2016). A key assumption is that precipitation primarily runs off as surface water and shallow groundwater in the stormflow zone.

Historical continuous flow monitoring data were not previously available for NT-10, NT-11, or D-10W. The available U.S. Geological Survey base flow data indicated that base flow is continuous along the NT-10, D-10W, and NT-11 stream channels during the winter/spring non-growing wet season. During the summer/fall growing season with warm and often dry conditions, base flow is negligible and limited to pulsed flow associated with significant storm rainfall events. Flow monitoring for Bear Creek downstream of the CBCV site indicates continuous flow in Bear Creek (DOE 2017).

2.3 GROUNDWATER

There were no previous groundwater elevation data available for the CBCV site prior to this investigation. Available groundwater elevation data were projected to this site from adjacent areas with similar hydrogeologic conditions to plan the Phase 1 investigation. A key assumption is that groundwater elevations are typical of other BCV wells in similar settings. As the landfill is constructed, the current surface water and groundwater flow regime will be modified due to regrading of the site and installation of impermeable barriers and adjustments to surface runoff.

2.4 SITE CONCEPTUAL MODEL

The majority of flow from upland areas is directed toward the valley axis by the NTs. Groundwater in bedrock that does not discharge directly to surface water (e.g., within a confined system) has an

upward gradient because of the pressure gradient of recharge from Pine Ridge and discharges into the Bear Creek–Maynardville Limestone drainage system.

Bear Creek flows more or less continuously over non-karst bedrock, but loses flow to subsurface conduits where it crosses karst features in the Maynardville Limestone. Underflow conduits in the Maynardville Limestone continuously convey base flow, while overflow conduits and Bear Creek carry high flows during the wet season and heavy rainfall events.

The CBCV site area slopes to the south–southeast. As described in the *Oak Ridge Reservation Physical Characteristics and Natural Resources* (ORNL 2006), sloping land surfaces on the ORR exhibit the characteristics of hillslope hydrology. In undisturbed, naturally vegetated areas such as the CBCV site, an estimated 80 to 90% of precipitation is captured and discharged from the 3 to 6.5-ft (1- to 2-m) storm-flow zone/root zone and does not infiltrate into the groundwater table. During November through March when plants are not consuming water and shallow soils are saturated, lateral drainage of water occurs on slopes through macropores (e.g., holes left by the decay of dead plant roots and animal burrows) as well as through vertical seepage to the water table through pervious zones (Clapp 1997).

3. SURFACE WATER WALKDOWN EVALUATION

3.1 APPROACH

Two detailed site walkovers were performed during the wet season (January 30, 2018, and February 27, 2018) to further characterize surface geology; identify geotechnical areas of interest; and identify seeps, springs, and other expressions of shallow groundwater in NT-10, D-10W, D-11E, and NT-11. The walkovers were conducted by a qualified hydrologic professional, as defined in Tennessee Department of Environment and Conservation (TDEC) 0400-40-17. TDEC personnel also participated in all of the walkovers.

Observations of flow in macropores and similar features during the wet season were also noted to determine potential impacts on design. The walkover included a description every 50 ft of NT-10, D-10W, and NT-11 (as safe access allowed) and field measurements of temperature, specific conductivity, and pH.

Two additional walkovers, representing drier conditions (May 1 and June 4, 2018) were also completed. The results of all walkovers are documented in Appendix A. Additional dry season walkovers will be performed and documented in the TM #2, as appropriate.

3.2 FINDINGS

The site walkovers have identified several noteworthy soil macropore and channel features in the upper 3 ft of soil in the Nolichucky Shale. A shallow macropore/soil channel transmits percolation water from soils to the NT-11 stream channel in the Nolichucky Shale outcrop area. Overland surface water flow into a soil macropore/channel was also observed, and that subsurface channel is daylighted a short distance downstream due to collapse and downstream transport of shallow soils. A small amount of water flow emanating from the channel has been observed at this location. This feature joins another branch of subsurface flow from an unnamed western valley. These types of soil drainage features are typical in undisturbed ORR soils and are a part of the stormflow system that rapidly conducts percolation water laterally downslope to stream channels.

The site walkover found that the east–west valley draining to NT-11, also referred to as D-11E, located on the western slope of the high knoll in the Maryville Formation, contained no defined surface water channel.

A well-established surface channel approximately 1-ft wide by 1-ft deep was encountered in the D-10W valley. The channel contained isolated pools of standing water, but no flow was occurring. The D-10W valley is approximately 50% less incised than the adjacent NT-10 and NT-11 valleys and has a much narrower headwater basin.

The surface water field measurenment locations are shown on Fig. 3.1. The results of the surface water field measurements are illustrated on maps included in Appendix A.

3.2.1 Parameter Results

Appendix A provides illustrations of the field data collected during the four walkover surveys (January, February, May, and June 2018) conducted to date. These figures show that, in general, pH and specific conductivity of the surface water in these tributaries increase from north to south. This indicates influx of groundwater and an increasing carbonate content of the bedrock to the south.




Fig. 3.1. Surface water measurment locations in the vicinity of the EMDF.

3.2.2 Seep Locations

Seep locations are identified on Fig. 3.1. All but one of the previously identified seeps were located and no additional seeps were located during the site walkovers. One seep was previously located in an area disturbed by the UPF and could not be located during the walkovers.

This page intentionally left blank.

4. MAYNARDVILLE CONTACT EVALUATION

Previous mapping of BCV indicated that the contact between the Nolichucky Shale and Maynardville Limestone was located approximately 300 ft south of the proposed southernmost waste limit (DOE 2017).

4.1 APPROACH

The Nolichucky/Maynardville geologic contact in the NT-10 and D-10W stream channels was located during the first surface water walkover in January 2018. Participants included a hydrogeologist/subject matter expert from the URS | CH2M Oak Ridge LLC (UCOR) Water Resources Restoration group and TDEC geologists. The walkover used observations of bedrock outcrops in the stream channels and observations of weathered bedrock material to more precisely identify the geologic contact. Coordinates for these contact locations were obtained using Global Positioning System equipment.

4.2 FINDINGS

The Maynardville/Nolichucky geologic contact was observed in the field at three locations. The contact was located in the drainage channel of NT 10, D-10W, and near the confluence of NT-11 and Bear Creek (Fig. 4.1). The location of the Maynardville/Nolichucky geologic contacts observed in the field were approximately 50 ft further south than represented on the geologic maps prior to the field mapping effort.




Fig. 4.1. Monitoring locations at EMDF.

5. SURFACE WATER FLOW EVALUATION

5.1 APPROACH

The areas of the three surface water basins between the crest of Pine Ridge on the northwest and the geologic contact between the Maynardville Limestone and the Nolichucky Shale on the southeast are shown in Fig. 4.1. The Maynardville/Nolichucky geologic contact is the most downstream flow measurement location because further downstream surface water tends to sink into the Maynardville karst, causing a low bias to the flow data.

Six surface water flow measurement stations were installed at locations identified during the January surface water walkdown. These were located in the Nolichucky Shale and Maryville Formation outcrop areas in NT-10, D-10W, and NT-11 (Fig. 5.1). TDEC personnel participated in the walkdown including discussion of flume placement.

Three measurement flumes were installed in NT-11 at locations identified during the site walkover (SF-1, -2, and -3; see Fig. 4.1). For the D-10W valley, a surface water flow measurement station was installed downstream of the Haul Road (SF-4) and another downstream of Bear Creek Road near the Nolichucky Shale/Maynardville Limestone geologic contact (SF-5). Another surface water flow measurement station (SF-6) was placed on the downstream side of the culvert under Haul Road in NT-10, the northernmost location with a well-defined stream channel. The flumes were installed during March 2018.

The flumes were sized based on historical flow information and measurements of the stream width, depth, and bankfull dimensions collected during the site walkover. Based on this information, 2.0-ft H-flumes and 1.5-ft H-flumes were sized for installation at the site. The 1.5-ft H-flumes were installed at upstream locations, where the stream channels, size of the catchment basins, and associated runoff are smaller. The 2.0-ft H-flumes were installed downstream, where higher flows are expected due to larger drainage areas as well as the influence of the Haul Road, Bear Creek Road, UPF Spoils Area, and other disturbed areas. In total, three 2.0-ft H-flumes and three 1.5-ft H-flumes were installed within the three primary tributaries at EMDF.

All of the surface water flumes were equipped with a flow meter and water quality analyzer and controller system to provide monitoring of water flow through the flumes. Final surveying of all locations occurred upon completion of monitoring station installation. The coordinates and elevations of the locations of each monitoring site and positions and elevations of the base of each flow control section were surveyed to an accuracy of 0.1 ft horizontal and 0.01 ft vertical.

5.2 FLUME DATA FINDINGS

Surface water flow measurements were performed as described in the Phase 1 FSP and included continuous flow, temperature pH, and specific conductivity measurements collected at 30-min intervals.

Flow data collected at the flumes installed in March 2018 at EMDF are illustrated in Fig. 5.1. As expected, flow rates increase downstream, from north to south, and increase quickly in response to rainfall. April 2018 flow rates for NT-11 ranged from 22 to 700 gallons per minute (gpm). The flow rate for NT-10 during April 2018 has a similar range of 24 to 693 gpm. D-10W is a smaller stream and has a lower flow rate. The April 2018 flow rate ranged from 6 to 478 gpm. Later in the year during the dry season, there may be no flow at some of these flumes.

Table 5.1 provides a summary of the flow rates recorded in April 2018.




Fig. 5.1. Surface water flow measurements at EMDF weirs.

Table 5.1. Minimum and maximum flow rates for EMDF flumes, April 2018

Tributary measured	Flume	Minimum flow rate (gpm)	Maximum flow rate (gpm)
NT-11	SF-1	30	700
NT-11	SF-2	28	538
NT-11	SF-3	22	328
D-10W	SF-4	12	395
D-10W	SF-5	6	478
NT-10	SF-6	24	693

D = drainage.
EMDF = Environmental Management Disposal Facility.
gpm = gallons per minute.
NT = North Tributary.

This page intentionally left blank.

6. GROUNDWATER EVALUATION

6.1 APPROACH

The following describes the installation and results of the piezometers installed at the EMDF during the Phase 1 site characterization. The locations of the piezometers are shown on Fig. 6.1.

Flexible Liner Underground Technologies, LLC (FLUTe™)[1] tests (bedrock piezometers) and slug tests (shallow piezometers) were conducted to develop a more complete picture of the *in situ* hydraulic conductivity. Hydraulic conductivity (horizontal) was measured by performing slug tests for piezometers completed in the residuum, and FLUTe™ testing was performed for bedrock intervals to maximize the amount and precision of hydraulic conductivity information obtained.

FLUTe™ Tests

FLUTe™ testing was performed in each open, deep borehole prior to piezometer installation. The results from the FLUTe™ testing and interpretation of the borehole logs, relative to identifying target intervals of permeable water-bearing bedrock, were used to determine screen and sand-pack intervals for both the deep and shallow piezometers at each location. During FLUTe™ testing, a flexible borehole liner made of a water-tight, urethane-coated, nylon fabric is lowered into the borehole. Each flexible liner is custom made for each borehole and shipped from the FLUTe™ manufacturing facility in New Mexico to the field site on a reel. Tests were performed in accordance with the manufacturer's guidelines. The rate of water addition to the liner during installation is carefully controlled to create a nearly constant applied head differential between the inside of the liner and the water level in the formation outside the liner. The rate at which water is added to the liner is governed mostly by the rate at which the water can escape into the permeable features in the open hole below the descending liner as it forces the water out into the permeable zones in the formation. About 1% of the transmissivity (T) remaining below the descending liner at any depth in the hole is the limit of resolution. For that reason, the resolution in the bottom portion of the hole is better than in the upper portion of the hole.

Slug Tests

Hydraulic conductivity (horizontal) was measured by performing slug tests for piezometers completed in the residuum. Slug tests were performed after well development in shallow piezometers GW-979, GW-981, GW-983, GW-987, GW-989, GW-993, GW-995, and GW-999 (Table 6.1). The slug tests were conducted by monitoring water-level changes after displacement of a volume of water. Water was displaced by the insertion of a 4-ft by 1.25-in. stainless steel slug bar into the well just below the static water level. Steady but rapid insertion of the slug bar was employed to create as rapid a displacement of the water as possible while creating minimal splash in the piezometer. A second test was performed by displacing water downward with the sudden removal of the slug bar. Slug test results are summarized in Table 6.2 and presented in Appendix C.

Water-level data were collected during the slug tests using a pressure transducer data logger. Static water levels were measured manually and recorded prior to setting the transducer into the piezometer. The pressure transducer was then lowered into the well. The transducer was set at a depth below the water table appropriate for the pressure range of the transducer and deep enough to be below the inserted slug bar during the test. After setting the transducer, the water level was allowed to equilibrate to static conditions

[1] Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors.




Fig. 6.1. Piezometer locations at the EMDF.

Table 6.1. Slug test results for the EMDF shallow piezometers

Well ID	Screen depth (ft bgs)	Saturated thickness (ft)	Type of test	Initial displacement (ft)	Static water column height (ft)	Bouwer-Rice hydraulic conductivity (cm/sec)
GW-979	26.3 - 36.3	9.7	Slug in	1.44	21.24	4.17E-04
			Slug out	1.55	21.27	4.96E-04
			Average			4.56E-04
GW-981	22.1 - 32.1	9.7	Slug in	1.01	10.96	6.39E-05
			Slug out	1.2	11.03	4.61E-05
			Average			5.50E-05
GW-983	79.1 - 89.2	9.7	Slug in	0.67	26.14	5.04E-03
			Slug out	1.28	26.16	4.96E-03
			Average			5.00E-03
GW-987	16.1 - 26.1	9.7	Slug in	1.43	19.45	9.52E-05
			Slug out	1.45	18.84	9.75E-05
			Average			9.64E-05
GW-989	33.6 - 43.6	9.7	Slug in	1.35	31.59	1.42E-04
			Slug out	1.49	31.61	6.68E-05
			Geometric mean			9.74E-05
GW-993	23.0 - 33.0	9.7	Slug in	0.63	28.46	5.88E-04
			Slug out	0.68	28.51	6.98E-04
			Average			6.43E-04
GW-995	22.1 - 32.1	9.8	Slug in	1.44	24.05	1.85E-04
			Slug out	1.45	24.07	1.84E-04
			Average			1.85E-04
GW-999	10.3 - 20.3	9.7	Slug in	1.31	18.3	5.14E-04
			Slug out	1.43	18.33	4.54E-04
			Average			4.84E-04

bgs = below ground surface.
cm = centimeters.
EMDF = Environmental Management Disposal Facility.
ft = feet.
ID = identification.
sec = seconds.

prior to starting the test. The transducer was set to logarithmic data collection mode so that rapid water-level changes in the early part of the slug test could be monitored accurately. The slug bar, transducer, cable, and water-level tape were decontaminated using a non-phosphate detergent solution followed by a distilled water wash, prior to insertion in each well.

6.2 NEW PIEZOMETERS

Eight pairs of piezometers were installed to monitor the shallow and intermediate groundwater within the cell boundary (Fig. 6.1). Piezometers were installed in each designated borehole by Tennessee qualified monitoring well drillers in accordance with ORR requirements as described in Appendix B, Sect. B.3, of the FSP (DOE 2018). Depths and testing requirements for each piezometer are provided in Table 6.2. Piezometers were developed no sooner than 24 hr after installation, and development continued until the piezometer responded to water-level changes and produced clear, sediment-free water to the extent possible.

Boreholes were cored from the surface to total depth to obtain representative lithologic data from across the site and in representative formations, and the cores were described and logged at the drillsite. The borehole logs are provided in Appendix B. Piezometers were placed to obtain representative lithologic and groundwater data from across the site and in representative formations. Because these piezometers could be preferential pathways to groundwater, all piezometers within the footprint of the disposal cells will be plugged and abandoned as per UCOR procedures prior to construction of the EMDF (DOE 2018).

Monitoring wells were constructed with 2-in.-diameter, 0.010-in. slot, schedule 40 polyvinyl chloride (PVC) screen and schedule 40 flush-threaded PVC riser pipe. The installed screen sections were either 5 or 10-ft in length depending on the length of the target interval. All shallow piezometers were constructed with 10-ft screens. Screen caps were constructed of schedule 40 PVC threaded end caps along with a 1-ft section of blank schedule 40 PVC riser pipe. The screen and riser sections are Silver-Line Plastics, Enviro Pure brand and arrived at the site in factory packaging. Packaging was only removed immediately prior to well installation, and casing and screen sections were handled while wearing clean, disposable, nitrile gloves during installation. All well screen and riser components were measured to the nearest 0.01 in., assembled, and lowered into the borehole. The length of casing extending above ground level relative to total screen and casing riser length was calculated to properly position the monitoring well screen. The sand pack consisted of DSI “GP#2” gravel pack specifically packaged for use in the environmental industry. The sand pack was gravity placed into the annular space between the piezometer screen and the borehole wall from the bottom of the well screen to a minimum of 2 ft and a maximum of 5 ft above the top of the screen.

Following sand-pack installation, at least 2 ft of coated bentonite pellets were added as a seal above the sand pack. In the boreholes that required centralizers, the pellets also were installed and measured through the 1-in. tremie pipe, as described above for the sand pack. In the auger boreholes, augers were pulled back exposing the borehole wall as the bentonite pellets were added. The depth to the sand pack and bentonite pellet seal was periodically checked with a sounding tape to verify proper placement. Per application instructions, the bentonite pellet seal requires a minimum of 8 hr to hydrate prior to grouting. In the field, the bentonite pellet seal was given 16 to 24 hr to hydrate, exceeding this requirement. The remainder of the annular space was sealed with a cement-bentonite grout mixed to specifications outlined in the statement of work.

Table 6.2. EMDF piezometer construction summary

Location ID	Date completed	Drilling method[1]	Location coordinates		Boring depth (ft)	Ground elev. (ft-MSL)	Casing ID (in.)	Elevation at top of casing (ft-MSL)	Elevation at bottom of casing (ft-MSL)	Casing stick-up (ft)	Screen interval (ft-bgs)	Top of screen elev. (ft-MSL)	Bottom of screen elev. (ft-MSL)	Sand pack interval (ft-bgs)	Bentonite pellet seal interval (ft-bgs)	Grout interval (ft-bgs)	Total depth of well (ft-TOC)	Depth of water at completion (ft-TOC)
			Northing	Easting														
Deep Piezometers																		
GW-978	2/27/2018	HSA/HQ/R	30656.68	38643.59	80.0	953.5	2.0	955.97	882.6	2.3	59.5 - 69.6	894.0	883.9	56.1 - 71.5	53.0 - 56.1	0.5 - 53.0	73.18	10.63
GW-980R[2]	3/5/2018	R	30379.90	38138.34	74.4	963.5	2.0	965.63	892.2	2.1	59.9 - 70.0	903.6	893.5	55.0 - 72.3	51.5 – 54.9	0.5 - 51.5	73.44	28.27
GW-982	3/5/2018	HSA/HQ/R	30317.82	38617.04	126.5	1015.6	2.0	1018.02	902.2	2.4	102.1 - 112.1	913.5	903.5	99.2 - 114.5	95.9 - 99.2	0.5 - 95.9	115.82	66.39
GW-986	3/1/2018	HSA/HQ/R	30130.30	38191.80	59.6	930.2	2.0	932.37	882.7	2.2	41.0 - 46.0	889.3	884.2	38.6 - 48.0	35.8 - 38.6	0.5 - 35.8	49.70	6.38
GW-988	3/1/2018	HSA/HQ/R	29952.47	38091.14	78.5	957.0	2.0	958.95	883.8	2.0	61.9 - 71.9	895.1	885.1	59.6 - 74.0	55.1 - 59.6	0.5 - 55.1	75.20	13.56
GW-992R[2]	3/3/2018	R	29698.29	38737.35	55.5	908.9	2.0	911.40	863.2	2.5	39.3 - 44.4	869.6	864.5	37.2 - 48.2	33.8 - 37.2	0.5 - 33.8	48.21	4.88
GW-994	3/1/2018	HSA/HQ/R	29644.99	38051.04	55.0	916.7	2.0	918.89	863.4	2.2	42.0 - 52.0	874.7	864.7	37.0 - 54.6	32.3 - 37.0	0.5 - 32.3	55.54	6.98
GW-998	2/27/2018	HSA/HQ/R	29021.82	37742.36	45.0	877.7	2.0	880.18	839.8	2.5	26.6 - 36.6	851.1	841.1	24.0 - 40.0	21.7 - 24.0	0.5 - 21.7	40.37	4.55
Shallow Piezometers																		
GW-979	2/27/2018	HSA/HQ/R	30656.61	38653.90	37.6	953.7	2.0	955.99	916.1	2.3	26.3 - 36.3	927.5	917.4	21.2 - 37.8	19.0 - 21.2	0.5 - 19.0	39.88	14.70
GW-981	3/6/2018	HSA/HQ	30396.70	38148.33	34.0	963.2	2.0	965.74	929.8	2.5	22.1 - 32.1	941.1	931.1	20.0 - 34.0	17.9 - 20.0	0.5 - 17.9	35.85	22.20
GW-983	3/6/2018	HSA/HQ	30325.62	38606.49	92.2	1015.6	2.0	1018.07	925.1	2.5	79.1 - 89.2	936.4	926.4	74.1 - 91.5	70.2 - 74.1	0.5 - 70.2	92.99	65.92
GW-987	3/3/2018	HSA/HQ	30138.34	38194.40	27.9	930.5	2.0	932.94	903.1	2.4	16.1 - 26.1	914.4	904.4	13.3 - 27.9	10.9 - 13.3	0.5 - 10.9	29.77	9.49
GW-989	3/6/2018	HSA/HQ	29950.44	38082.67	45.0	955.7	2.0	957.86	910.8	2.3	33.6 - 43.6	922.1	912.1	30.0 - 45.0	25.7 - 30.0	0.5 - 25.7	47.21	14.03
GW-993	3/3/2018	HSA/HQ/R	29690.50	38724.90	35.5	909.7	2.0	911.76	875.4	2.1	23.0 - 33.0	886.8	876.7	19.8 - 35.5	14.5 - 19.8	0.5 - 14.5	36.37	5.45
GW-995	3/3/2018	HSA/HQ	29646.82	38039.32	34.0	916.3	2.0	918.76	882.9	2.5	22.1 - 32.1	894.2	884.2	19.2 - 34.0	17.0 - 19.2	0.5 - 17.0	35.85	11.93
GW-999	3/5/2018	HSA/HQ	29025.01	37750.58	22.0	877.6	2.0	880.11	856.0	2.5	10.3 - 20.3	867.4	857.3	8.3 - 21.6	1.0 - 8.3	--	24.10	3.41

[1] HSA = Hollow Stem Augers; HQ = HQ Rock Core; and R = Rotary.
[2] Replacement borehole. Original borehole abandoned and sealed.
bgs = below ground surface.
EMDF = Environmental Management Disposal Facility.
ft = feet.
ID = identification.
in. = inches.
MSL = mean sea level.
TOC = top of casing.

This page intentionally left blank.

6.3 FINDINGS

Figures 6.2 and 6.3 provide geologic cross-sections constructed from the EMDF boreholes. The completed screen depths are also indicated along with water levels measured at the time of well completion and the first indication of groundwater encountered during drilling based on the drilling logs. These first indications of groundwater may not reflect the groundwater table, but indicate zones where groundwater can be readily released from the formations.

6.3.1 FLUTe™/Slug Test Results

FLUTe™ Tests

FLUTe™ testing was performed within the open, uncased boreholes in each of the deeper piezometer pairs (GW-978, GW-980R, GW-982, GW-986, GW-988, GW-992R, GW-994, and GW-998) to determine transmissivity (and/or hydraulic conductivity) values within the bedrock (Table 6.3). See Appendix D for a summary of FLUTe™ testing results. It should be noted that GW-982 was nearly impermeable below 54 ft below ground surface, and GW-980R had permeability too low to conduct profiling.

The liner descent-rate or velocity is a measure of T of the entire borehole. As the liner continues down the borehole and seals each permeable feature, changes in the liner velocity indicate the position of each feature and an estimate of T is provided using the Thiem equation (Wenzel and Fishel 1942) for steady radial flow. After the liner reaches the bottom of the hole, the liner acts as a seal preventing borehole cross-connection between transmissive features at different depths.

Slug Tests

Slug tests were performed in shallow piezometers GW-979, GW-981, GW-983, GW-987, GW-989, GW-993, GW-995, and GW-999 (Table 6.1). Slug-test data were analyzed using the Bouwer-Rice method (Bouwer and Rice 1976; Bouwer 1989) within the AQTESOLV software.[2] Water-level recovery data are plotted semi-logarithmically versus time. The slope of a line defined by the recovery data is then used, along with data on well geometry, to calculate hydraulic conductivity.

The results shown in Table 6.1 indicate that hydraulic conductivity ranged from 4.6E-05 to 5.0E-03 centimeters per second (cm/sec) in the shallow piezometers. The average/mean hydraulic conductivity determined for the two individual tests for each piezometer ranged from 5.5E-05 to 5.0E-03 cm/sec.

[2] AQTESOLV (AQuifer TEst SOLVer) is a software used for the design and analysis of aquifer tests (pumping tests, slug tests, constant-head tests, groundwater mounding, etc.) in confined, leaky, unconfined, and fractured aquifers.

This page intentionally left blank.




Fig. 6.2. North–south geologic cross-section of EMDF.




Fig. 6.3. East–west geologic cross-section of EMDF.

Table 6.3. FLUTe™ test result summary for the EMDF piezometers

Well ID	Depth to water (ft)	Borehole depth (ft bgs)	Casing depth (ft bgs)	Depth of FLUTe™ profile (ft bgs)	Flow rate per unit driving pressure (gal/min/ft)	Length of borehole remaining (ft)	Transmissivity of remaining borehole (cm^2/sec)	Average hydraulic conductivity for remaining borehole (cm/sec)	Total borehole transmissivity (cm^2/sec)
GW-978	10.75	82.1	27	76.85	0.01	5.24	0.02705	1.30E-04	0.16164
GW-980R	28.27	74.4	27	--	--	--	--	--	--
GW-982	52.38	125.3	50	53.74	0.00217	71.56	0.0045	2.06E-06	0.05181
GW-986	5.00	59.4	20	49.17	0.01538	10.25	0.01538	1.02E-04	0.09862
GW-988	13.9	79	36.5	75.37	0.02739	3.64	0.056714	5.12E-04	0.10648
GW-992R	1.5	54.83	31	51.12	0.02047	3.71	0.04239	3.75E-04	0.10757
GW-994	7.06	54.75	35	52.02	0.03347	2.73	0.,06932	8.34E-04	0.09845
GW-998	1.45	45.1	20	39.92	0.02745	5.16	0.05684	3.62E-04	0.19806

Note: Permeabilty of the GW-980R borehole was too low to adequately measure flow into the bedrock using the FLUTe™ technology.
bgs = below ground surface.
cm = centimeters.
EMDF = Environmental Managaement Disposal Facility.
FLUTe™ = Flexible Liner Underground Technologies, LLC.
ft = feet.
gal = gallons.
ID = identification.
min = minutes.
sec = seconds.
-- = not available/applicable.

6.3.2 Groundwater Monitoring Findings

Data collected for the piezometers is shown on Figs. 6.4 through 6.11. These graphs represent the water level, pH, and specific conductivity measured in the wells at 30-min intervals. The precipitation recorded at the the nearby Spallation Neutron Source site is also illustrated on the graphs. This precipitation gauge location was selected due to its closer proximity to the CBCV site than the gauge at the EMWMF.

In general, the EMDF wells show typical fluctuations in specifc conductivity and pH in response to precipitation events. However, of particular interest is the behavior at well GW-993 (Fig. 6.9). This well is the shallow well paired with GW-992R completed in the deeper bedrock. GW-993 monitors the alluvial groundwater in the D-10W valley. The curious behavior of the monitored parameters at GW-993 appears to indicate that the rising groundwater from bedrock into the shallow well has higher specific conductivity and higher pH that disappears when the shallow alluvial groundwater enters the screen during a precipitation event decline cycle. Thus, GW-993 appears to monitor exactly on the hydrogeochemical interface between bedrock and the unconsolidated alluvial zone groundwater.

Specific conductivity at the shallow piezometers at EMDF has ranged from 194 to 1266 µS/cm over the period from March to early May 2018. As would be expected, the bedrock wells showed less fluctuation in specific conductivity with a range of 299 to 892 µS/cm over the same period. The measured pH in shallow piezometers ranged from 6.45 to 8.97 from March to early May. With the exception of GW-978 (11.47) and GW-982 (10.78), the pH in the bedrock piezometers ranged from 6.74 to 7.95 over the period from March to early May 2018. The initial high pH measured in GW-978 appears to represent early effects from well construction, and since March 17, 2018, the pH at this piezometer has ranged from 7.9 to 8.5. The sudden increase in both pH and specific conductivity over approximately 10 days in late March and early April at GW-982 does not appear to be related to precipitation, but the initial increase does correspond to a field adjustment of the transducer. Since the second week of April the pH at GW-982 has ranged from 7.9 to 8.9.

In general, groundwater temperatures ranged from 14 to 15.5° C over the late March to early May period in the EMDF piezometers. Overall, temperature data show little fluctuation in response to precipitation events in the EMDF piezometers. This is especially true for the bedrock piezometers, but also for most of the shallow piezometers. Exceptions to this occurred in the shallow piezometers GW-993 and GW-999, which show obvious response to precipitation.

6.3.3 Groundwater Elevation Data

Groundwater elevations determined from depth-to-water measurements are used to: (1) estimate the groundwater surface elevations across the entire footprint of EMDF prior to construction, and (2) provide information to develop the engineering design.

Groundwater elevation data also were collected by using downhole monitors placed in each piezometer. Data were collected continuously and recorded every 30 min with downloads every two weeks. This TM includes data from the continuous monitoring of these 16 piezometers during the March/April time frame. The water level data for the eight EMDF well pairs that have been monitored during March and April 2018 are shown on Figs. 6.4 through 6.11. Monitoring of the EMDF water levels will continue for at least one year to ensure seasonal high-water levels are captured for evaluation in the design of the EMDF.

Water level elevations for the paired wells, and elevation of the ground surface at the well pair, are shown in Figs. 6.12 through 6.19. The water level data collected to date at EMDF show that, in general, there are significant downward gradients beneath the knoll (GW-980R/GW-981), little to no gradient between the shallow and deeper piezometers nearer the streams (GW-992R/GW-993), and slight upward gradients in

the southern part of the footprint (GW-.994/GW-995). Table 6.4 provides a summary of the vertical gradients observed at the EMDF well pairs.

Table 6.4. Vertical hydraulic gradients at EMDF, Spring 2018

Well pair	Vertical gradient direction, Spring 2018
GW-978/GW-979	Slight downward
GW-980R/GW-981	Downward
GW-982/GW-983	None
GW-986/GW-987	Downward
GW-988/GW-989	Downward
GW-992R/GW-993	None
GW-994/GW-995	Slight upward
GW-998/GW-999	Slight upward

EMDF = Environmental Management Disposal Facility.

Groundwater levels show responses to rainfall events in most shallow and deep piezometers beneath the knolls, indicating some recharge is occurring on the site.

6.3.4 Comparable Existing Piezometers

Quarterly groundwater elevation data are available for many of the EMWMF wells since 2002 or before, including recent wetter periods. Continuous groundwater elevation monitors were installed in March 2017 in EMWMF wells and, therefore, have more specific data to forecast responses to precipitation over the year. In addition, continuous groundwater elevation monitors were installed prior to completing and instrumenting the CBCV piezometers (Fig. 6.20). Data from these wells provide additional, comparable, wet season data to augment what was collected for the CBCV piezometers. Groundwater elevation data for an appropriate BCV well were matched to the groundwater elevation data for a given EMDF well to help predict the wet season data for that well to date, during this calendar year. The water level elevation data for an appropriate match in water level behavior were normalized to the EMDF well elevations and used to extrapolate the water level fluctuations back during February 2018 to represent the wet season fluctuations (see Figs. 6.21 through 6.36). The water level graphs with extrapolated data and comparison of the graphs of the selected representative well are presented in Appendix E.




Fig. 6.4. Time trend plot of groundwater elevation, specific conductivity, and pH with daily rainfall for well pair GW-978/GW-979.




Fig. 6.5. Time trend plot of groundwater elevation, specific conductivity, and pH with daily rainfall for well pair GW-980R/GW-981.




Fig. 6.6. Time trend plot of groundwater elevation, specific conductivity, and pH with daily rainfall for well pair GW-982/GW-983.




Fig. 6.7. Time trend plot of groundwater elevation, specific conductivity, and pH with daily rainfall for well pair GW-986/GW-987.




Fig. 6.8. Time trend plot of groundwater elevation, specific conductivity, and pH with daily rainfall for well pair GW-988/GW-989.




Fig. 6.9. Time trend plot of groundwater elevation, specific conductivity, and pH with daily rainfall for well pair GW-992R/GW-993.




Fig. 6.10. Time trend plot of groundwater elevation, specific conductivity, and pH with daily rainfall for well pair GW-994/GW-995.




Fig. 6.11. Time trend plot of groundwater elevation, specific conductivity, and pH with daily rainfall for well pair GW-998/GW-999.




Fig. 6.12. Water levels at well pair GW-978/GW-979.




Fig. 6.13. Water levels at well pair GW-980R/GW-981.




Fig. 6.14. Water levels at well pair GW-982/GW-983.




Fig. 6.15. Water levels at well pair GW-986/GW-987.




Fig. 6.16. Water levels at well pair GW-988/GW-989.




Fig. 6.17. Water levels at well pair GW-992R/GW-993.




Fig. 6.18. Water levels at well pair GW-994/GW-995.



Fig. 6.19. Water levels at well pair GW-998/GW-999.

This page intentionally left blank.




Fig. 6.20. Bear Creek Valley well locations.

This page intentionally left blank.




Fig. 6.21. Extrapolated water levels for GW-978.




Fig. 6.22. Extrapolated water levels for GW-979.




Fig. 6.23. Extrapolated water levels for GW-980R.




Fig. 6.24. Extrapolated water levels for GW-981.




Fig. 6.25. Extrapolated water levels for GW-982.




Fig. 6.26. Extrapolated water levels for GW-983.




Fig. 6.27. Extrapolated water levels for GW-986.




Fig. 6.28. Extrapolated water levels for GW-987.




Fig. 6.29. Extrapolated water levels for GW-988.




Fig. 6.30. Extrapolated water levels for GW-989.




Fig. 6.31. Extrapolated water levels for GW-992R.




Fig. 6.32. Extrapolated water levels for GW-993.




Fig. 6.33. Extrapolated water levels for GW-994.




Fig. 6.34. Extrapolated water levels for GW-995.




Fig. 6.35. Extrapolated water levels for GW-998.




Fig. 6.36. Extrapolated water levels for GW-999.

7. GEOTECHNICAL TEST RESULTS

7.1 APPROACH

The laboratory testing program was directed toward determining the general soil classification, physical properties, shear strength, and compressibility of the soil pertinent to the engineering analysis and design of the EMDF. Limited permeability testing was also conducted on both relatively undisturbed samples (tube samples) and from recompacted bulk samples taken from auger cuttings. Samples tested in the laboratory included those from split spoons, thin-walled tube samples, rock core, and bulk samples of auger cuttings. All laboratory testing was performed in accordance with applicable American Society for Testing and Materials Standards as detailed in Table 7.1. In total, 18 thin-walled (Shelby tube) samples, 69 split-spoon soil samples, 10 bulk soil samples, and 10 rock core samples were shipped to laboratories for testing.

7.2 SUMMARY OF KEY RESULTS

Table 7.1 provides a summary of the key index test results obtained from the split-spoon sampling and from bulk samples taken from borehole cuttings. Appendix F provides the complete laboratory reports for all geotechnical laboratory testing conducted on the split-spoon samples, the thin-walled tube samples, and rock cores. The EMDF design will provide more information/detail on interpretation of the geotechnical tests.

Table 7.1. Summary of EMDF split-spoon and bulk sample laboratory index test results

Boring No.	Sample No.	Moisture content (%)	Liquid limit (%)	Plastic limit (%)	Plasticity index	% Gravel	% Sand	% Fines	USCS group symbol[1]	Dry unit weight (lbf/ft^3)	Water content (%)
	SS-1	21.8									
	SS-3	19.3									
	SS-4	24	45	21	24	0.5	34.2	65.3	CL		
GW-978	SS-5	21									
	SS-8	11.5									
	SS-9	11.7									
	SS-10	11.1									
GW-979	BS-S01									114.8[2]	13.5[2]
	SS-2	13.8				45	32	23	SM		
	SS-3	15.1	N/A	NP	NP						
	SS-4	15									
	SS-6	12.6									
GW-980R	SS-8	14.5									
	SS-9	10.2									
	SS-10	4.3									
	SS-12	11.7									
	SS-13	12.3									
GW-981	BS-S02									120.7[2]	13.9[2]
	SS-2	11									
	SS-3	13.1									
	SS-4	12.5									
	SS-5	12.3	33	23	10	2.2	47	50.8	CL		
	SS-8	13.9				4.8	65.9	29.3			
GW-982	SS-10	10.8									
	SS-13	11.9									
	SS-16	4.7									
	SS-18	8.9									
	SS-21	7	28	19	9	14.7	56.8	28.5	SC		
	SS-23	5.5									

Table 7.1. Summary of EMDF split-spoon and bulk sample laboratory index test results (cont.)

Boring No.	Sample No.	Moisture content (%)	Liquid limit (%)	Plastic limit (%)	Plasticity index	% Gravel	% Sand	% Fines	USCS group symbol[1]	Dry unit weight (lbf/ft^3)	Water content (%)
GW-983	BS-S03					4	37	59		120.2[2] 112.2[3]	11.3[2] 11.7[3]
GW-986	SS-2	20.4	37	18	19	7.8	52.8	39.4	SC		
	SS-3	21.1									
	SS-4	14.6									
	SS-6	8.4									
	SS-7	8.7									
	SS-9	4.3									
GW-988	SS-2	34.6									
	SS-3	25.1									
	SS-4	33.6	41	27	14	0.6	42	57.4	ML		
	SS-6	29.8									
	SS-8	26.2									
	SS-11	21.5									
	SS-13	16									
	SS-16	9.9	32	19	13	3.3	66.9	29.8	SC		
	SS-18	9.9									
GW-989	BS-S04					1.4	22.9	75.7		107.8[2]	12.5[2]
GW-992R	SS-1	29.3	38	20	18	7	36	57	CL		
	SS-2	23.9									
	SS-4	37.1									
	SS-5	13.4									
	SS-7	21.3									
	SS-8	16.2									
	SS-10	15.5				1	62	37			
	SS-12	17.6									
	SS-13	10.8									

Table 7.1. Summary of EMDF split-spoon and bulk sample laboratory index test results (cont.)

Boring No.	Sample No.	Moisture content (%)	Liquid limit (%)	Plastic limit (%)	Plasticity index	% Gravel	% Sand	% Fines	USCS group symbol[1]	Dry unit weight (lbf/ft^3)	Water content (%)
	SS-2	22.8	47	18	29						
	SS-3	23.6									
	SS-4	21.7				0.6	9.4	90	CL		
	SS-6	39.2									
	SS-8	24.4									
GW-994	SS-10	16.6									
	SS-12	18.7									
	SS-14	13.6				9.2	56.9	33.9			
	SS-15	13.3									
	SS-17	15.9									
	SS-18	14.6									
	SS-1	18.9	38	22	16						
	SS-2	22									
	SS-3	27.4									
GW-998	SS-4	18.6				4.3	58.4	37.3			
	SS-5	26									
	SS-7	23.8									
	SS-9	15.4									
GW-999	BS-S06					3.5	35.4	61.1		110.6[2]	12.1[2]

[1] USCS symbol based only on laboratory results. See the borehole logs in Appendix B for complete descriptions.
[2] Determined by method ASTM D 1557.
[3] Determined by method ASTM D 698.
Soil Classification: CL = lean clay; ML = silt; SC = clayey sand; and SM = silty sand.
ASTM = American Society for Testing and Materials.
BS = bulk sample.
EMDF = Environmental Management Disposal Facility.
N/A = not applicable.
NP = non-plastic.
USCS = Unified Soil Classification System.

8. VALIDATION OF KEY ASSUMPTIONS

Key assumptions developed for the EMDF, and the validation of those assumptions, are as follows:

- Geology is typical of BCV with steeply dipping, fractured bedrock, and there are no major karstic features in the Maryville, Nolichucky, or Rogersville formations underlying the CBCV site.
  - Core drilling for the EMDF piezometers confirmed the presence of typical BCV geologic structures in the subsurface, including steeply dipping beds; interbedded shales, siltstones, and some limestone; and the presence of joints and fractures in bedrock.
- The contact with the Maynardville Limestone is located south of the currently proposed EMDF footprint.
  - The location of the Maynardville was confirmed in field surveys that located the Maynardville/Nolichucky geologic contact approximately 50 ft further south of the proposed EMDF than previously mapped. The EMDF footprint and buffer zone are, therefore, north of this formation.
- Precipitation primarily runs off as surface water and shallow groundwater in the stormflow zone.
  - Site walkovers confirmed the presence of abundant macropores—such as result from decayed trees—and an active stormflow zone in the area of the EMDF. Flow through macropores and the resurgence of shallow underflow were observed to occur.
  - Flumes record higher stream flows following precipitation, indicating that most precipitation is running off as stormwater. Flow rates rapidly decrease when precipitation is over, indicating a smaller influence from groundwater.
  - Walkovers confirmed the location of existing seeps and did not locate additional seeps in the EMDF area.
- Groundwater elevations are typical of other BCV wells in similar settings.
  - Groundwater levels measured in both deep and shallow piezometers during the Phase 1 characterization confirmed that prior to landfill construction, groundwater discharges as seeps in the valleys and drainages. Mirroring topography, groundwater is higher beneath knolls/ridges. However, the groundwater elevation beneath the largest knoll in the site is deeper below ground surface than predicted in the RI/FS. Groundwater levels show responses to rainfall events and downward gradients beneath the knoll, indicating minor recharge is occurring on the site.

Results of the Phase 1 site characterization validate the key assumptions regarding the hydrogeologic setting (groundwater and surface water conditions) at the site. The results confirm the acceptability of the CBCV site for a new, low-level waste landfill and support final site selection.

This page intentionally left blank.

9. REFERENCES

Bouwer, H., and Rice, R. C. 1976. "A slug test method for determining hydraulic conductivity of unconfined aquifers with completely or partially penetrating wells," *Water Resources Research* **12**(3): 423–428.

Bouwer, H. 1989. "The Bouwer and Rice Slug Test — An Update," *Groundwater* **27**(3): 304–309.

Clapp, R. B. 1997. *Estimating groundwater recharge to the shale aquifers in Eastern Tennessee using a topography-based, water-budget model* (in) Extended Abstracts from Seventh Tennessee Water Resources Symposium, Nashville, Tennessee, February 24−26, pp. 151–153.

DOE (U.S. Department of Energy) 2014. *Groundwater Strategy for the U.S. Department of Energy, Oak Ridge Reservation, Oak Ridge, Tennessee*, DOE/OR/01-2628/V1&D2, U.S. Department of Energy, Office of Environmental Management, Oak Ridge, TN.

DOE 2016. *2016 Remediation Effectiveness Report for the U.S. Department of Energy Oak Ridge Reservation, Oak Ridge, Tennessee*, DOE/OR/01-2707&D2, U.S. Department of Energy, Office of Environmental Management, Oak Ridge, TN.

DOE 2017. *Remedial Investigation/Feasibility Study for the Comprehensive Environmental Response, Compensation, and Liability Act Oak Ridge Reservation Waste Disposal, Oak Ridge, Tennessee*, DOE/OR/01-2535&D5, U.S. Department of Energy, Office of Environmental Management, Oak Ridge, TN.

DOE 2018. *Phase 1 Field Sampling Plan for the Proposed Environmental Management Disposal Facility for Comprehensive Environmental Response, Compensation, and Liability Act Oak Ridge Reservation Waste Disposal, Oak Ridge, Tennessee*, DOE/OR/01-2739&D2, U.S. Department of Energy, Office of Environmental Management, Oak Ridge, TN.

ORNL (Oak Ridge National Laboratory) 1989. *Geology of the West Bear Creek Site*, ORNL/TM-10887, R. R. Lee and R. H. Ketelle, Oak Ridge National Laboratory, Oak Ridge, TN, January.

ORNL 2006. *Oak Ridge Reservation Physical Characteristics and Natural Resources*, ORNL/TM-2006/110, P. D. Parr and J. F. Hughes, Oak Ridge National Laboratory, Oak Ridge, TN, September.


Wenzel, L. K., and Fishel, V. C. 1942. *Methods for determining permeability of water-bearing materials, with special reference to discharging-well methods*, U.S. Department of the Interior, Geological Survey, Water-Supply Paper 887, U.S. Govt. Printing Office, Washington, D.C.


This page intentionally left blank.


APPENDIX A

SURFACE WATER MEASUREMENTS

This page intentionally left blank.


NT11-20 | DATE | T | pH | CON | 01/18 | 6.69 | 6.7 | 28
NT11-HW STATION | DATE | T | pH | CON | 01/18 | 6.72 | 6.4 | 28
NT11-21 | DATE | T | pH | CON | 01/18 | 6.79 | 6.5 | 29
NT11-23 | DATE | T | pH | CON | 01/18 | 7.03 | 6.3 | 29
NT11-19 | DATE | T | pH | CON | 01/18 | 6.63 | 6.8 | 28
NT11-24 | DATE | T | pH | CON | 01/18 | 7.23 | 6.3 | 29
NT11-18 FORKS | DATE | T | pH | CON | 01/18 | 6.39 | 6.6 | 32
NT11-22 | DATE | T | pH | CON | 01/18 | 6.91 | 6.2 | 30
NT11-18b | DATE | T | pH | CON | 01/18 | 5.83 | 6.4 | 65
NT11-EF2 | DATE | T | pH | CON | 01/18 | 5.08 | 6.3 | 35
NT11-18a | DATE | T | pH | CON | 01/18 | 6.48 | 6.6 | 29
NT11-EF1 | DATE | T | pH | CON | 01/18 | 5.85 | 6.6 | 67
NT11-17 | DATE | T | pH | CON | 01/18 | 6.21 | 6.7 | 34
D11E-1 | DATE | T | pH | CON | 01/18 | 8.86 | 6.3 | 68
NT11-16b | DATE | T | pH | CON | 01/18 | 5.97 | 6.8 | 35
NT11-16 | DATE | T | pH | CON | 01/18 | -- | -- | --
NT11-16a | DATE | T | pH | CON | 01/18 | 6.36 | 6.8 | 40
NT11-15 | DATE | T | pH | CON | 01/18 | 6.23 | 6.9 | 40
NT11-SEEP 2 | DATE | T | pH | CON | 01/18 | -- | -- | --
NT11-14 | DATE | T | pH | CON | 01/18 | 6.11 | 6.9 | 42
NT11-13 | DATE | T | pH | CON | 01/18 | 5.98 | 7.0 | 41
NT11-12 | DATE | T | pH | CON | 01/18 | 5.87 | 7.1 | 43
NT11-10 | DATE | T | pH | CON | 01/18 | 5.60 | 7.2 | 54
NT11-11 | DATE | T | pH | CON | 01/18 | 5.64 | 7.2 | 52
NT11-9 | DATE | T | pH | CON | 01/18 | 5.54 | 7.2 | 56
NT11-SEEP 1 | DATE | T | pH | CON | 01/18 | -- | -- | --
NT11-2 | DATE | T | pH | CON | 01/18 | 5.24 | 7.0 | 70
NT11-8 | DATE | T | pH | CON | 01/18 | 5.43 | 7.1 | 60
NT11-PF-1 | DATE | T | pH | CON | 01/18 | 5.24 | 7.0 | 70
NT11-7 | DATE | T | pH | CON | 01/18 | 5.37 | 7.1 | 60
NT11-3 | DATE | T | pH | CON | 01/18 | 5.21 | 7.0 | 67
NT11-6 | DATE | T | pH | CON | 01/18 | 5.30 | 7.0 | 60
NT11-4 | DATE | T | pH | CON | 01/18 | 5.20 | 7.0 | 64
NT11-5 | DATE | T | pH | CON | 01/18 | 5.25 | 7.0 | 62
D10W-4 | DATE | T | pH | CON | 01/18 | 6.93 | 6.2 | 46
D10W-5 | DATE | T | pH | CON | 01/18 | 6.75 | 5.9 | 44
D10W-7 | DATE | T | pH | CON | 01/18 | 6.73 | 6.2 | 45
D10W-8 | DATE | T | pH | CON | 01/18 | 6.58 | 6.3 | 45
D10W-9 | DATE | T | pH | CON | 01/18 | 6.59 | 6.3 | 59
D10W-10 | DATE | T | pH | CON | 01/18 | 6.56 | 6.5 | 49
D10W-11 | DATE | T | pH | CON | 01/18 | 6.58 | 6.5 | 51
D10W-12 | DATE | T | pH | CON | 01/18 | 6.61 | 6.6 | 52
D10W-13 | DATE | T | pH | CON | 01/18 | 6.45 | 6.7 | 55
D10W-14 | DATE | T | pH | CON | 01/18 | 6.31 | 6.8 | 63
D10W-15 | DATE | T | pH | CON | 01/18 | 5.14 | 6.9 | 86
D10W-16 | DATE | T | pH | CON | 01/18 | 5.60 | 7.5 | 100
D10W-17 | DATE | T | pH | CON | 01/18 | 5.52 | 7.4 | 100
D10W-18 | DATE | T | pH | CON | 01/18 | 5.51 | 7.3 | 100
D10W-19 | DATE | T | pH | CON | 01/18 | 5.52 | 7.3 | 101
D10W-20 | DATE | T | pH | CON | 01/18 | 5.50 | 7.3 | 103
D10W-21 | DATE | T | pH | CON | 01/18 | 5.50 | 7.3 | 101
D10W-22 | DATE | T | pH | CON | 01/18 | 5.53 | 7.4 | 102
D10W-1 | DATE | T | pH | CON | 01/18 | 7.13 | 6.3 | 44
D10W-2 | DATE | T | pH | CON | 01/18 | 7.10 | 6.3 | 48
D10W-3 | DATE | T | pH | CON | 01/18 | 6.94 | 6.2 | 44
D10W-SEEP 1 | DATE | T | pH | CON | 01/18 | 6.53 | 5.7 | 27
D10W-6 | DATE | T | pH | CON | 01/18 | 6.81 | 6.0 | 43
NT10-15 | DATE | T | pH | CON | 01/18 | 7.61 | 7.0 | 36
NT10-14 | DATE | T | pH | CON | 01/18 | 7.54 | 7.1 | 38
NT10-13 | DATE | T | pH | CON | 01/18 | 7.56 | 7.2 | 37
NT10-12 | DATE | T | pH | CON | 01/18 | 7.01 | 7.3 | 39
NT10-11 | DATE | T | pH | CON | 01/18 | 7.01 | 7.3 | 39
NT10-10 | DATE | T | pH | CON | 01/18 | 6.43 | 7.2 | 50
NT10-9 | DATE | T | pH | CON | 01/18 | 6.42 | 7.0 | 56
NT10-8 | DATE | T | pH | CON | 01/18 | 6.26 | 7.4 | 56
NT10-7 | DATE | T | pH | CON | 01/18 | 6.43 | 7.3 | 66
NT10-5 | DATE | T | pH | CON | 01/18 | 6.26 | 7.3 | 76
NT10-6 | DATE | T | pH | CON | 01/18 | 6.33 | 7.3 | 70
NT10-3 | DATE | T | pH | CON | 01/18 | 6.1 | 7.4 | 81
NT10-4 | DATE | T | pH | CON | 01/18 | 6.17 | 7.3 | 81
NT10-1 | DATE | T | pH | CON | 01/18 | 6.1 | 7.5 | 83
NT10-2 | DATE | T | pH | CON | 01/18 | 6.2 | 7.5 | 81
HAUL ROAD
BEAR CREEK ROAD
BEAR CREEK
46 CONTACT
51 CONTACT
Cn
Cmn
960
940
920
900
880
980
LEGEND:
SURFACE CONTOUR 100' INTERVAL
SURFACE CONTOUR 20' INTERVAL
CREEK AND TRIBUTARIES
PAVED ROADS
SURFACE WATER SAMPLE LOCATION
MAYNARDVILLE/NOLICHUCKY CONTACT
T..... TEMPERATURE (DEGREES CENTIGRADE)
pH.....POTENTIAL OF HYDROGEN
CON.....CONDUCTIVITY (μmho/cm)
GEOLOGIC CONTACT
Cn .....NOLICHUCKY SHALE
Cmn.....MAYNARDVILLE LIMESTONE
NOTES:
1. SAMPLES WERE TAKEN ON JANUARY 30, 2018.
O.R. ADMIN. GRID
34°13'±
TRUE NORTH
0 100 200 300
SCALE: 1" = 300'
EMDF SITE
SURFACE WATER
MEASUREMENTS
JANUARY 30, 2018
UCOR
URS | CH2M
Oak Ridge LLC
July 31, 2018
K:\13013\DWGS\R98_EMDF_DB_1-30-18
A-3


NT11-20
DATE T pH CON
02/18 10.93 6.48 24
NT11-HW STATION
DATE T pH CON
02/18 10.97 6.36 24
NT11-21
DATE T pH CON
02/18 11.01 6.38 26
NT11-23
DATE T pH CON
02/18 11.04 6.34 26
NT11-19
DATE T pH CON
02/18 10.87 6.65 24
NT11-24
DATE T pH CON
02/18 11.15 5.97 25
NT11-18 FORKS
DATE T pH CON
02/18 10.73 6.75 27
NT11-22
DATE T pH CON
02/18 11.04 6.26 26
NT11-18b
DATE T pH CON
02/18 10.03 6.79 54
NT11-EF2
DATE T pH CON
02/18 9.37 6.60 35
NT11-18a
DATE T pH CON
02/18 10.80 6.74 24
NT11-EF1
DATE T pH CON
02/18 9.57 6.96 45
NT11-17
DATE T pH CON
02/18 10.65 6.88 27
D11E-1
DATE T pH CON
02/18 10.75 6.78 39
NT11-16b
DATE T pH CON
02/18 10.57 7.04 27
NT11-16
DATE T pH CON
02/18 – – –
NT11-16a
DATE T pH CON
02/18 10.62 7.02 35
NT11-15
DATE T pH CON
02/18 10.57 7.07 35
NT11-SEEP 2
DATE T pH CON
02/18 – – –
NT11-14
DATE T pH CON
02/18 10.51 7.18 36
NT11-13
DATE T pH CON
02/18 10.52 7.27 36
NT11-12
DATE T pH CON
02/18 10.38 7.44 38
NT11-10
DATE T pH CON
02/18 10.12 7.52 49
NT11-11
DATE T pH CON
02/18 10.15 7.60 47
NT11-9
DATE T pH CON
02/18 10.08 7.5 50
NT11-SEEP 1
DATE T pH CON
02/18 – – –
NT11-2
DATE T pH CON
02/18 9.70 7.26 58
NT11-8
DATE T pH CON
02/18 9.97 7.51 53
NT11-PF-1
DATE T pH CON
02/18 9.70 7.16 59
NT11-7
DATE T pH CON
02/18 9.94 7.59 53
NT11-3
DATE T pH CON
02/18 9.75 7.25 58
NT11-6
DATE T pH CON
02/18 9.91 7.48 53
NT11-4
DATE T pH CON
02/18 9.77 7.24 58
NT11-5
DATE T pH CON
02/18 9.81 7.37 56
D10W-4
DATE T pH CON
02/18 11.20 5.99 43
D10W-5
DATE T pH CON
02/18 11.06 5.98 37
D10W-7
DATE T pH CON
02/18 11.02 5.99 37
D10W-8
DATE T pH CON
02/18 11.00 5.99 37
D10W-9
DATE T pH CON
02/18 11.02 6.02 38
D10W-10
DATE T pH CON
02/18 11.03 6.07 40
D10W-11
DATE T pH CON
02/18 11.09 6.20 42
D10W-12
DATE T pH CON
02/18 11.16 6.23 42
D10W-13
DATE T pH CON
02/18 10.99 6.44 50
D10W-14
DATE T pH CON
02/18 11.00 6.53 55
D10W-15
DATE T pH CON
02/18 10.39 7.28 66
D10W-16
DATE T pH CON
02/18 10.24 7.12 81
D10W-17
DATE T pH CON
02/18 10.21 7.09 82
D10W-18
DATE T pH CON
02/18 10.18 7.00 84
D10W-19
DATE T pH CON
02/18 10.18 7.02 87
D10W-20
DATE T pH CON
02/18 10.22 7.00 90
D10W-21
DATE T pH CON
02/18 10.27 7.05 90
D10W-22
DATE T pH CON
02/18 10.27 7.09 91
D10W-1
DATE T pH CON
02/18 11.33 6.17 39
D10W-2
DATE T pH CON
02/18 11.39 6.15 48
D10W-3
DATE T pH CON
02/18 11.19 6.09 42
D10W-SEEP 1
DATE T pH CON
02/18 10.87 6.00 27
D10W-6
DATE T pH CON
02/18 11.04 6.03 37
NT10-15
DATE T pH CON
02/18 11.15 6.39 28
NT10-14
DATE T pH CON
02/18 11.09 6.62 28
NT10-13
DATE T pH CON
02/18 11.14 6.67 28
NT10-12
DATE T pH CON
02/18 11.71 6.67 32
NT10-11
DATE T pH CON
02/18 11.30 6.68 38
NT10-10
DATE T pH CON
02/18 11.22 6.61 40
NT10-9
DATE T pH CON
02/18 11.27 6.65 44
NT10-8
DATE T pH CON
02/18 11.16 6.80 46
NT10-7
DATE T pH CON
02/18 11.15 6.84 54
NT10-5
DATE T pH CON
02/18 11.22 6.94 60
NT10-6
DATE T pH CON
02/18 11.19 6.83 55
NT10-3
DATE T pH CON
02/18 11.24 7.03 64
NT10-4
DATE T pH CON
02/18 11.16 6.87 61
NT10-1
DATE T pH CON
02/18 11.32 7.09 64
NT10-2
DATE T pH CON
02/18 11.30 7.07 64
HAUL ROAD
BEAR CREEK ROAD
BEAR CREEK
46 CONTACT
51 CONTACT
Cn
Cmn
960
940
920
900
880
980
A-4
LEGEND:
SURFACE CONTOUR 100' INTERVAL
SURFACE CONTOUR 20' INTERVAL
CREEK AND TRIBUTARIES
PAVED ROADS
SURFACE WATER SAMPLE LOCATION
MAYNARDVILLE/NOLICHUCKY CONTACT
T..... TEMPERATURE (DEGREES CENTIGRADE)
pH.....POTENTIAL OF HYDROGEN
CON.....CONDUCTIVITY (μmho/cm)
GEOLOGIC CONTACT
Cn .....NOLICHUCKY SHALE
Cmn.....MAYNARDVILLE LIMESTONE
NOTES:
1. SAMPLES WERE TAKEN ON FEBRUARY 27, 2018.
O.R. ADMIN. GRID
34°13'±
TRUE NORTH
0 100 200 300
SCALE: 1" = 300'
EMDF SITE
SURFACE WATER
MEASUREMENTS
FEBRUARY 27, 2018
UCOR
URS | CH2M
Oak Ridge LLC
July 31, 2018
K:\13013\DWGS\R98_EMDF_DB_2-27-18



LEGEND:

- SURFACE CONTOUR 100' INTERVAL
- SURFACE CONTOUR 20' INTERVAL
- CREEK AND TRIBUTARIES
- PAVED ROADS
- SURFACE WATER SAMPLE LOCATION
- MAYNARDVILLE/NOLICHUCKY CONTACT
- T. TEMPERATURE (DEGREES CENTIGRADE)
- pH POTENTIAL OF HYDROGEN
- CON CONDUCTIVITY (μmho/cm)
- GEOLOGIC CONTACT
- Cn NOLICHUCKY SHALE
- Cmn MAYNARDVILLE LIMESTONE


NOTES:

1. SAMPLES WERE TAKEN ON MAY 1, 2018.

EMDF SITE
SURFACE WATER
MEASUREMENTS
MAY 1, 2018

UCOR
URS | CH2M
Oak Ridge LLC

6/13/2018
K:\13013\DWGS\R98_EMDF_DB_5-1-18


NT11-20 DATE T pH CON 06-04-18 16.8 7.0 48
NT11-HW STATION DATE T pH CON 06-04-18 16.7 6.8 47
NT11-21 DATE T pH CON 06-04-18 16.6 6.8 48
NT11-23 DATE T pH CON 06-04-18 16.6 6.8 49
NT11-19 DATE T pH CON 06-04-18 16.8 7.0 53
NT11-24 DATE T pH CON 06-04-18 16.5 6.7 46
NT11-18 FORKS DATE T pH CON 06-04-18 16.7 7.3 59
NT11-22 DATE T pH CON 06-04-18 16.6 6.8 49
NT11-18b DATE T pH CON 06-04-18 16.8 7.1 125
NT11-EF2 DATE T pH CON 06-04-18 17.7 6.8 75
NT11-18a DATE T pH CON 06-04-18 16.7 7.2 49
NT11-EF1 DATE T pH CON 06-04-18 17.3 7.2 115
NT11-17 DATE T pH CON 06-04-18 16.7 7.3 64
D11E-1 DATE T pH CON 06-04-18 16.0 6.5 69
NT11-16b DATE T pH CON 06-04-18 16.6 7.2 64
NT11-16 DATE T pH CON 06-04-18 – – –
NT11-16a DATE T pH CON 06-04-18 16.5 7.1 67
NT11-15 DATE T pH CON 06-04-18 16.5 7.3 68
NT11-SEEP 2 DATE T pH CON 06-04-18 – – –
NT11-14 DATE T pH CON 06-04-18 16.5 7.4 71
NT11-13 DATE T pH CON 06-04-18 16.4 7.7 71
NT11-12 DATE T pH CON 06-04-18 16.6 7.7 80
NT11-10 DATE T pH CON 06-04-18 16.6 7.8 109
NT11-11 DATE T pH CON 06-04-18 16.6 7.8 98
NT11-9 DATE T pH CON 06-04-18 16.6 7.8 111
NT11-SEEP 1 DATE T pH CON 06-04-18 – – –
NT11-2 DATE T pH CON 06-04-18 16.2 7.1 134
NT11-8 DATE T pH CON 06-04-18 16.6 7.7 113
NT11-PF-1 DATE T pH CON 06-04-18 16.1 7.2 135
NT11-7 DATE T pH CON 06-04-18 16.5 7.7 113
NT11-6 DATE T pH CON 06-04-18 16.5 7.6 113
NT11-5 DATE T pH CON 06-04-18 16.5 7.4 117
NT11-4 DATE T pH CON 06-04-18 16.4 7.2 133
NT11-3 DATE T pH CON 06-04-18 16.3 7.1 128
D10W-4 DATE T pH CON 06-04-18 17.4 6.4 64
D10W-5 DATE T pH CON 06-04-18 17.5 6.3 69
D10W-7 DATE T pH CON 06-04-18 17.3 6.5 80
D10W-8 DATE T pH CON 06-04-18 17.2 6.7 82
D10W-9 DATE T pH CON 06-04-18 17.2 6.7 86
D10W-10 DATE T pH CON 06-04-18 17.2 6.8 99
D10W-11 DATE T pH CON 06-04-18 17.2 6.9 103
D10W-12 DATE T pH CON 06-04-18 17.3 7.0 102
D10W-13 DATE T pH CON 06-04-18 17.5 7.4 139
D10W-14 DATE T pH CON 06-04-18 17.4 7.7 140
D10W-15 DATE T pH CON 06-04-18 21.3 7.6 175
D10W-16 DATE T pH CON 06-04-18 19.6 7.6 241
D10W-17 DATE T pH CON 06-04-18 19.7 7.5 224
D10W-18 DATE T pH CON 06-04-18 19.7 7.5 223
D10W-19 DATE T pH CON 06-04-18 19.6 7.6 223
D10W-20 DATE T pH CON 06-04-18 19.5 7.6 223
D10W-21 DATE T pH CON 06-04-18 19.8 7.7 225
D10W-22 DATE T pH CON 06-04-18 – – –
D10W-1 DATE T pH CON 06-04-18 17.4 6.2 60
D10W-2 DATE T pH CON 06-04-18 17.4 6.4 68
D10W-3 DATE T pH CON 06-04-18 17.4 6.3 62
D10W-SEEP 1 DATE T pH CON 06-04-18 – – –
D10W-6 DATE T pH CON 06-04-18 17.4 6.5 73
NT10-15 DATE T pH CON 06-04-18 17.0 7.5 73
NT10-14 DATE T pH CON 06-04-18 17.1 7.6 69
NT10-13 DATE T pH CON 06-04-18 17.3 7.5 71
NT10-12 DATE T pH CON 06-04-18 17.8 7.3 92
NT10-11 DATE T pH CON 06-04-18 17.7 7.6 105
NT10-10 DATE T pH CON 06-04-18 17.6 7.4 109
NT10-9 DATE T pH CON 06-04-18 17.5 7.3 116
NT10-8 DATE T pH CON 06-04-18 17.4 7.3 121
NT10-7 DATE T pH CON 06-04-18 17.4 7.4 143
NT10-5 DATE T pH CON 06-04-18 17.4 7.3 153
NT10-6 DATE T pH CON 06-04-18 17.4 7.3 148
NT10-3 DATE T pH CON 06-04-18 17.4 7.4 157
NT10-4 DATE T pH CON 06-04-18 17.3 7.3 156
NT10-1 DATE T pH CON 06-04-18 17.6 7.5 159
NT10-2 DATE T pH CON 06-04-18 17.5 7.4 158
HAUL ROAD
BEAR CREEK ROAD
BEAR CREEK
Cn
Cmn
46 CONTACT
51 CONTACT
960
940
920
900
880
980
LEGEND:
SURFACE CONTOUR 100' INTERVAL
SURFACE CONTOUR 20' INTERVAL
CREEK AND TRIBUTARIES
PAVED ROADS
SURFACE WATER SAMPLE LOCATION
MAYNARDVILLE/NOLICHUCKY CONTACT
T..... TEMPERATURE (DEGREES CENTIGRADE)
pH..... POTENTIAL OF HYDROGEN
CON..... CONDUCTIVITY (μmho/cm)
GEOLOGIC CONTACT
Cn ..... NOLICHUCKY SHALE
Cmn..... MAYNARDVILLE LIMESTONE
NOTES:
1. SAMPLES WERE TAKEN ON JUNE 4, 2018.
O.R. ADMIN. GRID
34°13'±
TRUE NORTH
0 100 200 300
SCALE: 1" = 300'
EMDF SITE
SURFACE WATER
MEASUREMENTS
JUNE 4, 2018
UCOR
URS | CH2M
Oak Ridge LLC
6/13/2018
K:\13013\DWGS\R98_EMDF_DB_6-4-18
A-6

APPENDIX B

BORING LOGS

This page intentionally left blank.

Eagon & Associates, Inc.

BOREHOLE LOG

Site Name and Location: **EMDF Characterization Project Oak Ridge, TN**	Drilling Methods: 2 1/4" HSA, HQ3 Core w/water, 10" hammer bit w/air, 5 7/8" tricone bit w/water/air.				Boring Number: GW-978
Drilling Firm: *Tri-State Drilling*	DATE	TIME	DEPTH DRILLED (ft)	WATER LEVEL (ft)	
Driller / Rig: *Fred Reynolds/Mobile 42C*	2/12/18	0910	18.3	9.81	*Page 1 of 4*
Logged by: *Ryan Hansel*	Sampling Methods: ST = Shelby Tube; WS = Waxed Sample; SP = Sand Pump; GP or DP = Direct Push; CT = Cuttings; SS = Split Spoon; CS = Continuous Sampler; C = Coring; NS = Not Sampled; B = Bailer				Start: *Time 0849, Date 2/10/18*
Coordinates: *30656.68N 38643.59E*					Finish: *Time 1658, Date 2/18/18*
Surface Elevation: *953.5 ft/MSL*					
Surface Conditions / Weather: *Gravel road base, wet / 45°F, Cloudy, calm*					
Remarks:					

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
1	NS			ROAD BASE.		Ran 2 1/4" HSA (7" OD) w/center plug while augering. Continuous 2" OD, 2' drive split spoons, 140 lb hydraulic hammer. HQ3 Core (3 7/8" OD) w/water.	
2	SS-1	1.0' 66.7%	2 2 3	Yellowish brown to dark yellowish brown (10YR 5/6 - 4/6) CLAYEY SILT. Trace fine grained sand. Trace angular shale clasts, 1" - 1/2" diameter. Medium to high plasticity. Cohesive. Mottled appearance. Stiff to very stiff. High dry strength. No dilatancy. Weathering present with iron oxide and manganese oxide on surfaces of shale clasts. No reaction with HCl. Moist. RESIDUAL SOIL.		SS-1 Lab results: Moisture Content (MC) 21.8%.	CL
3							
4	SS-2	1.9' 95%	3 5 6 7			On 2/15/18, used Ingersoll-Rand T3W rotary rig to ream borehole to 26.5' using 10" air hammer bit and set permanent 6" ID PVC casing. Casing sealed with cement bentonite grout.	
5							
6	SS-3	2.0' 100%	5 7 9 11	Below 5' roots (trace). Siltstone clasts present, trace, up to 1" diameter. Clay content increasing with depth.		SS-3 Lab results: MC 19.3%.	
7				Underlying contact is transitional. Change at 7.4'.			
8	SS-4	1.9' 95%	4 7 9 11	Pale yellow to pale gray (5Y 8/2 - 7/2) to strong brown (7.5YR 5/6 - 4/6) SILTY CLAY. Trace fine grained sand. Trace angular shale and siltstone clasts. Medium to high plasticity. Cohesive. Color gives mottled appearance. Very stiff. High dry strength. Weathered. Iron and/or manganese oxide throughout. No reaction with HCl. Shale clasts becoming oriented in same direction. Moist. COLLUVIUM.		SS-4 Lab results: MC 24%; 0.5% Gravel; 34.2% Sand; 65.3% Fines.	CL
9							
10	SS-5	2.0' 100%	4 8 16 19	Change at 9.9'. Gray to dark gray (10YR 5/1 - 4/1) completely weathered SHALE (SAPROLITE). Trace fine grained sand. Laminated to thinly bedded. Shale clasts are comprised mostly of silt and clay. Some shale broken into angular/subangular gravel-sized pieces with iron oxide and manganese oxide on shale surface. Shale bedding is at ~40°-50° angle. Very stiff to hard. Cohesive. High plasticity. Highly decomposed. No dilatancy. Weathered. No reaction with HCl. Dry to moist. SAPROLITE.		SS-5 Lab results: MC 21%.	CL
11							
12	SS-6	1.7' 85%	9 20 34 40	Below 12.1' some silt beds and partings present .			
13	SS-7	0.9' 100%	14 50/5	13.7' - 13.9' Color is olive gray to olive (5Y 5/2 - 4/3).			
14	NS			Below 13.7' becomes moderately to highly decomposed. Shale is becoming more intact. Slickensided features along shale bedding planes. Dry to moist.			
15	SS-8	1.0' 100%	46 50/6			SS-8 Lab results: MC 11.5%.	
16	NS			Becoming less weathered with depth.			
17	SS-9	1.3' 100%	24 45 50/3			SS-9 Lab results: MC 11.7%.	
18	NS					2/12/18 at 0910 DTW=9.81 BGS.	
19	SS-10	0.7' 100%	40 50/2	No reaction with HCl.		SS-10 Lab results: MC 11.1%.	

BOREHOLE LOG V.2 OAK RIDGE.GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

EMDF Characterization Project
Oak Ridge, TN

BOREHOLE LOG

Boring Number GW-978

Remarks:

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
	NS			Gray to dark gray (10YR 5/1 - 4/1) completely weathered SHALE (SAPROLITE). (Cont'd.)		Water on AW rods when pulling SS-10. Water in hole may be from surface. ~4" rain over weekend.	CL
21	SS-11	0.2' 100%	50/2	Below 21.0' shale is mostly intact. Iron oxide and manganese oxide become trace. Sample is mostly pulverized due to sample technique and high blow counts. Color becomes gray to dark gray (N 5/ - 4/). Shale clasts are difficult to be broken by hand. Dry to moist.			
22	NS					SS-12 No return. Very hard sampling and augering.	
23	SS-12	0	50/2				
24	NS			Underlying contact may be as high as 17.0'.			
25	SS-13	0	50/2	Change at 25.1'.		SS-13 No return. Switching to core to attempt better sample recovery. DTW = 17.85' BGS on 2/12/18 at 1055. Added 1/2 bag 3/8" bentonite chips to hole. Lowered 4" ID temporary surface casing to 25.0'.	
	C-1	0.9' 100%	0%	Overall structure is a laminated to thinly INTERBEDDED LIMESTONE and SHALE. The shale is very dusky red (10R 2/2). The limestone is dark reddish gray (10GY 4/1). The shale is laminated to thinly bedded. Abundant with slickensides, most along bedding plane. Strong field strength. The limestone is laminated in parts with glauconite grains. Has a strong reaction with HCl. The overall structure is fresh to slightly decomposed. Slightly disintegrated. Intensely to very intensely fractured. Most fractures are along the 45° bedding plane and mechanically induced. Some fractures are completely healed with white to pink/orange calcite and dusky red mudstone. Soft sediment deformation and cross-bedding is present throughout and along shale/limestone bedding contact.		C-1 25.1' - 26.0' 1256-1311.	
26							
27							
28	C-2	3.1' 62%	0%				
29				26.0' - 27.3' Multiple horizontal and vertical breaks and fractures. Some are healed with calcite. Most are mechanically induced.		C-2 26.0' - 31.0' 1326-1429. (Stopped run from 1340 - 1345 to switch water tanks.)	
30				At 27.3, iron oxide on fracture perpendicular to the bedding plane. Below 27.3' sample is very intensely fractured (pulverized). Probably mechanically induced.			
31				Change at 31.0'.			
32				Dusky red to very dusky red (10R 3/2 - 2.5/2) SHALE. Laminated to thinly bedded. Strong field strength. Trace limestone beds and partings. Abundant slickensides mostly along bedding plane. Bedding is ~40°-50°. Trace glauconite grains and stringers. Fresh. Slightly disintegrated.		C-3 31.0' - 34.6' 1442-1550. 1526-1540 Change water/break.	
33	C-3	3.6' 100%	28.9%	Moderately to intensely fractured. Most breaks/fractures are mechanically induced. Trace to little fractures are healed with calcite. No reaction with HCl in shale. Strong reaction on limestone beds and calcite veins.		33.0' Fracture perpendicular to bedding plane.	
34				31.6', 31.85' - 32.0' Fracture perpendicular to bedding plane. 32.3' Fracture along bedding plane with slickensides and brittle calcite. 32.5' - 33.0' Very intensely fractured. Multiple fractures/breaks along and perpendicular to bedding planes.		35.6' Fracture along bedding plane healed with calcite. 33.6' - 33.8' Vertical fracture.	
35	C-4	1.4' 100%	38.6%	37.5' - 37.6' Dark greenish gray limestone parting. Limestone contains angular clasts of limestone (interclasting limestone).		C-4 34.6' - 36.0' 1608-1627.	
36				37.6' - 38.8' Shale is pulverized. Dark greenish gray in color.		C-5 36.0' - 38.8' 1640-1714. 1649-1655 Change water.	
37	C-5	2.6' 93%	29.6%	Below 38.8' becoming moderately fractured. 38.9' - 39.1' Calcite healed fracture perpendicular to bedding. 39.1' - 39.4' Fracture along bedding plane, slickensided with thin calcite precipitate.			
38							
39	C-6	2.1' 95.5%	45.5%	39.4' - 40.2' Trace siltstone/mudstone partings. Irregular breaks in core. Horizontal to core axis. Same color as shale. Strong to moderate reaction with HCl. 40.2' - 40.4' Fracture along bedding plane with thin calcite precipitate. Below 41.0' limestone beds and partings become trace to little.		2/12/18 at 1719 DTW = 5.65' BGS. 2/13/18 at 0810 DTW = 9.19' BGS.	
40							
41				41.4' - 41.5' Fracture perpendicular to bedding plane with brittle calcite. 41.7' Fracture horizontal to core axis with brittle calcite. 42.5' Bedding plane fracture with brittle calcite.		C-6 38.8' - 41.0' 0830-0856.	
42				Below 42.6' shale becomes very dark greenish gray (10Y 3/1). Limestone beds and partings increasing with depth. Limestone beds present with bioturbidation.		42.0' Water circulation becomes light gray.	
43	C-7	5.0' 100%	33.8%	42.6' - 42.9 Fracture perpendicular to bedding plane with calcite. Change at 42.7'. (Transitional).		C-7 41.0' - 46.0' 0905-0956. 0914-0919 Change water.	
44				Laminated to thinly INTERBEDDED SHALE and LIMESTONE. The shale is dark reddish gray to reddish black (2.5YR 3/1 - 2.5/1). Laminated to thinly bedded. Strong field strength. Abundant slickensides. The limestone is gray to dark gray (N 5/ - 4/). Bioturbidation and soft sediment			

BOREHOLE LOG V.2 OAK RIDGE.GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

EMDF Characterization Project
Oak Ridge, TN

BOREHOLE LOG

Boring Number GW-978

Remarks:

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
46	C-7	5.0' 100%	33.8%	deformation. Strong field strength. Trace glauconite grains. The contact between the shale and limestone is in most part deformed. Trace glauconite veins/stringers. Fresh to slightly decomposed. Intensely to moderately fractured. Most fractures are along bedding planes and probably mechanically induced. Trace to some fractures are completely healed with calcite.		At ~45' water circulation turned brown. ~45.5' Water circulation dark to light gray.	
47				44.6' - 45.1' Multiple fractures with and against bedding plane. Iron oxide and manganese oxide present on all fracture surfaces. Iron oxide halo from 44.6' - 44.9'.		C-8 46.0' - 51.0' 1020-1200.	
48	C-8	4.9' 98%	36.6%	45.0' - 45.3' Multiple fracture with and against bedding plane. Iron oxide and manganese oxide on each fracture face. Iron oxide halo ~0.01' around fractures.		46.5' Water brown. 47.0' Water light gray.	
49				47.2' Fracture along bedding plane with Iron and manganese oxide.			
50				49.0' and 49.2' Fracture horizontal to core axis with iron and manganese oxide.			
51				Below 51.0' becomes moderately fractured. Most to all mechanically induced.		On C-8 ran out of water at 50.8'. Finish run after lunch. Lunch 1100-1155.	
52				52.2' - 53.2' Fracture perpendicular to bedding plane completely healed with calcite.		C-9 51.0' - 56.0' 1210-1320. 1237-1309 Stop - out of water.	
53	C-9	4.7' 94%	35.8%	Below 52.5' trace to little glauconite stringers/veins/partings. Limestone has fine grains of glauconite. Limestone and shale interbeds are mostly wavy and deformed. There are some subrounded, reworked limestone clasts oriented with bedding (40° - 50°).			
54				Below 54.0' bedding becomes mostly planar with some soft sediment deformation. Shale has a very dark greenish gray color (10GY 3/1).			
55							
56				Below 56.0' becomes intensely fractured to very intensely fractured. Multiple fracture/breaks are along calcite healed fractures or bedding planes. Shale becomes dark reddish brown (5YR 3/2). 56.2' - 56.4' Fracture perpendicular to bedding plane healed with calcite.			
57	C-10	2.7' 90%	0%	57.2' - 59.0' Very intensely fractured. Most/all are mechanical breaks along bedding planes/calcite healed fractures.		C-10 56.0' - 59.0' 1330-1424. 1356-1413 Change water.	
58				59.0' - 59.2' Vertical fracture (mechanical break) healed with calcite. 59.0' - 59.6' Shale is very dark greenish gray (10GY 3/1).			
59				Below 59.6' soft sediment deformation becomes trace to little.		At 59.0' driller noted spike in water pressure. Stopped run at 59.0'.	
60	C-11	1.9' 95%	0%	61.4' - 61.6' Shale is very dark greenish gray (10GY 3/1). Shale beds becoming dominant.		C-11 59.0' - 61.0' 1435-1450.	
61				61.8' - 62.0' Fracture along bedding plane healed with calcite.			
62				62.6' Mechanical break perpendicular to bedding.		C-12 61.0' - 65.6' 1502-1536.	
63	C-12	3.4' 74%	0%	63.0' - Mechanical break perpendicular to bedding. Below 63.6' shale becomes dark greenish gray (10GY 3/1). Shale and limestone beds become 50/50. Soft sediment deformation becomes few to little.			
64				64.1' - 64.2' Fracture perpendicular to bedding plane healed with calcite.		65.0' Driller noted spike in water pressure. Pulled run, thinks lost from bottom of C-12.	
65	C-13	0.7' 77.8%	37.8%	Below 65.1' shale becomes dark reddish brown (5YR 3/2). Fractures healed with calcite become trace to rare.		C-13 65.6' - 66.0' 1545-1557.	
66	C-14	1.3' 81.3%	0%	66.6' Horizontal fracture healed with calcite.			
67				67.9' Horizontal fracture with calcite. Multiple fractures along bedding plane are mechanically induced.		C-14 66.0' - 67.6' 1608-1628. Spike in water pressure blocked tip. Pulled run at 67.6'. Lost from bottom of run.	
68	C-15	3.2' 94.1%	0%				
69				69.9' - 70.2' Fracture perpendicular to bedding plane healed with calcite.		C-15 67.6' - 71.0' 1636-1714. 1643-1650 Change water.	

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.

EMDF Characterization Project Oak Ridge, TN	**BOREHOLE LOG**	Boring Number GW-978

Remarks:

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
71	C-15	3.2'	0%	Gray to dark gary (N 5/ - 4/) to dark reddish brown (5YR 3/2) INTERBEDDED SANDSTONE and SHALE. (Cont'd.)		2/13/18 at 1710 DTW=21.51 BGS. 2/14/18 at 0802 DTW=18.05 BGS.	
72	C-16	2.7	0%	71.0 - 71.5' Highly broken zone. Mechanically induced. Some fractures completely healed with calcite. 71.9' Fracture horizontal to core axis healed with calcite. Glauconite veins and stringers become little. Most breaks are along bedding plane and mechanically induced.		C-16 71.0' - 73.9' 0922-0948.	
74	C-17	1.1	0%			C-17 73.9' - 75.0' 0957-1006.	
75	NS					2/14/18 at 1021 DTW=33.96 BGS.	
80				Bottom of Borehole = 80.0'. Piezometer GW-978 installed in borehole. See Monitoring Well Installation Report GW-978 for details.		2/18/18 Reamed borehole and advanced borehole to 80.0' using Ingersoll-Rand T3W rotary rig with 5 7/8" tricone bit with water and air circulation. Completed at 1658.	

BOREHOLE LOG V.2 OAK RIDGE.GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.

Well Number GW-978

Monitoring Well Installation Report

Site Name and Location: *EMDF Characterization Project, Oak Ridge, TN*	Completion Date: *3/8/18*
Coordinates: *30656.68N 38643.59E*	Borehole Depth (ft): *80.0*
Elevation Top of Casing (ft/MSL): *955.97*	Borehole Diameter (in):*10" (0'-26.5'), 5 7/8" (26.5'-80.0')*
Elevation Ground Surface (ft/MSL): *953.5*	Drilling Methods: *2 1/4" HSA, HQ3 Core w/water, 10" hammer bit w/air, 5 7/8" tricone bit w/water/air.*
Installed By: *Fred Reynolds/Tri-State Drilling*	Completed Drilling: *2/18/18*
Supervised By: *Shay Beanland/Eagon & Associates, Inc.*	Drilling Water Used (gals):

Well Design

Component	Materials	Depth (LSD)	Elevation
Well Protector	4" Square Steel Protector w/Locking Lid	-2.8 - 2.2	956.3 - 951.3
Riser	2" ID Schedule 40 PVC	-2.3 - 59.5	955.8 - 894.0
Surface Seal	3' x 3' Concrete Pad	-0.5 - 0.5	954.0 - 953.0
Conductor Casing	6" ID PVC Schedule 40, Flush Threaded	-0.4 - 26.5	953.9 - 927.0
Cement Grout	Cement Bentonite Grout	0.5 - 53.0	953.0 - 900.5
Bentonite Seal	Pel Plug 1/4" Coated Bentonite Pellets	53.0 - 56.1	900.5 - 897.4
Sand Pack	DSI "GP #2" Gravel Pack	56.1 - 70.9	897.4 - 882.6
Screen	2" ID Schedule 40 PVC, 10-Slot	59.5 - 69.6	894.0 - 883.9
Well Point Blank	2" ID Sch. 40 PVC Cap & Riser Section	69.6 - 70.9	883.9 - 882.6
Sand Pack Bottom	DSI "GP #2" Gravel Pack	70.9 - 71.5	882.6 - 882.0
Bentonite Seal	Pel Plug 1/4" Coated Bentonite Pellets	71.5 - 80.0	882.0 - 873.5


Well Development

Well Depth (ft,TOC):	Depth to Water (ft,TOC):	Well Volume (gals):	Volume Purged (gals):
73.18	*10.63*	*10.2*	*467.5*

Development Method:
Bailer, surge block, Tornado pump

Date	Time	Cumulative Volume Removed (gals)	Temp (°C)	Specific Conductivity (µmhos/cm)	pH (S.U.)	Turbidity (NTU)
2/26/18	1700	125	--	--	--	--
2/27/18	0810	145	14.1	372	8.29	3.6
2/27/18	1304	250	14.8	351	7.56	2.7
2/27/18	1314	265	14.8	342	7.57	6.0
2/27/18	1344	310	14.8	334	7.52	1.8
2/27/18	1555	467.5	15.1	340	7.48	2.0


Recovery Data



Sampling Equipment:

Comments:

Stainless steel centralizers set at 52' and 27' from ground surface. Washed sand pack and pellets in using tremie pipe. Grout mixing and placement information provided by Tri-State Drilling. Screen slot interval 59.8 - 69.5 bgs.



Boring depth=80.0 ft.

MONITOR WELL INSTALLATION 2 OAK RIDGE .GPJ EAGON.GDT 4/4/18

This page intentionally left blank.

Eagon & Associates, Inc.

BOREHOLE LOG

Site Name and Location: **EMDF Characterization Project Oak Ridge, TN**	Drilling Methods: 3 1/4" ID HSA, HQ Core with water, 5 7/8" air hammer bit.				Boring Number: GW-979
Drilling Firm: *Tri-State Drilling*	DATE	TIME	DEPTH DRILLED (ft)	WATER LEVEL (ft)	
Driller / Rig: *Fred Reynolds/Mobile Drill B42C*					*Page 1 of 2*
Logged by: *Shay Beanland*	Sampling Methods: ST = Shelby Tube; WS = Waxed Sample; SP = Sand Pump; GP or DP = Direct Push; CT = Cuttings; SS = Split Spoon; CS = Continuous Sampler; C = Coring; NS = Not Sampled; B = Bailer				Start: *Time 1112, Date 2/21/18* / Finish: *Time 1358, Date 2/22/18*
Coordinates: *30656.61N 38653.90E*					
Surface Elevation: *953.7 ft/MSL*					
Surface Conditions / Weather: *Gravel road base, wet / 70°F, Overcast, light sprinkle*					

Remarks: Borehole installed for the collection of geotech samples and installation of shallow piezometer.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
1–3	NS			See Borehole Log GW-978 for detailed lithologic description and stratigraphic interpretation.		Ran 3 1/4" ID HSA with center plug while augering. 7" OD borehole.	
3–5	ST-1	2.0	700 PSI 700 PSI 750 PSI 850 PSI	At base of tube, sample was light brown to strong brown (7.5YR 6/4 - 5/6) SANDY SILTY CLAY. Sand is fine grained. Sample is mottled. Moist.		Pushed Shelby tube from 3.0' - 5.0'. Let Shelby tube (ST-1) set from 1119 to 1132. Bucket Sample BS-1 collected from 4.0' - 5.0' at 1140.	
5–7	NS					Bucket Sample BS-2 collected from 5.0' - 6.0' at 1141.	
7–8	ST-2	1.25	900 PSI 900 PSI				
8–9	NS		1000/3 PSI	At base of tube, sample was reddish brown (5YR 5/3 - 4/4) SAPROLITE (SHALE). Highly weathered. Easily crumbled with hand. Moist.		Pushed Shelby tube (ST-2) from 7.5' - 8.75', which is where refusal was. Let Shelby tube set from 1144 to 1154.	
9–10	ST-3	1.6	850 PSI 1100 PSI				
10–11							
11–15	NS		1500/4 PSI	At base of tube, sample was light yellowish brown to light olive brown (2.5Y 4/3 - 5/3) SHALE (SAPROLITE). Weathered. Easily crumbled with hand. Iron oxide and manganese oxide on bedding plane surfaces.		Pushed Shelby tube (ST-3) from 9.5' - 10.8'. Let tube set from 1201 to 1208.	
15–19							

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.

EMDF Characterization Project Oak Ridge, TN	**BOREHOLE LOG**	Boring Number GW-979

Remarks: Borehole installed for the collection of geotech samples and installation of shallow piezometer.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
21	C-1	0.4' 44.4%	0%	Dark gray to very dark green gray (N 4/ - 5GY 3/1) INTERBEDDED SHALE and LIMESTONE. Limestone tends to be lighter in color - gray to greenish gray (N 5/ - 5GY 5/1). Laminated in places with glauconite grains. Overall structure of interbeds is laminated to medium bedded. Shale is laminated. Slickensides observed on bedding plane surfaces due to soft sediment deformation. Bioturbation and other soft sediment deformation features observed. Bedding is at 40° to 50° angles. No iron staining observed. Field strength is strong. Core is fresh and competent to slightly disintegrated where trace fractures have been healed with calcite. Some fractures that are healed with calcite are at 45° angles and opposite direction of bedding. Intensely to very intensely fractured in part, but breaks are along bedding planes and are likely mechanical.		Auger refusal at 20.2'. Switch to HQ core barrel and start coring and pulled augers at 1359 - 1421 went to get casing. 1421 Attempting to install PVC casing.	
22							
23	C-2	3.9' 100%	26.1%			1424 WL at 18.55', TD = 20'.	
24							
25						1643 WL at 5.8', TD = 27.1'.	
26	C-3	2.1' 100%	0%			25.6' - 26.0' Calcite present along fracture face.	
27						C-1 Run: recovery has been highly disturbed. Limestone beds intact, shale has been pulverized and did not feed into barrel. Sample destroyed.	
28						C1: 20.2 - 21.1' 1445-1455.	
29						C2: 26.1' - 25.0' 1500-1522.	
30						21.1' - 21.3' Very intensely broken along bedding planes and some at an angle perpendicular to bedding direction. Iron staining throughout. No iron staining present below 21.3'.	
31							
32	NS					C3: 25.0' - 27.0' 1528-1548.	
33							
34							
35							
36							
37							
38				Bottom of Borehole = 37.6'. Piezometer GW-979 installed in borehole. See Monitoring Well Installation Report GW-979 for details.		On 2/22/18 used Ingersoll-Rand T3W rotary rig to ream corehole and advance borehole to 37.6' using 5 7/8" hammer bit. Completed drilling at 1358.	
39							
40							
41							
42							
43							
44							

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.

Well Number GW-979

Monitoring Well Installation Report

Site Name and Location: *EMDF Characterization Project, Oak Ridge, TN*	Completion Date: *3/8/18*
Coordinates: *30656.61N 38653.90E*	Borehole Depth (ft): *37.8*
Elevation Top of Casing (ft/MSL): *955.99*	Borehole Diameter (in):*5 7/8" (0'-37.75')*
Elevation Ground Surface (ft/MSL): *953.7*	Drilling Methods: *3 1/4" ID HSA, HQ Core with water, 5 7/8" air hammer bit.*
Installed By: *Fred Reynolds/Tri-State Drilling*	Completed Drilling: *2/22/18*
Supervised By: *Shay Beanland/Eagon & Associates, Inc.*	Drilling Water Used (gals):

Well Design

Component	Materials	Depth (LSD)	Elevation
Well Protector	4" Square Steel Protector w/Locking Lid	-2.6 - 2.4	956.3 - 951.3
Riser	2" ID Schedule 40 PVC	-2.3 - 26.3	956.0 - 927.5
Surface Seal	3' x 3' Concrete Pad	-0.5 - 0.5	954.2 - 953.2
Cement Grout	Cement Bentonite Grout	0.5 - 19.0	953.2 - 934.7
Bentonite Seal	Pel Plug 1/4" Coated Bentonite Pellets	19.0 - 21.2	934.7 - 932.6
Sand Pack	DSI "GP #2" Gravel Pack	21.2 - 37.6	932.6 - 916.1
Screen	2" ID Schedule 40 PVC, 10-Slot	26.3 - 36.3	927.5 - 917.4
Well Point Blank	2" ID Sch. 40 PVC Cap & Riser Section	36.3 - 37.6	917.4 - 916.1
Sand Pack Bottom	DSI "GP #2" Gravel Pack	37.6 - 37.8	916.1 - 916.0


Well Development

Well Depth (ft,TOC):	Depth to Water (ft,TOC):	Well Volume (gals):	Volume Purged (gals):
39.88	*14.70*	*4.1*	*236.0*

Development Method:
Surge block, bailer, Tornado pump

Date	Time	Cumulative Volume Removed (gals)	Temp (°C)	Specific Conductivity (µmhos/cm)	pH (S.U.)	Turbidity (NTU)
2/27/18	1100	108.5	14.4	311	7.35	41.9
2/27/18	1110	123.5	14.4	306	7.44	13.1
2/27/18	1150	183.5	14.5	304	7.35	1.0
2/27/18	1200	198.5	14.5	304	7.30	1.9
2/27/18	1210	213.5	14.5	301	7.38	0.9
2/27/18	1225	236.0	14.5	303	7.32	0.7


Recovery Data



Sampling Equipment:

Comments:

Grout mixing and placement information provided by Tri-State Drilling. Screen slot interval 26.5 - 36.2 bgs.



Boring depth=37.8 ft.

MONITOR WELL INSTALLATION 2 OAK RIDGE .GPJ EAGON.GDT 4/4/18

This page intentionally left blank.

Eagon & Associates, Inc.

BOREHOLE LOG

Site Name and Location: **EMDF Characterization Project Oak Ridge, TN**	Drilling Methods: 3 1/4" ID HSA, HQ3 Core with water circulation, 10" air hammer bit, 5 7/8" tricone bit with air/water.				Boring Number: GW-980
Drilling Firm: *Tri-State Drilling*	DATE	TIME	DEPTH DRILLED (ft)	WATER LEVEL (ft)	
Driller / Rig: *Shannon Snow/CME-550*					*Page 1 of 4*
Logged by: *David J. Sugar*	Sampling Methods: ST = Shelby Tube; WS = Waxed Sample; SP = Sand Pump; GP or DP = Direct Push; CT = Cuttings; SS = Split Spoon; CS = Continuous Sampler; C = Coring; NS = Not Sampled; B = Bailer				Start: *Time 1525, Date 2/13/18* / Finish: *Time 1202, Date 2/17/18*
Coordinates: *30388.00N 38138.34E*					
Surface Elevation: *963.4 ft/MSL*					
Surface Conditions / Weather: *Gravel pad, moist, slopping / 51°F, Overcast*					
Remarks:					

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
				Road bed/pad. Gravel.		3 1/4" ID HSA, 7 1/2" OD, ran center bit while augering. Continuous 2" OD, 2' drive split spoons 140 lb automatic hammer.	
1	NS			Dark yellowish brown (10YR 4/4 - 4/6) SANDY SILT. Few clay. Few to some gravel clasts, up to 1 3/8" shale/sandstone fragments. Unsorted, generally jumbled fabric (no dominant orientation of clasts). Low to medium plasticity. Low to medium toughness. Weathered. Moist to slightly moist. RESIDUUM/COLLUVIUM.		Possibly ML-CL classification. Trace to some iron oxide coatings on rock fragments. Does not appear to follow soil fractures, isolated to rock fragments.	ML
2	SS-1	0.5' 83%	4				
3	SS-2	1.6' 80%	5 10 12 17				
4				Trace to some very grayish green (5GY 3/2) zones. Possibly highly weathered glauconitic rock fragments.		No reaction with HCl.	
5	SS-3	2.0' 100%	6 21 29 30			On 2/15/18 used Ingersoll-Rand T3W rotary rig to ream corehole to 26.5' using 10" air hammer bit. Set permanent 6" PVC casing and sealed with cement bentonite grout.	
6							
7	SS-4	2.0' 100%	43 68 73 70	Below 6.9' primarily slightly moist. Color is lighter light brownish gray, brown to yellowish brown (10YR 5/2 - 5/6).		SS-2 Lab results: Moisture Content (MC) 13.8%; 45% Gravel; 32% Sand; 23% Fines.	
8							
9	SS-5	2.0' 100%	16 25 49 42				
10							
11	SS-6	2.0' 100%	6 25 78 100	11.1' - 11.2' grayish green glauconitic sandstone fragment.		Possibly ML-CL classification. SS-3 Lab results: MC 15.1%.	
12							
13	SS-7	1.4' 70%	11 39 100/4	Light yellowish brown to brownish yellow (10YR 6/4 - 6/8) and greenish gray (5G 5/1). Highly to completely weathered SHALE. Thinly bedded. Considerable yellowish brown iron oxide coatings. Trace manganese oxide.		Zone with rock structure. Possibly large rock fragment. SS-4 Lab results: MC 15%. SS-6 Lab results: MC 12.6%. SS-8 Lab results: MC 14.5%. No reaction with HCl.	
14	NS						
15	SS-8	2.0' 100%	39 54 66 51	Continues to have low to medium plasticity, low to possibly medium toughness. Possibly ML-CL classification.		Appears saprolitic in places, may be large flat rock fragments. Slightly moist.	
16							
17	SS-9	1.9' 95%	20 63 57 100/5	Underlying contact is gradational from 17.2' - 17.5'. Change at 17.4'.		SS-9 Lab results: MC 10.2%. SS-10 Lab results: MC 4.3%.	
18	SS-10	0.7' 100%	92 100/2	Gray to greenish gray (N 5/ - 10Y 5/1) SHALE. Soft. Sample structure is generally destroyed by sampling process. Trace yellowish brown iron oxide, fracture coatings. Appears thinly bedded with relatively high bedding angle.		No reaction with HCl. Unweathered to slightly weathered.	
19	NS			Below 18.0' primarily gray (N 5/) color. Trace yellowish brown iron oxide near 18.6'.		Slightly moist to dry structure is mostly disturbed by the	

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

EMDF Characterization Project
Oak Ridge, TN

BOREHOLE LOG

Boring Number GW-980

Remarks:

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
	SS-11	0.5'/100%	100/5	Very dark gray to black (N3/ - N2.5/) SHALE. (Cont'd.)		sampling process. SS-11 Sample is wet, ~1' of cutter sampler was also wet. After taking SS-11 (1700) measured WL at 19.22' (1705).	
21	NS			Trace yellowish brown iron oxide from 20.2' to 20.3'.			
22	SS-12	0.9' 90%	69 100/2	Trace white precipitate (?) does not react with HCl. Trace amount associated with bedding planes.		SS-12 Lab results: MC 11.7%. SS-13 Lab results: MC 12.3%.	
23	NS			Below 22.0' oxidation not present. Formation is soft but relatively unweathered.		SS-11 and SS-12 Recovery is broken due to the sampling process. Bedding appears to be angled but gradation is not apparent.	
24	SS-13	0.8' 80%	40 100/3	SS-13 Sample has relatively intact bedding. 40° - 45° Bedding angle, appears thinly bedded.		End 2/13/18, 1735, at 25.0'. 1746 WL = 20.72' from GS. Begin 2/14/18, 0830, 45°-50°F, light rain. 0808 WL = 14.12' from GS.	
25	NS						
26				Change at 26.3'.			
27	C-1	2.6 87%	0%	Interbedded dark reddish gray/weak red to dark red (2.5 4/1 - 4/2 and 3/1 - 3/2) SHALE and dark gray to very dark gray (N4/ - N3/) LIMESTONE or calcareous SILTSTONE. Thinly bedded to banded, beds are generally less than 0.1', and up to 0.2'. Trace to few dark green/greenish black glauconitic beds and partings. Bedding is typically irregular, showing soft sediment deformation features. Limestone content generally varies between 30 to 40%. Healed fractures with white calcite infilling are generally present, but seldom exceed 2mm in width and are often hairline.		Auger SS-13 interval and advance augers to 26.0'. Not refusal but formation appears competent to core. Installed 4" temporary casing to 26.3'. Start HQ3 coring at 1053, water circulation.	
28							
29				The formation is moderately to intensely fractured, however most of the breaks are associated with bedding plane breaks and are mechanical breaks at planes of weakness. Some surfaces are slickenside, but appear to be depositional, associated with lithification. Limestone beds are moderately hard to hard and shale beds are soft. The formation is unweathered, fresh.		Bedding generally varies between 35° and 40°.	
30	C-2	2.5' 81%	13%			C-1 26.3' - 29.3' 1033-1056. C-2 29.3' - 32.9' 1101-1115. C-3 32.9' - 33.1' 1125-1130.	
31				27.2' - 27.8' Glauconitic limestone seam. Interclastic, with clasts up to 1/2" diameter, irregular elliptical shape with reddish brown hematitic halo.		27.2' - 27.8' Fracture or fracture set, rough face. Secondary clear crystals on face, relatively flat crystals, does not react with HCL - possibly gypsum or celestite.	
32				At 31.2' and 31.3' fracture, orientation is approximately 35° to the bedding angle. Face is heavily striated (slickenside) with red clay or hematite on fracture face. Ferrous oxide.			
33	C-3	0.6' 100%	0%			C-3 Run picked up 0.4' from C-2 run.	
34				Below 32.9' the reddish color hue changes to dark reddish gray/reddish black (7.5R 3/1 - 2.5/1)		29.9' - 30.0' Calcite filled fractures perpendicular to bedding.	
35	C-4	3.9' 81%	31%	Below 34.6' generally becoming more competent, moderately fractured with most core breaks attributed to mechanical drilling breaks.		31.1' and 33.5' Bedding breaks with slickenside surfaces, no mineralization present, probably mechanical.	
36							
37						C-4 33.1' - 37.9' 1132-1152.	
38				Below 37.9' healed fractures with white calcite infilling are relatively rare and usually less than 1 to 2 mm wide. Limestone/limey siltstone content is probably closer to 25-30%.		37.9' - 39.2' Broken zone, several breaks along bedding planes with slickenside surfaces.	
39							
40	C-5	4.7' 94%	9%			At 38.7' bedding break with slickenside and very fine secondary pyrite crystals on fracture face.	
41							
42						C-5 37.9' - 42.9' 1249-1314.	
43						C-6 42.9' - 47.9' 1323-1339.	
44	C-6	5.0' 100%	56%	Below 42.9' deformation of limestone/limey siltstone appears slightly more pronounced. Most bedding breaks are associated with depositional slickenside surfaces. Most have trace to full thin coatings of calcite. Bedding angle is approximately 40°.		43.2' - 44.2' Several bedding breaks (0.1' - 0.4' intervals) faces are generally slickensided (appears depositional) with trace to full carbonate coatings (calcite).	

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

EMDF Characterization Project Oak Ridge, TN	**BOREHOLE LOG**	Boring Number GW-980

Remarks:

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
46	C-6	5.0' 100%	56%	Interbedded dark reddish gray to reddish black (7.5R 3/1 - 2.5/1) SHALE and dark gray to very dark gray LIMESTONE to LIMEY SILTSTONE. (Cont'd.)		Moderate to slightly fractured.	
47							
48	C-7	5.0' 100%	77%	Continues to be fresh, no observed oxidation. Thinly bedded and competent. Bedding contacts are deformed, wavey structure.		Bedding angle is approximately 45°.	
49							
50						Fracture at 49.8' has a white calcite coating.	
51						C-7 47.9' - 52.9' 1347-1358.	
52							
53	C-8	5.0' 100%	65%				
54						C-8 52.9' - 57.9' 1405-1417.	
55							
56				Bedding angle approximately 47°.			
57							
58	C-9	1.0' 100%	71%			C-9 57.9' - 58.9' 1428-1440.	
59	C-10	3.2' 80%	28%	Bedding angle varies between 35° - 40°. 59.2' - 64.3' Moderate to intensely broken. Most breaks correspond with bedding breaks/depositional slickenside surfaces. Slightly higher concentration of calcite healed fractures are perpendicular to bedding.		59.2' - 60.1' Zone with healed (calcite filled) fractures, generally oriented perpendicular to bedding angle. At 59.2', 59.5', and 59.8' fractures are open but appear broken by the drilling process.	
60				By 60.5' bedding angle is approximately 50°.			
61						C-10 58.9' - 62.9' 1445-1457.	
62				62.2' - 63.5' Bedding turns (deformed) to vertical and back to normal (~45°) bedding angle.		No weathering or oxidation observed. C-10 recovery loss appears associated with this zone.	
63	C-11	4.8' 96%	39%				
64				Below 64.3' slightly fractured to unfractured. Continues to be fresh, no oxidation, competent. Bedding angle is approximately 45°.			
65						C-11 62.9' - 67.9' 1503-1517.	
66							
67						67.0' - 67.3' Bedding plane break with apparent depositional slickensides. Trace calcite coating and fine pyrite crystals.	
68	C-12	5.0' 100%	86%	Bedding angle is approximately 50°. 68.0' - 68.2' Bedding plane break, weak slickenside surface, calcite generally coats face. Probably mechanical break.			
69						C-12 67.9' - 72.9' 1529-1540.	

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

EMDF Characterization Project Oak Ridge, TN	**BOREHOLE LOG**	Boring Number GW-980

Remarks:

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
71	C-12	5.0' 100%	86%	Interbedded dark reddish gray to reddish black (7.5R 3/1 - 2.5/1) SHALE and dark gray to very dark gray LIMESTONE to LIMEY SILTSTONE. (Cont'd.)		Continues to be very competent, fresh, relatively unfractured. Bedding angle is approximately 50°. 72.4' - 72.5' Bedding plane break, weak slickensides (depositional). Trace calcite on face.	
72							
73	NS						
74				Bottom of Borehole = 73.6'. Borehole sealed with cement bentonite grout due to damage to the surface casing at the beginning of reaming activities. Installation borehole for piezometer GW-980 installed approximately 7' north of original borehole.		Finished coring at 1540, 2/14/18. Prior to removing core from C-12 run, flushed borehole from 1540 to 1550. Returns were free of cuttings. On 2/17/18 used Ingersoll-Rand T3W rotary rig to ream corehole and advance borehole to 73.6' using 5 7/8" hammer bit. Finished at 1202.	
75							
76							
77							
78							
79							
80							
81							
82							
83							
84							
85							
86							
87							
88							
89							
90							
91							
92							
93							
94							

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.

BOREHOLE LOG

Site Name and Location: **EMDF Characterization Project Oak Ridge, TN**	Drilling Methods: 10" Air Hammer, 5 7/8" tricone bit with water and air.				Boring Number: GW-980R
Drilling Firm: *Tri-State Drilling*	DATE	TIME	DEPTH DRILLED (ft)	WATER LEVEL (ft)	
Driller / Rig: *Travis Morgan/Ingersoll-Rand T3W*					*Page 1 of 4*
Logged by: *Nelson Novak*	Sampling Methods: ST = Shelby Tube; WS = Waxed Sample; SP = Sand Pump; GP or DP = Direct Push; CT = Cuttings; SS = Split Spoon; CS = Continuous Sampler; C = Coring; NS = Not Sampled; B = Bailer				Start: *Time 1525, Date 2/22/18* / Finish: *Time 1152, Date 2/27/18*
Coordinates: *30379.90N 38138.34E*					
Surface Elevation: *963.5 ft/MSL*					
Surface Conditions / Weather: *Damp gravel road / 55°F, Cloudy*					

Remarks: Drilled approximately 7' north of borehole GW-980.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
1–19	NS			GW-980R is a replacement well and was straight drilled. See Borehole Log GW-980 for detailed lithologic description and stratigraphic interpretation.		Straight drilled using 10" hammer bit to 27.0'. Set permanent 6" PVC casing and sealed with cement bentonite grout.	

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

EMDF Characterization Project Oak Ridge, TN	**BOREHOLE LOG**	Boring Number GW-980R

Remarks: Drilled approximately 7' north of borehole GW-980.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
21							
22							
23							
24							
25							
26							
27						Below 27.0', straight drilled to 74.4' using 5 7/8" tricone bit with air and water circulation.	
28							
29							
30							
31							
32	NS						
33							
34							
35							
36							
37							
38							
39							
40							
41							
42							
43							
44							

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

EMDF Characterization Project Oak Ridge, TN	**BOREHOLE LOG**	Boring Number GW-980R

Remarks: Drilled approximately 7' north of borehole GW-980.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
46							
47							
48							
49							
50							
51							
52							
53							
54							
55							
56							
57							
58	NS						
59							
60							
61							
62							
63							
64							
65							
66							
67							
68							
69							

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

EMDF Characterization Project Oak Ridge, TN	**BOREHOLE LOG**	Boring Number GW-980R

Remarks: Drilled approximately 7' north of borehole GW-980.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
71							
72	NS						
73							
74							
75				Bottom of Borehole = 74.4'. Piezometer GW-980R installed in borehole. See Monitoring Well Installation Report GW-980R for details.			
76							
77							
78							
79							
80							
81							
82							
83							
84							
85							
86							
87							
88							
89							
90							
91							
92							
93							
94							

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.

Well Number GW-980R

Monitoring Well Installation Report

Site Name and Location: *EMDF Characterization Project, Oak Ridge, TN*	Completion Date: *3/8/18*
Coordinates: *30379.90N 38138.34E*	Borehole Depth (ft): *74.4*
Elevation Top of Casing (ft/MSL): *965.63*	Borehole Diameter (in):*10" (0'-27.0'), 5 7/8" (27.0'-74.4')*
Elevation Ground Surface (ft/MSL): *963.5*	Drilling Methods: *10" Air Hammer, 5 7/8" tricone bit with water and air.*
Installed By: *Fred Reynolds/Tri-State Drilling*	Completed Drilling: *2/27/18*
Supervised By: *Shay Beanland/Eagon & Associates, Inc.*	Drilling Water Used (gals):

Well Design

Component	Materials	Depth (LSD)	Elevation
Well Protector	4" Square Steel Protector w/Locking Lid	-2.4 - 2.6	965.9 - 960.9
Riser	2" ID Schedule 40 PVC	-2.1 - 59.9	965.6 - 903.6
Cement Grout	Cement Bentonite Grout	-0.5 - 51.5	964.0 - 912.0
Surface Seal	3' x 3' Concrete Pad	-0.5 - 0.5	964.0 - 963.0
Conductor Casing	6" ID Sch. 40 PVC, Flush Threaded	-0.4 - 27.0	963.9 - 936.5
Bentonite Seal	Pel Plug 1/4" Coated Bentonite Pellets	51.5 - 54.9	912.0 - 908.6
Sand Pack	DSI "GP #2" Gravel Pack	55.0 - 71.3	908.5 - 892.2
Screen	2" ID Schedule 40, 10-Slot	59.9 - 70.0	903.6 - 893.5
Well Point Blank	2" ID Sch. 40 PVC Cap & Riser Section	70.0 - 71.3	893.5 - 892.2
Sand Pack Bottom	DSI "GP #2" Gravel Pack	71.3 - 72.3	892.2 - 891.2
Bentonite Seal	Enviro Plug Medium Chips	72.3 - 74.4	891.2 - 889.1


Well Development

Well Depth (ft,TOC):	Depth to Water (ft,TOC):	Well Volume (gals):	Volume Purged (gals):
73.44	*28.27*	*7.4*	*61.0*

Development Method:
Bailer, surge block, Tornado pump

Date	Time	Cumulative Volume Removed (gals)	Temp (°C)	Specific Conductivity (µmhos/cm)	pH (S.U.)	Turbidity (NTU)
3/5/18	0908	27	14.6	324.7	8.50	17.4
3/5/18	1025	35	13.9	325.1	8.78	15.3
3/5/18	1340	46	14.9	317.6	8.23	7.2
3/5/18	1532	54.5	14.6	330.2	8.48	7.3
3/5/18	1535	57	14.7	328.5	8.37	9.7
3/5/18	1537	59	14.4	328.0	8.45	12.1


Recovery Data



Sampling Equipment:

Comments:

Stainless steel centralizers set at 49 and 24.5 from ground surface. Washed sand pack and pellets in using tremie pipe. Grout mixing and placement information provided by Tri-State Drilling. Screen slot interval 60.2 - 69.9 bgs.



MONITOR WELL INSTALLATION 2 OAK RIDGE .GPJ EAGON.GDT 4/4/18

This page intentionally left blank.

Eagon & Associates, Inc.

BOREHOLE LOG

Site Name and Location: **EMDF Characterization Project Oak Ridge, TN**	Drilling Methods: 4 1/4" ID HSA, HQ3 Core with water.				Boring Number: GW-981
Drilling Firm: *Tri-State Drilling*	DATE	TIME	DEPTH DRILLED (ft)	WATER LEVEL (ft)	
Driller / Rig: *Shannon Snow/CME-550*					*Page 1 of 2*
Logged by: *David J. Sugar*	Sampling Methods: ST = Shelby Tube; WS = Waxed Sample; SP = Sand Pump; GP or DP = Direct Push; CT = Cuttings; SS = Split Spoon; CS = Continuous Sampler; C = Coring; NS = Not Sampled; B = Bailer				Start: *Time 1455, Date 2/23/18* / Finish: *Time 0955, Date 2/26/18*
Coordinates: *30396.70N 38148.33E*					
Surface Elevation: *963.2 ft/MSL*					
Surface Conditions / Weather: *Gravel pad, relatively flat / 79°F, Mostly sunny*					

Remarks: Borehole installed for the collection of geotech samples and installation of shallow piezometer.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
1–2	NS			See Borehole Log GW-980 for detailed lithologic description and stratigraphic interpretation. RESIDUUM/COLLUVIUM.		4 1/4" ID HSA, ran auger plug while augering. 7 1/2" OD borehole.	
3–4	ST-1	1.65	1200 PSI				
4–5				Description based on inspection of bottom of ST-1 recovery. Dark yellowish brown (10YR 4/4 - 4/6) highly (completely) weathered SHALE. ~45° Bedding angle. Appears in place, but may be a large rock fragment.		Auger cuttings bucket sample; BS-1 collected from 4.0' - 6.0'.	
6–7						Auger cuttings bucket sample; BS-2 collected from 6.0' - 8.0'.	
8–12	NS						
13–19							

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.

EMDF Characterization Project Oak Ridge, TN	**BOREHOLE LOG**	Boring Number GW-981

Remarks: Borehole installed for the collection of geotech samples and installation of shallow piezometer.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
21	NS			Based on C-1 recovery, contact with overlying saprolite is above 23.0'.		End 2/23/18, 1536 at 20.5'. Begin 2/24/18, 0915. 0900 Augers measured dry.	
22							
23				Change at 23.0'.			
24	C-1	2.0' 100%	0%	Interbedded dark reddish gray to weak red/dusky red (2.5YR 4/1, 4/2 - 3/2) SHALE and dark gray to very dark gray (N 4/ - N 3/) LIMESTONE to calcareous SILTSTONE. Thinly bedded, generally less than 0.1' intervals, partings are not uncommon. Bedding angle is approximately 45°. Limestone beds are generally less than 1/2" thick and have wavey deformed bedding contacts, comprises approximately 40% of formation. Fresh, no indication of weathering. Limestone beds are hard (strong) and shale beds are soft (very weak to weak). Moderate to intensely fractured. Trace glauconite partings and thin seams.		Trace (rare) calcite filled/healed fractures below 26.0'. Very thin, less than 1 mm to hairline. Limestone reacts strongly to HCl, shale does not react. C-1: 23' - 25.0' 0930-0941. Top of C-2 run 25.0' - 25.4' is highly broken, probable mechanical. Mechanical breaks along bedding planes are common. C-2: 25.0' - 30.0' 0959-1015. 25.4' - 26.3 High angle fracture, jagged/rough face. Trace secondary calcite and possibly celestite. 25.9' - 26.0' Limestone seam fractured roughly 90° to bedding. Trace glauconite nodules (<1 mm).	
25							
26				24.0' - 24.9' Broken zone, fractures oriented perpendicular to bedding (possibly associated with healed fractures where the calcite infilling has been removed). Trace thin secondary calcite on fracture faces.			
27	C-2	5.0' 100%	39%	25.5' - 26.7' Bedding is horizontal. Becomes very deformed from 26.4' - 26.7'. Possible breaks near top and bottom of zone. Below zone 26.7' - 27.0' bedding transitions back to 45° angle.			
28							
29				27.0' - 27.2' Calcite filled fracture along bedding plane. Face is striated. No oxidation. May be healed. Possibly depositional slump (slickensides).			
30				At 27.7' 1/2" glauconitic seam.			
31				28.1' - 28.4' Broken zone. Appears mechanical, but there is no obvious change in rock to explain breakage. Several slickenside surfaces (not all appear oriented with bedding). No apparent secondary mineralization.		At 27.4' bedding break, face has slickensides. Trace calcite and pyrite on face.	
32	NS			Below 28.7' all breaks appear mechanical. Trace very fine mica on some of the mechanical breaks.		Finished coring at 1015, 2/24/18. Overdrilled corehole with HSA and advanced borehole to 33.5'. End 2/24/18, 1113 at 33.5'. 2/26/18, 0921, WL = 14.77'. Finished drilling 2/26/18 at 0955, advanced borehole to 34.0'.	
33							
34				Bottom of Borehole = 34.0'.		2/24/18 at 1247 WL = 12.0'.	
35				Piezometer GW-981 installed in borehole. See Monitoring Well Installation Report GW-981 for details.			
36							
37							
38							
39							
40							
41							
42							
43							
44							

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.

Well Number GW-981

Monitoring Well Installation Report

Site Name and Location: *EMDF Characterization Project, Oak Ridge, TN*	Completion Date: *3/8/18*
Coordinates: *30396.70N 38148.33E*	Borehole Depth (ft): *34.0*
Elevation Top of Casing (ft/MSL): *965.74*	Borehole Diameter (in):*7 1/2"*
Elevation Ground Surface (ft/MSL): *963.2*	Drilling Methods: *4 1/4" ID HSA, HQ3 Core with water.*
Installed By: *Shannon Snow/Tri-State Drilling*	Completed Drilling: *2/26/18*
Supervised By: *David J. Sugar/Eagon & Associates, Inc.*	Drilling Water Used (gals): *~500*

Well Design

Component	Materials	Depth (LSD)	Elevation
Well Protector	4" Square Steel w/Locking Lid	-2.8 - 2.2	966.0 - 961.0
Riser	2" ID Schedule 40 PVC	-2.5 - 22.1	965.7 - 941.1
Surface Seal	3' x 3' Concrete	-0.5 - 0.5	963.7 - 962.7
Cement Grout	Cement Bentonite Grout	0.5 - 17.9	962.7 - 945.3
Bentonite Seal	Pel-Plug 1/4" Coated Bentonite Pellets	17.9 - 20.0	945.3 - 943.2
Sand Pack	DSI "GP #2" Gravel Pack	20.0 - 33.4	943.2 - 929.8
Screen	2" ID Schedule 40 PVC, 10-Slot	22.1 - 32.1	941.1 - 931.1
Well Point Blank	2" ID Sch. 40 PVC Cap & Riser Section	32.1 - 33.4	931.1 - 929.8
Sand Pack Bottom	DSI "GP #2" Gravel Pack	33.4 - 34.0	929.8 - 929.2


Well Development

Well Depth (ft,TOC):	Depth to Water (ft,TOC):	Well Volume (gals):	Volume Purged (gals):
35.85	*22.20*	*2.2*	*89.0*

Development Method:
Bailer, surge block, Tornado pump

Date	Time	Cumulative Volume Removed (gals)	Temp (°C)	Specific Conductivity (µmhos/cm)	pH (S.U.)	Turbidity (NTU)
3/2/18	1655	15	15.2	322.7	8.14	>1000
3/3/18	1224	25	14.8	271.9	8.50	>1000
3/5/18	1624	60.5	14.8	302.0	7.99	185.0
3/6/18	1550	82.0	15.2	257.9	7.88	163.0
3/6/18	1553	85.0	15.5	271.8	7.90	-
3/6/18	1632	88.0	15.1	255.2	7.79	153.0


Recovery Data



Sampling Equipment:

Comments:

Grout mixing and placement information provided by Tri-State Drilling. Screen slot interval 22.3 - 32.0 bgs.



Boring depth=34.0 ft.

MONITOR WELL INSTALLATION 2 OAK RIDGE .GPJ EAGON.GDT 4/4/18

This page intentionally left blank.

Eagon & Associates, Inc.

BOREHOLE LOG

Site Name and Location: **EMDF Characterization Project Oak Ridge, TN**	Drilling Methods: 3 1/4" ID HSA, HQ3 Core with water circulation, 10" air hammer bit, 5 7/8" tricone bit with air/water.				Boring Number: GW-982
Drilling Firm: *Tri-State Drilling*	DATE	TIME	DEPTH DRILLED (ft)	WATER LEVEL (ft)	
Driller / Rig: *Shannon Snow/CME-550*					*Page 1 of 6*
Logged by: *David J. Sugar*	Sampling Methods: ST = Shelby Tube; WS = Waxed Sample; SP = Sand Pump; GP or DP = Direct Push; CT = Cuttings; SS = Split Spoon; CS = Continuous Sampler; C = Coring; NS = Not Sampled; B = Bailer				Start: *Time 1135, Date 2/7/18* / Finish: *Time 0945, Date 2/18/18*
Coordinates: *30317.82N 38617.04E*					
Surface Elevation: *1,015.6 ft/MSL*					
Surface Conditions / Weather: *Gravel road bed, relatively flat, moist / Overcast, ~45°F*					

Remarks:

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
1	NS			Gravel road bed. Topsoil removed during road construction. Change at 1.2'.		3 1/4" ID HSA, 7 1/2" OD. Continuous 2" OD, 2' drive split spoons, 140 lb automatic hammer. Ran center bit while augering to sample depth. On 2/15/18 used Intersoll-Rand T3W rotary rig to ream borehole to 50.3' using 10 air hammer bit and set permanent 10" PVC casing. Casing sealed with cement bentonite grout.	
2	SS-1	0.8' 100%	1, 4	Brown to yellowish brown (10YR 5/3 - 5/6) SANDY SILT to SILT. Trace clay. Trace to some gravel size (fine to coarse) shale fragments, angular, increasing content with increasing depth. Unsorted, jumbled fabric. Does not appear to have preferred orientation. Becomes mottled near lower contact. Low plasticity. Low toughness. Low dry strength. Rapid dilatancy. Very stiff. Moist. Weathered. SOIL/SUBSOIL. Change at 2.5'.		1.2' - 1.6' Trace roots. No reaction with HCl.	ML
3	SS-2	1.85' 92.5%	6 11 15 21			SS-2 Lab results: Moisture Content (MC) 11%.	CL
4				Light yellowish brown (2.5Y 6/3 - 6/4) and light olive brown (2.5Y 5/3 - 5/6) highly weathered to completely weathered SHALE (SAPROLITE). Shale structure is intact, does not appear disturbed. Thinly bedded (generally less than 1/2"), 40°-50° bedding angle (disturbed by sampling process in some areas). Sample can be molded with hand pressure. Primarily clay to silty clay composition. Trace to few fine sand. High plasticity, toughness, and dry strength. No dilatancy with added water. Hard. Slightly moist to moist. Highly weathered. SAPROLITE.			
5	SS-3	1.35' 67.5%	12 20 29 39			SS-3 Lab results: MC 13.1%.	
6						SS-4 Lab results: MC 12.5%. No reaction with HCl.	
7	SS-4	2.0' 100%	28 38 44 48	At 6.9' and 8.0' - 8.4' Trace light gray incorporations and deformed partings. Fine sandstone/silty sandstone partings and/or incorporations.		Trace dark brown/reddish brown to black iron and manganese oxide precipitates follow fracture plates and bedding breaks. Fracture traces are generally not well defined or difficult to follow over distance.	
8							
9	SS-5	2.0' 100%	28 56 71 60	Bedding angle appears to be fairly consistent, between 40° to 50° and continues to be thinly bedded.		SS-5 Lab results: MC 12.3%; 2.2% Gravel; 47% Sand; 50.8% Fines.	
10						4.2' - 4.4' High angle fracture with iron oxide coating.	
11	SS-6	1.7' 85%	10 32 41 48	Below 10.0' dark brown/black manganese oxide deposition increases, continues to be associated with bedding breaks and fractures oriented perpendicular to bedding. Traces are generally not well developed or destroyed by the sampling process.		Below 5.1' increase in black to dark brown iron/manganese oxide, generally 0.2' to 0.3' intervals.	
12						Sample continues to be broken at intervals less than 1/2".	
13	SS-7	2.0' 100%	12 18 20 26	12.1' - 14.4' Zone with mottling, dark brown/black iron/manganese oxide and light gray/greenish gray inclusions or irregular partings (deformed sandy zones). 13.5' - 13.8' Zone with very high clay content, light yellowish brown and olive gray (weak mottled appearance). Rock structure is not prominent. Moist.		12.1' - 14.4' Slightly higher moisture content, still moist with no visible water.	
14							
15	SS-8	1.75' 87.5%	11 23 33 68	14.6' - 15.0' Dark gray brown to black sandy zone, probable fine silty sandstone or sandy siltstone remnant. May be a highly weathered glauconite bed.		0.0' - 20.0' No indication of water. Sample is consistently slightly moist to moist. No free water observed on drill rods or sampler.	
16							
17	SS-9	2.0' 100%	29 66 89 80/4	Below 16.5', trace reddish brown iron oxide, less manganese oxide.		SS-8 Lab results: MC 13.9%; 4.8% Gravel; 65.9% Sand; 29.3% Fines.	
18						SS-10 Lab results: MC 10.8%. Becoming difficult to mold sample. Gravel/sand sized rock fragments within molded sample.	
19	SS-10	2.0 100%	41 42 71 100	18.4' - 19.0' Dark brownish gray to black seams, not well defined, sandy saprolite.		No reaction with HCl.	

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

EMDF Characterization Project
Oak Ridge, TN

BOREHOLE LOG

Boring Number GW-982

Remarks:

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
21	SS-11	1.5	62 100/5	Light yellowish brown (2.5Y 6/3 - 6/4) and light olive brown (2.5Y 5/3 - 5/6) highly weathered SHALE (SAPROLITE). (Cont'd.)		No reaction with HCl. SS-11, SS-12, SS-13, and SS-14 greater recovery than, all looked in-place. Slightly less weathered, becoming more competent. Still appears to be saprolite. Continues to be thinly bedded, broken <0.05' (1/2"). Sampling process is altering/disturbing the rock structure.	CL
22	NS						
23	SS-12	1.4	30 38 50/1	Below 19.0' trace (light) reddish brown and black iron oxide and manganese oxide.			
24	NS						
25	SS-13	1.4	20 71 73/2	Below 24.0' iron oxide not apparent, considerable dark brownish gray to black manganese oxide. Trace to few sand, probably associated with sandy partings and seams.		SS-13 Lab results: MC 11.9%. End 2/7/18, 1440, at 27.0' while augering below 26.0', stopped to repair a hydraulic line on the drill rig. 2/7/18, 1610 Borehole measured dry.	
26	NS						
27	SS-14	1.0	37 50/2				
28	NS					2/8/18 Borehole sounded dry at 0808. 0900 Start augering below 26.0'. No reaction with HCl.	
29	SS-15	1.35	63 100/5				
30	NS			Difficult to mold sample with added water, becoming more competent with depth. High plasticity, toughness, and dry strength. Continues to be highly weathered shale (saprolite). Dry to slightly moist.		Below 28.0' sample is generally disturbed from sample process. Bedding appears to still be in the range of 40° - 50°.	
31	SS-16	0.8	100			SS-16 Lab results: MC 4.7%.	
32	NS						
33	SS-17	1.0	82 100/4				
34	NS						
35	SS-18	1.1	32 100/6			SS-18 Lab results: MC 8.9%.	
36	NS						
37	SS-19	1.8	41 65 70 55	Below 36.0' slightly higher degree of weathering. Continues to be highly weathered shale, saprolite. Continues to have trace manganese oxide, bedding is mostly disturbed by the sampling process.			
38	SS-20	1.6	32 84 100/5				
39	NS						
40	SS-21	1.3	40 100/5			SS-21 Lab results: MC 7%; 14.7% Gravel; 56.8% Sand; 28.5% Fines.	
41	NS						
42	SS-22	1.0	28 100/4				
43	NS						
44	SS-23	1.0	60 100/3	Trace iron and manganese oxide. Sample continues to be mostly pulverized/broken from the sampling process.		Continues to be dry to slightly moist. No reaction with HCl. SS-23 Lab results: MC 5.5%.	

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

EMDF Characterization Project
Oak Ridge, TN

BOREHOLE LOG

Boring Number GW-982

Remarks:

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
46	NS			Light yellowish brown (2.5Y 6/3 - 6/4) and light olive brown (2.5Y 5/3 - 5/6) highly weathered SHALE (SAPROLITE). (Cont'd.)		No indication of water on drilling rods or sampler to 47.3'.	CL
	SS-24	0.2	50/1	Trace calcite appears to be 1 to 5 mm fracture infilling. Sample is pulverized.		SS-24 Strong reaction with HCl.	
47	NS			Change at 47.3'.			
48	C-1	1.5' 32%	0%	Olive gray to dark olive gray (5Y 4/2 - 3/2) and gray dark gray (5Y 5/1 - 4/1) SHALE and LIMESTONE. Limestone beds appear silty in places and may classify as a calcareous siltstone. Thinly bedded, sample is very broken (40° bedding angle). Trace white calcite veins (up to 5 mm). Trace black and brownish yellow iron/manganese oxide precipitate along bedding breaks and possible fractures. Gray-grayish beds are limestone. Olive colored beds are generally shale. Highly weathered. Moderate to very strong strength. Most of the lost recovery is expected to be within shale beds that have low field strength. C-1 recovery, bottom piece has reddish brown interbeds (<0.05'). Beds appear deformed with slight displacement along healed fractures (white calcite in-fill). Bottom of recovery has a fracture face that is perpendicular to bedding.		1128, 2/8/18, Auger refusal at 47.3'. 1308 Borehole measured dry at 46.2'. Set up to core. Set temporary 4 1/2" steel flush threaded casing, HQ3 core, water circulation. 1425 Start washing core bit to depth. C-1 47.3' - 52.0' 1450-1536. Cannot position C-1 core loss, sample is too broken. No reaction with HCl within shale, strong reaction with calcite fracture infilling and within limestone beds.	
52	C-2	2.8' 100%	0%	Below 52.0' higher percentage of shale, mostly shale. Limestone beds generally have calcite veins or healed fractures. Continues to be highly weathered. Predominate olive gray to dark olive color. Trace thin limestone interbeds below 54.1'.		C-2 Run, fractured throughout, faces are coated with iron and/or manganese oxide. C-2 52.0' - 54.8' 1555-1655. C-3 54.8' - 55.8' 1710-1730.	
55	C-3	1.0' 100%	0%			End 2/8/18, 1730 at 55.8'. Water level at 10.1', 1745 most if not all drilling water was recirculated during drilling.	
56	C-4	1.1' 92%	0%	Below 55.8 slight increase in brown color. Some dark olive gray to olive gray (5Y 4/2 - 3/2). Primarily shale or mudstone composition. Bedding angle is approximately 40°. Continues to be thinly bedded with limestone partings and thin seams (<0.05'). Moderate field strength. Limestone layers are strong to very strong. Moderately decomposed/weathered.		Begin 2/9/18 0830, driller changing out bit style, HQ3 still. Start coring at 0955. 0840, WL: 16.82 from GS. No reaction with HCl. Continues to be highly fractured with iron oxide precipitates on fracture faces. Breaks along bedding planes and angular fractures. Intensely to moderately fractured. Sample is generally very broken and fracture orientation and fracture traces are hard to follow.	
57	C-5	2.7' 54%	0%	Below 57.4' Trace to few dark greenish gray to very dark greenish gray (5GY 4/1 - 3/1) layers. Becoming less weathered. Stronger olive color associated with weathered areas. Core is very broken from 58.0' - 59.7'. Lost core probably from bottom of run. Below 58.4' limestone interbeds are deformed (soft sediment) irregular surfaces and thickness, generally less than 0.1' thick. Near 59.7', trace pink calcite, up to 5mm thick, appears to be fracture infilling.			
62	C-6	4.5' 90%	0%	Below 62.4' predominately dark gray to very dark gray (N 4/ - 3/) with trace olive gray/dark olive gray (5Y 4/2 - 3/2) zones associated with weathered areas. Trace gray (5Y 6/1 - 5/1) partings/thin limestone seams. Continues to be intensely fractured. 64.6' - 64.8', 65.2' - 65.4', 65.6' - 65.8' bedding plane fractures/breaks with iron oxide and trace calcite. 65.6' - 65.8' Fracture is polished (slickenside). 65.9' - 66.5' Recovery is very broken, some angular pieces with slickenside surfaces.		C-6 Run, bedding angle varies between 45° to 50° limestone seams are typically deformed and have wavy surfaces/contacts. 62.9' - 63.4' Oxidized bedding break, 3/4" olive gray weathering have faces coated with iron oxide. 63.6' - 64.0' Bedding break, calcite coating on face, no oxidation . Possible indication of saturation. Broken oxidized fractures above and below.	
67	C-7	2.3' 46%	0%	Below 67.0' primarily limestone and siltstone recovery. Few shale seams. Lost recovery (C-7 run) may be mostly shale. Highly broken interval, intensely fractured/broken. Fracture/bedding break faces are all oxidized with mostly iron oxide coatings; trace black manganese oxide. Mostly olive gray to dark olive gray (5Y 4/2 - 3/2). Some dark gray to very dark gray areas.		C-4 55.8' - 57.0' 0955-1010. C-5 57.0' - 62.0' 1018-1124. C-6 62.0' - 67.0' 1133-1220. C-7 67.0' - 72.0' 1429-1541.	
69							

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

EMDF Characterization Project
Oak Ridge, TN

BOREHOLE LOG

Boring Number GW-982

Remarks:

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
71	C-7	2.3' 46%	0%	Interbedded olive gray to dark olive gray (5Y 4/2 - 3/2), dark gray to very dark gray (N 4/ - 3/) SHALE and LIMESTONE. (Cont'd.) Trace to few limestone seams (<0.2' thick). 72.7' - 73.1', 0.15' Thick silty limestone seam. Strong reaction with HCl.		Lost recovery in C-7 run is assumed to be shale. Bedding angle is between 45° - 50°.	
72	C-8	1.2' 100%	0%	Highly fractured and broken. Generally has associated iron oxide coatings. Trace calcite precipitates.		Most of C-8 recovery is shale. C-8 72.0' - 73.2' 1555-1621.	
73				Change at 73.3'.		73.3' - 73.5; fracture oriented perpendicular to bedding. Face appears oxidized.	
74	C-9	3.8' 100%	16%	Dusky red (5R 3/3) OOLITIC LIMESTONE. Trace to few glauconite nodules (~1mm). Red color possibly associated with hematite. Massive. Field strength is strong, competent. Trace white calcite healed fractures. Fresh to slightly weathered. Change at 74.0'. Very dark gray to black (N 3/ - 2 1/2/) SHALE. Thinly bedded, ~45° - 50° angle. Trace gray ~1mm siltstone partings. Fresh. Intensely fractured or broken, mostly along bedding planes (some may be mechanical). Unweathered/no oxidation. Below 77.0' bedding angle is between 55° - 60°. Moderately to intensely fractured.		End 2/9/18, 0710 at 77.0' WL at 1724 = 23.72' from ground. C-9 73.2' - 77.0' 1633-1710. 2/10/18, 0805, WL = 63.0'. Begin 2/10/18, 0830, 45°F, overcast, tract light rain. Continue HQ core, using core barrel liner.	
77	C-10	2.9' 100%	35%	77.0' - 77.3' Bedding break, slickenside surface. No weathering or precipitates. 77.7' - 77.9' Bedding break surface has white noncarbonate precipitate, trace fine (<1mm) pyrite. Slickenside surface. 77.9' - 78.2' Bedding break, slightly polished surface. Trace thin (<1mm) calcite and clay (maybe from drilling) on face. No oxidation. Maybe open. 79.0' - 79.3' Set of bedding breaks, polished (slickenside) surfaces. Within interval, perpendicular fracture appears healed with white noncarbonate infilling (hairline). Change at 79.9'.		C-10 77.0' - 79.9' 0833-0920. Broken zones are identified fractures in C-10 interval appear to be mechanical, probably associated with wedging and difficulty with sample. Feeding, typically core wear indicates core was turning. Bottom of C-10 recovery mechanically fractured (broken), bit plugged at end of run. End 2/10/18, 1004, rain, at 80.2'.	
80	C-11	1.5' 71%	0%	Interbedded gray to very dark gray (N5/ to N3/) SHALE and LIMESTONE. Thinly bedded, generally between 0.1' - 0.3'. Limestone and shale partings are common. Shale beds are typically darker gray and soft while limestone beds are lighter gray and hard. Bedding appears to vary between 50° to 60°. Trace healed fractures, while calcite filled, generally oriented perpendicular to bedding, hairline to 2 mm width. Unweathered to slightly weathered (fresh). Mostly shale, 20 - 30% limestone.		Begin 2/12/18, 0920 continue C-11 run. 0907 WL = 35.05' from GS. 45°F, Overcast, wet. C-11 Run, lost recovery mostly from bottom of run. ~55° - 60° bedding angle At 81.4' fracture at 90° to bedding, iron oxide on face. Adjacent rock is not oxidized. 83.1' - 83.5' Broken zone, probable fracture or fractures, no oxidation. 83.3' - 83.5' 1/4" to 1/2" thick pink calcite filled fracture. 84.7' - 84.9' Set of fractures 45° to bedding angle, surfaces have slickensides. No precipitate or oxidation. C-11 79.9' - 82.0' 0920-0935. C-12 ~50° bedding angle.	
82	C-12	4.2' 84%	38%	Below 82.0' primarily shale, trace lighter (gray) limestone or siltstone partings (<1/4"). 85.0' - 85.9' Bluish gray to dark bluish gray (5PB 5/1 to 4/1) Interclastic Limestone Seam - elongated elliptical, clasts oriented parallel with bedding (long axis), up to 1" high and 1 3/4" wide. 45° - 50° bedding angle. Hard, unweathered except for lower contact which is oxidized yellowish brown. Trace fine (<1 mm) glauconite nodules.			
87	C-13	3.2' 64%	35%	Below 87.8' becomes interbedded limestone and shale, thinly bedded, somewhat deformed. Trace glauconitic beds/partings. Change at 87.8'. Bluish gray to dark bluish gray (5PB 5/1 - 4/1) LIMESTONE. Fine grained. Few 1 mm or less glauconite nodules. Trace stylolites, dark gray to black, jagged, trace. Thinly bedded. Fresh. Basal contact has rip up clasts, elliptical and elongated with bedding. Becoming interclastic. Change at 89.5'. Interbedded very dark gray to black (N 3/ - N 2 1/2) SHALE and gray to dark gray (N 5/ - 4/) LIMESTONE. Generally thinly bedded (0.1' or less). Trace white calcite filled fractures (healed). Limestone seams are generally deformed, wavey, uneven bedding. Fresh, no oxidation. Intensely broken along bedding planes, most are mechanical. Limestone is hard to moderately hard. Shale is soft. 92.0' - 93.7' Predominately shale, trace limestone partings.		At 87.8' oxidized (iron oxide) bedding contact. Strong reaction with HCl. At 88.0' fracture, 45° to bedding, oxidized (iron oxide on face). Limestone reacts strong with HCl. Shale has no reaction. 92.0' - 92.3', 93.1' - 93.4', and 93.4' - 93.7' Bedding plane breaks, slickenside surface. No oxidation or precipitates.	
92	C-14	4.0' 100%	10%	Below 93.7' trace bioturbation.		92.85' - 92.95' ~45° fracture, slickenside surface. No oxidation or precipitates. 45° - 50° Bedding angle. C-12 82.0' - 87.0' 1044-1105. C-13 87.0' - 92.0' 1140-1159.	

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

EMDF Characterization Project
Oak Ridge, TN

BOREHOLE LOG

Boring Number GW-982

Remarks:

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
96	C-14	4.0' 100%	10%	Interbedded very dark gray to black (N 3/ - N 2 1/2) SHALE and gray to very dark gray (N 5/ - 4/) LIMESTONE. (Cont'd.)		C-14 92.0' - 95.9' 1342-1356. C-15 95.9' - 97.0' 1436-1445. C-16 97.0' - 98.2' 1451-1505. C-17 98.2' - 102.0' 1524-1545.	
97	C-15	0.6' 55%	46%	95.9' - 96.5' Bluish gray to dark bluish gray (5PB 5/1 - 4/1) Interclastic LIMESTONE. Clasts up to 0.2', generally less than 0.1', elongated and elliptical. Clasts oriented parallel with bedding. Hard. Fresh.			
98	C-16	0.7' 58%	0%	Change at 98.9'.		C-16 Run highly broken, fractured faces with slickenside surfaces, too broken to determine position. No oxidation or precipitation.	
99	C-17	3.1' 81%	33%	Bluish gray to dark bluish gray (5PB 5/1 - 4/1) LIMESTONE. Fine crystalline. Trace glauconite nodules (up to 1mm). Trace stylolites. Fresh, unweathered. Hard. Trace pyrite.		Strong reaction with HCl. 99.6' - 99.8' and 100.0' - 100.3' bedding breaks, no oxidation or precipitates.	
100				98.5' - 98.9' Rip up clasts or deformation, up to 0.1' diameter, elongated. Change at 100.6'.			
101				Interbedded very dark gray to black (N 3/ - N 2 1/2) SHALE and gray to very dark gray (N 5/ - 4/) LIMESTONE. Thinly bedded. Shale is soft, limestone is hard. Generally fresh, unweathered. Limestone beds are generally thin (<0.1' thick). Shale beds are up to 0.3' thick. Limestone is hard, fresh, unweathered. Shale is soft, fresh, unweathered. 20 to 40% limestone. Continues to be intensely fractured. Bedding angle is near 45°.		Shale does not react with HCl. Limestone has a strong reaction. 45-50° Bedding angle.	
102	C-18	1.2' 31%	0%	102.0' - 102.3' Fracture zone/bedding breaks. Faces are oxidized with iron oxide coatings.		C-18 Recovery is poor, appears to have started run in a fracture zone cannot position lost recovery interval.	
103							
104						C-18 102.0' - 105.9' 1617-1649.	
105				Trace very dark greenish gray (10GY 3/1) thin seams, less than 0.1' thick, possibly glauconitic.		C-19 105.9' - 106.8' 1705-1710. C-20 106.8' - 107.0' 1720-1722.	
106	C-19	0.8' 89%	0%	Bedding angle ~45°.		C-21 107.0' - 108.3 0847-0900.	
107	C-20	0.2	0%			End 2/12/18, 1720 at 107.0'. 1730 WL = 14.02' from GS. Begin 2/13/18, 0847, 40°F, overcast, light rain. 2/13/18, 0830 WL = 21.65' GS.	
108	C-21	1.3' 100%	0%	107.6' - 107.9' Fracture 90° to bedding plane. Face has thin coating of calcite. No oxidation.			
109	C-22	0.9' 100%	40%	Underlying contact is relatively sharp color change. Change at 109.2'.		Continues to be intensely fractured. Most bedding breaks have slickenside surfaces. No oxidation or weathering.	
110	C-23	2.8' 100%	22%	Dark reddish gray (2.5YR 3/1 - 4/1) SHALE. Trace gray to very dark gray shale partings (generally <2mm). Soft. Thinly bedded, 40-45° angle, beds generally <0.1'. Fresh, unweathered. Moderately fractured. Breaks appear to be mechanical. Trace glauconitic partings (greenish color, no reaction with HCl.)		No reaction with HCl. 109.9' - 110.1'. 110.1' - 110.3' Bedding break with gray precipitate/clay on face.	
111						Below 110.5' broken along bedding contacts at 0.3' to 0.4' intervals. Face of break has slickensides, no oxidation or precipitates/mineralization.	
112				Change at 112.0'.		Most if not all breaks below 112' appear mechanical.	
113	C-24	4.9' 98%	54%	Interbedded very dark gray to black (N 3/1 - N 2-1/2/) and dark reddish gray (2.5YR 3/1 - 4/1) SHALE and LIMESTONE. Noticeable change to reddish color hues. Thinly bedded, color variation, highlights thinly bedded character. Limestone beds typically have stronger gray color hues, are hard and react strongly with HCl. Shale beds are soft, generally have stronger red color hues. Bedding is generally 0.1' or less, partings are common. Bedding contacts are generally wavy, have a deformed appearance. May in part be due to bioturbation. Beds or partings with green color hues are also present, appear to be glauconitic. Unweathered/fresh. Commonly broken along bedding, but generally attributed to mechanical breaks.		Trace slickenside surfaces, but no oxidation or mineralization observed. Possibly depositional.	
114							
115							
116				112.4' - 112.6' Limestone seam. Trace fine glauconite nodules, trace rare pyrite.		C-22 108.3' - 109.2' 0913-0920.	
117				Below 113.5' thinly bedded. Limestone and shale beds are generally 0.1' or less. Limestone beds are hard, typically gray to dark gray and shale beds are reddish gray, soft. Most limestone beds have deformed upper and lower surfaces, convoluted bedding.		C-23 109.2' - 112.0' 0934-0951.	
118	C-25	5.0' 100%	63%			C-24 112.0' - 117.0' 1000-1022.	
119						C-25 117.0' - 122.0' 1033-1048.	

BOREHOLE LOG V.2 OAK RIDGE.GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

EMDF Characterization Project Oak Ridge, TN	**BOREHOLE LOG**	Boring Number GW-982

Remarks:

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
121	C-25	5.0' 100%	63%	Interbedded dark reddish gray (2.5YR 3/1 - 4/1) SHALE and gray to very dark gray (N 3/ - N 2 1/2/) LIMESTONE. Thinly bedded. (Cont'd.)		Unweathered. Core breaks are along bedding planes. Most if not all appear mechanical.	
122							
123							
124	NS						
125							
126							
127				Bottom of Borehole = 126.5'. Piezometer GW-982 installed in borehole. See Monitoring Well Installation Report GW-982 for details.		2/13/18, 1156 WL = above GS. Probably drilling water. 2/13/18 1247 WL = 12.51'. 1250 Start pulling drill rods. 1320 Drill rods removed. 1326 WL = 33.43' GS. On 2/18/18 used Intersoll Rand T3W rotary rig to ream corehole and advance borehole to 126.5' using 5 7/8" tricone bit with air and water circulation. Finished drilling at 0945.	
128							
129							
130							
131							
132							
133							
134							
135							
136							
137							
138							
139							
140							
141							
142							
143							
144							

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.


Well Number GW-982

Monitoring Well Installation Report

Site Name and Location: *EMDF Characterization Project, Oak Ridge, TN*	Completion Date: *3/8/18*
Coordinates: *30317.82N 38617.04E*	Borehole Depth (ft): *126.5*
Elevation Top of Casing (ft/MSL): *1,018.02*	Borehole Diameter (in):*10" (0'-50.3'); 5 7/8" (50.3'-126.5')*
Elevation Ground Surface (ft/MSL): *1,015.6*	Drilling Methods: *3 1/4" ID HSA, HQ3 Core with water circulation, 10" air hammer bit, 5 7/8" tricone bit with air/water.*
Installed By: *Shannon Snow/Tri-State Drilling*	Completed Drilling: *2/18/18*
Supervised By: *David J. Sugar/Eagon & Associates, Inc.*	Drilling Water Used (gals): *~2000*

Well Design

Component	Materials	Depth (LSD)	Elevation
Well Protector	4" Square Steel w/Locking Lid	-2.7 - 2.3	1018.3 - 1013.3
Riser	2" ID Schedule 40 PVC	-2.4 - 102.1	1018.0 - 913.5
Surface Seal	3' x 3' Concrete	-0.5 - 0.5	1016.1 - 1015.1
Conductor Casing	6" ID Sch. 40 PVC, Flush Threaded	-0.4 - 50.3	1016.0 - 965.3
Cement Grout	Cement Bentonite Grout	0.5 - 95.9	1015.1 - 919.7
Bentonite Seal	Pel-Plug 1/4" Coated Bentonite Pellets	95.9 - 99.2	919.7 - 916.4
Sand Pack	DSI GP #2 Gravel Pack	99.2 - 113.4	916.4 - 902.2
Screen	2" ID Schedule 40 PVC, 10-Slot	102.1 - 112.1	913.5 - 903.5
Well Point Blank	2" ID Sch. 40 PVC Cap & Riser Section	112.1 - 113.4	903.5 - 902.2
Sand Pack Bottom	DSI GP #2 Gravel Pack	113.4 - 114.5	902.2 - 901.1
Bentonite Seal	Pel-Plug 1/4" Coated Bentonite Pellets	114.5 - 126.5	901.1 - 889.1




Well Development

Well Depth (ft,TOC):	Depth to Water (ft,TOC):	Well Volume (gals):	Volume Purged (gals):
115.82	*66.39*	*8*	*64.5*

Development Method:
Surge block, bailer, Tornado pump, bladder pump

Date	Time	Cumulative Volume Removed (gals)	Temp (°C)	Specific Conductivity (µmhos/cm)	pH (S.U.)	Turbidity (NTU)
3/3/18	0858	39.0	12.2	374	10.38	41.0
3/3/18	1408	50.0	15.8	354.3	9.35	24.8
3/5/18	0837	51.0	12.7	414.2	8.37	397.0
3/5/18	1257	61.5	15.1	359.9	9.17	29.0
3/5/18	1415	63.5	15.3	391.2	8.92	21.0
3/5/18	1455	64.5	14.5	395.6	8.87	17.5

Recovery Data



Sampling Equipment:

Comments:

Stainless steel centralizers set at 95.0' and 45.0'. Washed sand pack and pellets in using tremie pipe. Grout mixing and placement information provided by Tri-State Drilling. Screen slot interval 102.3 - 112.0 bgs.

MONITOR WELL INSTALLATION 2 OAK RIDGE.GPJ EAGON.GDT 4/4/18

This page intentionally left blank.

Eagon & Associates, Inc.

BOREHOLE LOG

Site Name and Location: **EMDF Characterization Project Oak Ridge, TN**	Drilling Methods: 4 1/4" ID HSA, HQ3 Core with water circulation, 5 7/8" hammer bit.				Boring Number: GW-983
Drilling Firm: *Tri-State Drilling*	DATE	TIME	DEPTH DRILLED (ft)	WATER LEVEL (ft)	
Driller / Rig: *Shannon Snow/CME-550*					*Page 1 of 4*
Logged by: *David J. Sugar*	Sampling Methods:				Start / Finish
Coordinates: *30325.62N 38606.49E*	ST = Shelby Tube; WS = Waxed Sample; SP = Sand Pump; GP or DP = Direct Push; CT = Cuttings; SS = Split Spoon; CS = Continuous Sampler; C = Coring; NS = Not Sampled; B = Bailer				Time: 1030 / 1257
Surface Elevation: *1,015.6 ft/MSL*					Date: 2/21/18 / 2/27/18
Surface Conditions / Weather: *Flat, gravel road bed / 74°F, Mostly sunny*					

Remarks: Borehole installed for the collection of geotech samples and installation of shallow piezometer.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
1–2	NS			See adjacent Borehole Log GW-982 for detailed lithologic description and stratigraphic interpretation.		Ran 4 1/4" ID HSA, ran center bit while augering.	
3–4	ST-1	1.7	1200 PSI	Description from bottom of ST-1. Brown to yellowish brown (10YR 5/3 - 5/6) SANDY SILT. Trace little clay. Mostly gravel size rock (shale) fragments, appears in-place, highly (completely) weathered shale. Slightly moist.		Auger cutting Bucket Sample BS-1 collected from 4.0' to 6.5'.	
5–8						Auger cutting Bucket Sample BS-2 collected from 6.5' to 8.5'.	
9–11						Cutting returns are slightly moist to moist.	
12	NS						
13–18							
19						Cutting returns are slightly moist to dry.	

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

EMDF Characterization Project Oak Ridge, TN	**BOREHOLE LOG**	Boring Number GW-983

Remarks: Borehole installed for the collection of geotech samples and installation of shallow piezometer.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
21				Augered without sampling, see adjacent Borehole Log GW-982 for detailed stratigraphic interpretation.		No indication of water with cutting returns.	
22							
23						End 2/21/18 at 23.5', 1700.	
24				Cutting returns are damp (slightly moist) to dry. Augered relatively smooth and consistent.		Begin 2/22/18, 0855. Borehole measured dry.	
25							
26						Auger cuttings continue to be slightly moist to dry.	
27							
28							
29							
30							
31							
32	NS						
33							
34							
35							
36							
37							
38							
39							
40							
41							
42						No indication of water in cutting returns (damp to dry) to 45.0'.	
43							
44				At 45.0' augered hard and rough, probable limestone or siltstone seam.		Below 45.0' switch over to HQ3 core, water circulation.	

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.

EMDF Characterization Project Oak Ridge, TN	**BOREHOLE LOG**	Boring Number GW-983

Remarks: Borehole installed for the collection of geotech samples and installation of shallow piezometer.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
46	C-1	3.7	0%	Interbedded olive gray to dark olive gray to olive (5Y 4/2 - 4/3 and 3/2) SHALE and LIMESTONE to CALCAREOUS SILTSTONE. Limestone seams have stronger gray color hues (5Y 4/1 - 4/2). Thinly bedded, generally less than 0.2' beds, with common partings and seams less than 0.1' thick. Limestone content estimated at 30%. Shale seams are soft, moderately to highly decomposed. Limestone seams are hard, moderately decomposed. Considerable iron oxide precipitates/coatings along fractures (bedding breaks and fractures oriented perpendicular to bedding). Weathered bedrock. Limestone/calcareous siltstone beds react strong with HCl. Shale has no reaction with HCl.		HQ3 core, water circulation. C-1 45.0' - 49.3' 1047-1129. Highly fractured, broken along bedding planes and perpendicular to bedding. All fractures are oxidized with iron oxide/manganese oxide coatings. Approximate 45° bedding angle. Sample (core) is relatively broken. At 46.8' probable glauconitic seam ~ 1/4" - 1/2".	
47							
48							
49							
50	NS					Finished coring at 1129. WL = 1.98' at 1157, 2/21. Removed augers. On 2/27/18, Ingersoll-Rand T4 rotary rig reamed corehole and advanced borehole to 92.2' using 5 7/8" hammer bit.	
51							
52							
53							
54							
55							
56							
57							
58							
59							
60							
61							
62							
63							
64							
65							
66							
67							
68							
69							

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.

EMDF Characterization Project Oak Ridge, TN	**BOREHOLE LOG**	Boring Number GW-983

Remarks: Borehole installed for the collection of geotech samples and installation of shallow piezometer.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
71							
72							
73							
74							
75							
76							
77							
78							
79							
80						Driller noted borehole making water between 80' - 81'.	
81	NS						
82							
83							
84							
85							
86							
87							
88							
89							
90							
91							
92							
				Bottom of Borehole = 92.2'.		Finished drilling to 92.2' at 1257.	
93				Piezometer GW-983 installed in borehole. See Monitoring Well Installation Report GW-983 for details.			
94							

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.


Well Number GW-983

Monitoring Well Installation Report

Site Name and Location: *EMDF Characterization Project, Oak Ridge, TN*	Completion Date: *3/8/18*
Coordinates: *30325.62N 38606.49E*	Borehole Depth (ft): *92.2*
Elevation Top of Casing (ft/MSL): *1,018.07*	Borehole Diameter (in):*5 7/8" (0'-92.2')*
Elevation Ground Surface (ft/MSL): *1,015.6*	Drilling Methods: *4 1/4" ID HSA, HQ3 Core with water circulation, 5 7/8" hammer bit.*
Installed By: *Fred Reynolds/Tri-State Drilling*	Completed Drilling: *2/27/18*
Supervised By: *Shay Beanland/Eagon & Associates, Inc.*	Drilling Water Used (gals):

Well Design

Component	Materials	Depth (LSD)	Elevation
Well Protector	4" Square Steel Protector w/Locking Lid	-2.8 - 2.2	1018.4 - 1013.4
Riser	2" ID Schedule 40 PVC	-2.5 - 79.2	1018.1 - 936.4
Surface Seal	3' x 3' Concrete Pad	-0.5 - 0.5	1016.1 - 1015.1
Cement Grout	Cement Bentonite Grout	0.5 - 70.2	1015.1 - 945.4
Bentonite Seal	Pel Plug 1/4" Coated Bentonite Pellets	70.2 - 74.1	945.4 - 941.4
Sand Pack	DSI "GP #2" Gravel Pack	74.1 - 90.5	941.4 - 925.1
Screen	2" ID Schedule 40 PVC, 10-Slot	79.2 - 89.2	936.4 - 926.4
Well Point Blank	2" ID Sch. 40 PVC Cap & Riser Section	89.2 - 90.5	926.4 - 925.1
Sand Pack Bottom	DSI "GP #2" Gravel Pack	90.5 - 91.5	925.1 - 924.1
Natural Fill	Natural Fill	91.5 - 92.2	924.1 - 923.4




Well Development

Well Depth (ft,TOC):	Depth to Water (ft,TOC):	Well Volume (gals):	Volume Purged (gals):
92.99	*65.92*	*4.4*	*50.0*

Development Method:
Tornado pump

Date	Time	Cumulative Volume Removed (gals)	Temp (°C)	Specific Conductivity (µmhos/cm)	pH (S.U.)	Turbidity (NTU)
3/6/18	1059	5	14.4	402.6	7.21	127.0
3/6/18	1113	15	14.3	410.5	7.13	97.8
3/6/18	1126	25	14.3	408.4	7.11	44.2
3/6/18	1133	30	14.3	406.9	7.12	22.7
3/6/18	1139	35	14.2	406.5	7.12	14.7
3/6/18	1201	50	14.5	405.7	7.11	3.1

Recovery Data



Sampling Equipment:

Comments:

Stainless steel centralizers set at 69' and 34' from ground surface. Washed sand pack and pellets in using tremie pipe. Grout mixing and placement information provided by Tri-State Drilling. Screen slot interval 79.4 - 89.1 bgs.

MONITOR WELL INSTALLATION 2 OAK RIDGE .GPJ EAGON.GDT 4/4/18

This page intentionally left blank.

Eagon & Associates, Inc.

BOREHOLE LOG

Site Name and Location: **EMDF Characterization Project Oak Ridge, TN**	Drilling Methods: 3 1/4" ID HSA, HQ3 Core with water circulation, 10" air hammer bit, 5 7/8" tricone bit with air/water.		Boring Number: GW-986
Drilling Firm: *Tri-State Drilling*	DATE	TIME / DEPTH DRILLED (ft) / WATER LEVEL (ft)	
Driller / Rig: *Shannon Snow/CME-550*			*Page 1 of 3*
Logged by: *David J. Sugar*	Sampling Methods: ST = Shelby Tube; WS = Waxed Sample; SP = Sand Pump; GP or DP = Direct Push; CT = Cuttings; SS = Split Spoon; CS = Continuous Sampler; C = Coring; NS = Not Sampled; B = Bailer		Start: *Time 1050, Date 2/15/18* / Finish: *Time 1240, Date 2/20/18*
Coordinates: *30130.30N 38191.80E*			
Surface Elevation: *930.2 ft/MSL*			
Surface Conditions / Weather: *Flat gravel drilling pad / 57°F, Overcast*			

Remarks:

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
0	NS			GRAVEL. Road bed/drilling pad. Change at 1.0'.		3 1/4" ID HSA, ran center plug while augering. Continuous 2" OD, 2' drive split spoons. 140 lb automatic hammer.	
1	SS-1	0.0	3, 1	Brown to strong brown (7.5 YR 5/4, 5/6, 4/4 - 4/6) SILTY CLAY. Trace highly weathered shale and sandstone fragments, up to 1/2" diameter, subrounded to subangular. Unsorted, weak mottled appearance. Trace dark reddish brown to black manganese oxide/iron oxide. Trace roots. High plasticity and toughness. No dilatancy. High dry strength. Moist. Weathered. SUBSOIL.		No reaction with HCL.	CL
2	SS-2	1.6' 80%	2, 3, 4, 4			1.0' - 2.0' Sample tip blocked with root fragment. SS-2 Lab results: Moisture Content (MC) 20.4%. SS-3 Lab results: MC 21.1%. Underlying contact is sharp.	
4	SS-3	1.15' 57.5%	5, 4, 5, 4	Change at 6.0'.		On 2/19/18 used Ingersoll-Rand T3W rotary rig to ream borehole to 20.0' using 10" air hammer bit and set permanent 6" PVC casing. Casing sealed with cement bentonite grout.	
6	SS-4	1.8' 90%	3, 9, 19, 23	Light yellowish brown, olive yellow, and light olive brown (2.5Y 6/4 - 6/6 and 5/4 - 6/6) highly to completely weathered SHALE (SAPROLITE). Trace bluish gray (5G 6/1 - 10GY 6/1) and light greenish gray to light bluish gray (10Y 7/1 - 10GY 7/1) zones. Trace to few dark reddish brown to black iron/manganese oxide coatings, appear associated with fractures, but are difficult to follow. Sample is moldable with added water. Low to medium plasticity and toughness. Dry strength. No dilatancy. Thinly bedded. Very hard when classified as soil. Slightly moist to dry. Highly to completely weathered. SAPROLITE.		No reaction with HCl. Remnant bedding angle is approximately 45°.	ML
8	SS-5	2.0' 100%	39, 47, 51, 70			Possibly ML-CL in part. Carbonates leached from formation.	
10	SS-6	1.8' 90%	6, 24, 56, 100			SS-4 Lab results: MC 14.6%; 7.8% Gravel; 52.8% Sand; 39.4% Fines. SS-6 Lab results: MC 8.4%. SS-7 Lab results: MC 8.7%.	
12	SS-7	1.4' 70%	16, 52, 44, 84	Below 11.5' color is primarily bluish gray (5G 6/1 - 10GY 6/1) to light bluish gray/light greenish gray (10Y 7/1 - 10GY 7/1). Highly weathered. Transitioning into weathered bedrock with depth.		SS-8 No reaction with HCl. Trace wet on SS-8 sampler tip and within sample. SS-9 Lab results: MC 4.3%.	
14	SS-8	0.3'/100%	100/5	SS-8 recovery is wet.		After augering to 20.0' WL measured at 13.94' from GS at 1341 (1 hr. 31 mins after drilling stopped). WL = 10.85' at 1445, TD = 20.0'.	
15	NS			Underlying contact may be as high as 14.3'. Change at 16.0			
16	SS-9	1.3' 92.3%	21, 89, 100/4	Interbedded greenish gray to dark greenish gray (5BG 5/1 - 4/1 and 10BG 5/1 - 4/1) SHALE and LIMESTONE. Some limestone seams may classify as calcareous siltstone. Trace to some reddish brown iron oxide, associated with fractures with poorly defined trace. Structure is also lost with the sampling process. Soft to medium hard. Thinly bedded. Highly weathered. At least partially wet (SS-9 recovery, bottom of sample was moist, SS-10 recovery was wet).		SS-9 1.5' of split barrel was wet. 16.0' - 16.5' is wet.	
18	NS						
	SS-10	0.2'/100%	100/2			Strong reaction with HCL.	
19	NS					End 2/15/18, 1210, sampled to 18.2'. Augered to 20.0' on 2/17/18 and switch over to HQ3 core, water circulation.	

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

EMDF Characterization Project
Oak Ridge, TN

BOREHOLE LOG

Boring Number GW-986

Remarks:

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
21	C-1	1.3' 65%	0%	Interbedded dark gray to very dark gray (N 5/ - 4/) SHALE and gray to dark gray (N 4/ - N 3/) LIMESTONE. Thinly bedded, beds generally less than 0.2', partings and very thin seams <1/4". Trace, healed, calcite (white) filled (<2 mm) fractures oriented perpendicular to bedding. Medium hard to hard limestone. Field strength is moderate to strong, but core generally breaks easily along bedding contacts between shale and limestone beds. Soft shale. Generally fresh with oxidation on some broken bedding contacts. Highly fractured, but most appear to be bedding breaks. Mechanical breaks along bedding is common. Bedding is deformed, wavey contacts between beds. Some thin limestone beds have discontinuous beds. Trace bioturbidation along some bedding breaks.		Shale, no reaction with HCl. Limestone, strong reaction with HCl. Bedding angle is approximately 45° (very broken sample). Below 22.0' bedding angle is approx. 40°.	
22							
23						22.25' - 22.35, 22.7' - 22.85', and 22.9' - 23.05' Bedding breaks with reddish brown to yellowish brown oxidation on bedding plane. Iron oxide precipitate.	
24	C-2	2.3' 46%	0%			C-1 20.0' - 22.0' 1030-1040. C-2 22.0' - 27.0' 1058-1134.	
25						23.6' - 24.3' Highly broken gravel size fragments. Trace iron oxide faces.	
26							
27						C-2 Lost recovery, most likely from bottom of run.	
28	C-3	0.0' 0%	0%	C-3 Run, core barrel did not latch. No recovery.		C-3 27.0' - 32.0' 1157-1232. C-4 32.0' - 32.9' 0914-0930. C-5 32.9' - 34.6' 1010-1027. C-6 34.6' - 36.1' 1113-1119. C-3 and C-4 runs cutting returns were gray.	
29							
30							
31							
32	C-4	0.0' 0%	0%			End 2/17/18, 1232 at 32.0'. Stopped due to rain. Begin 2/18/18, 35°F, sunny, 0800. WL = 2.15' at 0801. Start coring at 0914.	
33	C-5	1.5' 88.2%	0%	Oxidation/weathering not observed below 33.0'. 33.0' - 33.2' Limestone seam. Unweathered.			
34				Below 34.6' approximately 50% limestone, 50% shale. Thinly interbedded. Soft sediment deformation. Wavey to discontinuous bedding is more prominent.			
35	C-6	1.5' 100%	0%			Below 35.1' healed (white calcite filled) fractures are more prominent, generally less than 1 mm width. Often the fractures are associated with limestone seams and terminate in shale beds. C-6 Recovered 0.3' of C-5 run.	
36	C-7	1.2' 100%	0%	35.1' - 35.4' Gray to dark gray interclastic limestone. Elongated clasts oriented with bedding angle, up to 1 1/4" long by 3/4" high. Trace calcite filled/healed fracture, oriented perpendicular to bedding. Trace, very fine (<1 mm) pyrite and possibly glauconite nodules.			
37							
38	C-8	2.4' 86%	0%	Below 37.9' primarily dark bluish gray to very dark bluish gray (5B 4/1 - 3/1) to greenish black (5GY 2/1) shale with gray to dark gray (N 5/ - N 4/1) limestone partings. Approx. 45° bedding angle. Continues to be thinly bedded. Trace bioturbidation. Bedding continues to be deformed, wavey, and discontinuous in places.		Bedding angle ~45°.	
39						Core breaks easily along bedding contacts between shale and limestone.	
40							
41	C-9	2.2' 100%	54.1%	40.7' - 41.8' Shale seam. Trace white calcite filled/healed fractures, perpendicular to bedding.		Bedding angle ~45°.	
42						C-7 36.1' - 37.0' 1127-1131. C-8 37.0' - 39.8' 1250-1305. C-9 39.8' - 42.0' 1314-1324. C-10 42.0' - 44.6' 1330-1344. C-11 44.6' - 47.0' 1355-1406.	
43	C-10	2.6' 100%	0%	Below 42.6' bedding changes from 45° to 70° by 42.8'. By 43.2' bedding angle changes back to 45°-50°.			
44							
	C-11	2.4'	0%				

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

EMDF Characterization Project Oak Ridge, TN	**BOREHOLE LOG**	Boring Number GW-986

Remarks:

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
46	C-11	2.4' 100%	0%	Interbedded dark bluish gray to very dark bluish gray (5B 4/1 - 3/1) and greenish black (5G 2/1) SHALE and gray to dark gray (N 5/ - N 4/) LIMESTONE. (Cont'd.)		Continues to be broken along bedding planes. Calcite precipitates are usually present, and generally the surfaces have depositional slickenside surfaces. Breaks appear to be mechanical, typically at intervals between 0.3' to less than 0.1'.	
47							
48	C-12	2.3' 100%	0%	47.8' - 48.1' Interclastic limestone seam. Trace to few glauconite nodules (<1 mm). Trace (rare) pyrite nodules (<1 mm). Clasts elongated and oriented with bedding.		C-12 47.0' - 49.3' 1412-1423.	
49							
50	C-13	2.7' 100%	13%	At 49.8' fracture (appears mechanically broken), 2 mm calcite filled, broken face is striated at an orientation 30° from the fracture angle. At 50.2' fracture following bedding plane, face is polished with very fine pyrite on face.		C-13 49.3' - 52.0' 1431-1502. Stopped for water from 1430' - 1454'.	
51							
52				At 50.5' horizontal break, rough face. Trace pyrite.		C-14 52.0' - 55.0' 1508-1520. 45° Bedding angle.	
53	C-14	2.9' 97%	0%			52.7' - 53.3' ~50° Bedding angle.	
54							
55							
56						Finished coring 2/18/18 at 1520. WL = 10.5' from GS at 1534.	
57	NS						
58							
59							
60				Bottom of Borehole = 59.6'. Piezometer GW-986 installed in borehole. See Monitoring Well Installation Report GW-986 for details.		On 2/20/18 using Ingersoll-Rand T3W rotary rig, reamed corehole and advanced borehole using 5 7/8" tricone bit with air and water circulation. Finished at 1240.	
61							
62							
63							
64							
65							
66							
67							
68							
69							

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

This page intentionally left blank.

Eagon & Associates, Inc.


Well Number GW-986

Monitoring Well Installation Report

Site Name and Location: *EMDF Characterization Project, Oak Ridge, TN*	Completion Date: *3/8/18*
Coordinates: *30130.30N 38191.80E*	Borehole Depth (ft): *59.6*
Elevation Top of Casing (ft/MSL): *932.37*	Borehole Diameter (in):*10" (0'-20.0'), 5 7/8 (20.0'-59.6')*
Elevation Ground Surface (ft/MSL): *930.2*	Drilling Methods: *3 1/4" ID HSA, HQ3 Core with water circulation, 10" air hammer bit, 5 7/8" tricone bit with air/water.*
Installed By: *Fred Reynolds/Tri-State Drilling*	Completed Drilling: *2/20/18*
Supervised By: *Shay Beanland/Eagon & Associates, Inc.*	Drilling Water Used (gals):

Well Design

Component	Materials	Depth (LSD)	Elevation
Well Protector	4" Square Steel Protector	-2.5 - 2.6	932.7 - 927.7
Riser	2" ID Schedule 40 PVC	-2.2 - 41.0	932.4 - 889.3
Surface Seal	3' x 3' Concrete Pad	-0.5 - 0.5	930.7 - 929.7
Conductor Casing	6" ID Sch. 40 PVC, Flush Threaded	-0.4 - 20.0	930.6 - 910.2
Cement Grout	Cement Bentonite Grout	0.5 - 35.8	929.7 - 894.4
Bentonite Seal	Pel Plug 1/4" Coated Bentonite Pellets	35.8 - 38.6	894.4 - 891.6
Sand Pack	DSI "GP #2" Gravel Pack	38.6 - 47.6	891.6 - 882.7
Screen	2" ID Schedule 40 PVC, 10-Slot	41.0 - 46.0	889.3 - 884.2
Well Point Blank	2" ID Sch. 40 PVC Cap & Riser Section	46.0 - 47.6	884.2 - 882.7
Sand Pack Bottom	DSI "GP #2" Gravel Pack	47.6 - 48.0	882.7 - 882.2
Bentonite Seal	Pel Plug 1/4" Coated Bentonite Pellets	48.0 - 59.6	882.2 - 870.6



Boring depth=59.6 ft.


Well Development

Well Depth (ft,TOC):	Depth to Water (ft,TOC):	Well Volume (gals):	Volume Purged (gals):
49.70	*6.38*	*7.1*	*156.0*

Development Method:
Surge block, bailer, mega purger whale pump

Date	Time	Cumulative Volume Removed (gals)	Temp (°C)	Specific Conductivity (µmhos/cm)	pH (S.U.)	Turbidity (NTU)
3/1/18	0848	89	15.4	520	7.42	24.8
3/1/18	1422	97	14.9	560	7.37	210.0
3/1/18	1557	139	14.6	486	7.41	229.0
3/1/18	1612	145	15.1	494.6	7.43	82.2
3/1/18	1627	149	15.0	495	7.44	119.0
3/1/18	1652	156	14.8	488	7.45	28.2

Recovery Data



Sampling Equipment:

Comments:

Grout mixing and placement information provided by Tri-State Drilling. Screen slot interval from 41.1 - 45.9 bgs.

MONITOR WELL INSTALLATION 2 OAK RIDGE .GPJ EAGON.GDT 4/4/18

This page intentionally left blank.

Eagon & Associates, Inc.

BOREHOLE LOG

Site Name and Location: **EMDF Characterization Project Oak Ridge, TN**	Drilling Methods: 4 1/4" ID HSA, HQ3 Core with water circulation, 10" air hammer bit, 5 7/8" tricone bit with air/water.				Boring Number: GW-987
Drilling Firm: *Tri-State Drilling*	DATE	TIME	DEPTH DRILLED (ft)	WATER LEVEL (ft)	
Driller / Rig: *Shannon Snow/CME-550*					*Page 1 of 2*
Logged by: *David J. Sugar*	Sampling Methods: ST = Shelby Tube; WS = Waxed Sample; SP = Sand Pump; GP or DP = Direct Push; CT = Cuttings; SS = Split Spoon; CS = Continuous Sampler; C = Coring; NS = Not Sampled; B = Bailer				Start: *Time 1410, Date 2/20/18* / Finish: *Time 1102, Date 2/21/18*
Coordinates: *30138.34N 38194.40E*					
Surface Elevation: *930.5 ft/MSL*					
Surface Conditions / Weather: *Flat, gravel pad / 65°F, Mostly sunny*					

Remarks: Borehole installed for the collection of geotech samples and installation of shallow piezometer.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
1	NS			See adjacent Borehole Log GW-986 for detailed lithologic description and stratigraphic interpretation.		4 1/4" ID HSA, ran auger plug while augering. 8 1/2" Borehole.	CL
2							
3	ST-1	0.90	700	Description based on bottom of ST-1 recovery. Brown to strong brown (7.5YR 5/4 - 4/6) SILTY CLAY. Trace highly to completely weathered shale fragments, coarse sand to gravel size. Unsorted. high plasticity, toughness, and dry strength. Moist. Weathered. SUBSOIL. No reaction with HCl.		ST-1 recovery was partially blocked, not usable. Discarded.	
4							
5	NS			ST-3 Collected after completing GW-987; moved rig 3' off of GW-987 and pressed sample from 2.0' - 4.0'. Recovered 2.1', 700 PSI press.		Auger cuttings, bucket sample, BS-1 collected from 4.0' - 6.0'.	
6				Change at 6.0'.			
7	ST-2	1.75	1000	Description based on bottom of ST-2 recovery: Light yellowish brown, yellowish brown to light olive brown (2.5Y 6/4 - 6/6) highly weathered to completely weathered SHALE (SAPROLITE). Thinly bedded (<1/2") high bedding angle. Highly fractured with black iron oxide precipitate/coatings. Moist.		Auger cuttings bucket sample BS-2 collected from 6.0' - 8.5'. No reaction with HCl. Difficult to mold sample with added water.	ML
8							
9							
10							
11							
12	NS						
13							
14							
15						Below 17.5' switch to HQ3 core, water circulation.	
16							
17				Change at 17.5'.			
18	C-1	1.8' 72%	0%	Interbedded dark gray to olive gray (5Y 4/1 - 4/2) SHALE and LIMESTONE to CALCAREOUS SILTSTONE. Trace white calcite filled fractures, oriented perpendicular to bedding, <2 mm width. Thinly bedded, generally less than 0.1' thick, oriented at a relatively high angle. Moderate to highly decomposed. Shale seams are soft. Limestone seams are hard. Weathered.		Highly fractured. Primarily along bedding, trace fractures oriented perpendicular to bedding. Fracture faces are generally coated with manganese oxide precipitates.	
19				Below 20.0' color changes to dark gray, very dark gray (N 4/ - N 3/) and		C-1 17.5' - 20.0' 1554-1615.	

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.

EMDF Characterization Project Oak Ridge, TN	**BOREHOLE LOG**	Boring Number GW-987

Remarks: Borehole installed for the collection of geotech samples and installation of shallow piezometer.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
21	C-2	1.2' 32%	0%	gray-dark gray (N 5/ - 4/). Interbedded dark gray to very dark gray (N 4/ - N 3/) SHALE and gray to dark gray (N 5/ - 4/) LIMESTONE.		Becoming unweathered. Limestone reacts strong with HCl. Shale does not react. 20.0' - 20.3' Trace yellowish brown oxidation. Highly broken. ~45° Bedding angle. End 2/20/18, 1707 at 21.3'. Begin 2/21/18, 0909. WL at 0835 = 1.2' from GS. 65°F, light rain. 22.4' - 22.8' Several bedding breaks with oxidized (yellowish brown) faces. Fracture perpendicular to bedding angle is also oxidized. Below 22.8' oxidation/weathering not observed. C-2 20.0' - 21.3' 1640-1707. C-3 21.3' - 22.0' 0909-0926. C-4 22.0' - 26.5' 0932-0952.	
22	C-3	0.7'/100%	0%	Below 20.3' relatively unweathered. Thinly bedded and generally broken along bedding planes. Breaks appear mechanical.			
23	C-4	4.0' 89%	16%	At 21.4' and 21.7' dark yellowish brown to black iron oxide/manganese oxide on bedding breaks. Below 21.7' unweathered, oxidation not observed. Consistent dark gray to very dark gray.			
24				Trace bioturbidation burrows present along some bedding contacts. Trace glauconite nodules, generally associated with limestone seams. Continues to be thinly bedded (<0.1' beds). Bedding contacts generally are deformed and have bioturbidation.			
25				At 23.2' secondary calcite on bedding break, thin coating.			
26				Consistent thinly bedded shale and limestone, ~40% limestone, 60% shale.			
27	NS						
28				Bottom of Borehole = 27.9'.		Finished coring at 0952, 2/21/18. Overdrilled corehole with HSA and advanced borehole to 27.9'. Finished auger drilling at 1102.	
29				Piezometer GW-987 installed in borehole. See monitoring well installation report GW-987 for details.			
30							
31							
32							
33							
34							
35							
36							
37							
38							
39							
40							
41							
42							
43							
44							

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.


Well Number GW-987

Monitoring Well Installation Report

Site Name and Location: *EMDF Characterization Project, Oak Ridge, TN*	Completion Date: *3/8/18*
Coordinates: *30138.34N 38194.40E*	Borehole Depth (ft): *27.9*
Elevation Top of Casing (ft/MSL): *932.94*	Borehole Diameter (in):*7 1/2"*
Elevation Ground Surface (ft/MSL): *930.5*	Drilling Methods: *4 1/4" ID HSA, HQ3 Core with water circulation, 10" air hammer bit, 5 7/8" tricone bit with air/water.*
Installed By: *Shannon Snow/Tri-State Drilling*	Completed Drilling: *2/21/18*
Supervised By: *David J. Sugar/Eagon & Associates, Inc.*	Drilling Water Used (gals): *750*

Well Design

Component	Materials	Depth (LSD)	Elevation
Well Protector	4" Square Steel w/Locking Lid	-2.7 - 2.3	933.2 - 928.2
Riser	2" ID Schedule 40 PVC	-2.4 - 16.1	932.9 - 914.4
Surface Seal	3' x 3' Concrete	-0.5 - 0.5	931.0 - 930.0
Cement Grout	Cement Bentonite Grout	0.5 - 10.9	930.0 - 919.6
Bentonite Seal	Pel-Plug 1/4" Coated Bentonite Pellets	10.9 - 13.3	919.6 - 917.2
Sand Pack	DSI GP #2 Gravel Pack	13.3 - 27.4	917.2 - 903.1
Screen	2" ID Schedule 40 PVC, 10-Slot	16.1 - 26.1	914.4 - 904.4
Well Point Blank	2" ID Schedule 40 PVC Cap and Riser	26.1 - 27.4	904.4 - 903.1
Sand Pack Bottom	DSI GP #2 Gravel Pack	27.4 - 27.9	903.1 - 902.6




Well Development

Well Depth (ft,TOC):	Depth to Water (ft,TOC):	Well Volume (gals):	Volume Purged (gals):
29.77	*9.49*	*3.3*	*110.0*

Development Method:
Bailer, surge block, Tornado pump

Date	Time	Cumulative Volume Removed (gals)	Temp (°C)	Specific Conductivity (µmhos/cm)	pH (S.U.)	Turbidity (NTU)
2/23/18	1510	10.0	16.3	364	7.48	>1000
2/27/18	1652	17.5	15.6	380	7.57	>1000
2/28/18	1620	56.0	15.0	411	7.63	810.0
3/1/18	0859	66	14.8	422	7.55	>1000
3/2/18	1635	99	14.4	433	7.52	129.0
3/3/18	0850	110	14.8	437	7.49	68.8

Recovery Data



Sampling Equipment:

Comments:

Grout mixing and placement information provided by Tri-State Drilling. Screen slot interval 16.3 - 26.1 bgs.

MONITOR WELL INSTALLATION 2 OAK RIDGE .GPJ EAGON.GDT 4/4/18

This page intentionally left blank.

Eagon & Associates, Inc.

BOREHOLE LOG

Site Name and Location: **EMDF Characterization Project Oak Ridge, TN**	Drilling Methods: 2 1/4" HSA, HQ3 Core w/water, 10" air hammer bit, 5 7/8" tricone bit w/air/water.				Boring Number: GW-988
Drilling Firm: *Tri-State Drilling*	DATE	TIME	DEPTH DRILLED (ft)	WATER LEVEL (ft)	
Driller / Rig: *Fred Reynolds/Mobile 42C*	2/8/18	1719	51.6	19.45	*Page 1 of 4*
Logged by: *Ryan Hansel/Nelson Novak*	Sampling Methods: ST = Shelby Tube; WS = Waxed Sample; SP = Sand Pump; GP or DP = Direct Push; CT = Cuttings; SS = Split Spoon; CS = Continuous Sampler; C = Coring; NS = Not Sampled; B = Bailer				Start: *Time 1135, Date 2/7/18* / Finish: *Time 1120, Date 2/22/18*
Coordinates: *29952.47N 38091.14E*					
Surface Elevation: *957.0 ft/MSL*					
Surface Conditions / Weather: *Gravel pad on 10° slope, damp ground / 40°, Cloudy, 0-5 MPH SW*					

Remarks:

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
1	SS-1	1.4' 70%	1 2 2 2	Reddish yellow to strong brown (7.5YR 7/6 - 5/6) SAND. Few silt. Some gravel. Sand is fine grained, subangular to subrounded, loose, massive. Low dry strength, slow to rapid dilatancy. Moist. Road base. Below 1.2' becomes gray in color. Strong reaction to HCl. ROAD BASE. Change at 1.4'.		Ran 2 1/4" ID Hollow Stem Augers (7" OD) w/center plug while augering. Ran 2" (OD) by 2' drive split-spoon sampler driven by 140 lb hydraulic hammer/HQ3 core w/ water. SS-1 Lost return at top compaction of road base. On 2/20/18 used Intersoll-Rand T3W rotary rig to ream borehole to 36.0' using 10" hammer bit. Set permanent 6" conductor casing and sealed with cement bentonite grout.	
2				Yellow to olive yellow (2.5Y 7/6 - 6/6) to reddish yellow to strong brown (7.5YR 6/8 - 5/8) CLAYEY SILT. Trace fine grained sand. Trace shale fragments that have been weathered to gravel, subangular to angular. Thinly bedded with a mottled appearance, very stiff, low plasticity. Moderate strength, slow to rapid dilatancy. Weathered. Moist. RESIDUUM/COLLUVIUM.			ML CL
3	SS-2	2.0' 100%	3 4 5 8				
4							
5	SS-3	2.0' 100%	4 6 8 9	Below 5.2' silt lenses and partings present. Iron and manganese oxide present along shale fragments. No reaction with HCl.		SS-2 Lab results: Moisture Content (MC) 34.6%. SS-3 Lab results: MC 25.1%.	
6							
7	SS-4	2.0' 100%	4 8 12 17			SS-4 Lab results: MC 33.6%; 0.6% Gravel; 42% Sand; 57.4 Fines.	
8							
9	SS-5	2.0' 100%	3 13 16 19	Shale becoming more competent with depth. Shale bedding and structure becoming more defined/intact with depth. Bedding is at 45°.			
10							
11	SS-6	2.0' 100%	7 11 11 12	11.5' - 11.6' Strong reaction HCl. Underlying contact is transitional. Change at 11.6'.		SS-6 Lab results: MC 29.8%.	
12				Grayish brown to olive brown (2.5Y 5/2 - 4/3) highly weathered SHALE (SAPROLITE). Shale is mostly reduced to a silty clay. Trace fine grained sand. Some shale has been reduced to gravel, subangular to angular, thinly bedded (~45°), very stiff. Low to medium plasticity. Moderate dry strength. No dilatancy. Weathered with iron and manganese oxide present along clast surfaces. No reaction with HCl. SAPROLITE.			CL ML
13	SS-7	2.0' 100%	10 14 11 15				
14							
15	SS-8	2.0' 100%	7 11 13 15	Below 13.8' silt lenses and partings present. Silt has rapid dilatancy. Shale fragments up to 1" diameter.		SS-8 Lab results: MC 26.2%.	
16							
17	SS-9	1.6' 80%	7 9 10 14				
18							
19	SS-10	1.6' 80%	6 12 14 16				

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

EMDF Characterization Project Oak Ridge, TN	**BOREHOLE LOG**	Boring Number GW-988

Remarks:

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
21	SS-11	1.8' 90%	5 11 15 17	From 20.0' - 20.6' wet.		On SS-11 wet at top of spoon. SS-11 Lab results: MC 21.5%.	CL ML
23	SS-12	1.0' 50%	7 11 21 32	Below 22.0' shale is becoming more competent, harder, becoming brown to dark brown (7.5YR 4/2 - 3/2). Degree of weathering decreasing with depth. SAPROLITE.		After augering to 26', visible wet in cuttings after 45 min break.	
25	SS-13	1.5' 75%	17 29 32 46			SS-13 Lab results: MC 16%.	
27	SS-14	1.4' 100%	18 49 50/4	Below 26.0' shale clasts become light olive gray to olive gray (5Y 7/2 - 6/2). Iron oxide on clasts becomes trace to none. Some manganese oxide present on clasts surface. SAPROLITE.		Refusal at 27.4', augered to 28'.	
	NS						
29	SS-15	1.8' 90%	28 22 32 45	Below 28.7' shale clasts become brown to dark brown (7.5YR 4/2 - 3/2). Manganese oxide becomes trace to little on shale surfaces.			
31	SS-16	1.4' 100%	22 49 50/4	Below 30.0' becomes dry. Color becomes light olive gray to olive gray (5Y 6/2 - 4/2). Some iron oxide to manganese oxide on clast surfaces.		SS-16 Lab results: MC 9.9%; 3.3% Gravel; 66.9% Sand; 29.8% Fines.	
	NS					Refusal at 31.4', augered to 32.0'.	
33	SS-17	1.2' 60%	20 23 11 19	Shale structure becoming more defined, less weathered with depth.		SS-18 Lab results: MC 9.9%.	
34	SS-18	0.9' 100%	40 50/5			Auger refusal @ 35.6' @ 1625. 2/7/18 @ 1533 DTW - 25.3 BGS.	
35	NS			Change at 35.2'.		2/8/18 @ 0801 DTW = 13.11 BGS.	
36	C-1	1.0' 71.4%	0%	Overall structure is a laminated to thinly INTERBEDDED LIMESTONE and SHALE. The limestone is medium gray to medium dark gray (N 5/ - N 4/). The shale is dark gray to grayish black (N 3/ - N 2/). The limestone is massive, siliceous, very strong field strength. The shale is laminated to thinly bedded, strong field strength. The overall structure has a 45° bedding angle. Present with soft sediment deformation, bioturbidation, and cross bedding. The top portion (top 1/2') is present with iron staining on fracture traces.		Set PVC temporary surface casing to 35' in hole plug. Cleaned out hole to 35.2'. Start HQ3 core with water at 1140. Drilling water is being recirculated.	
38	C-2	2.2' 88%	0%	Below 35.4' the limestone and shale are fresh to slightly decomposed. Fracturing is moderate to very intense. Fractures along bedding planes are fresh and probably mechanically induced. Slickensides are observed along shale bedding planes. Multiple horizontal and vertical fractures are present that have been completely healed with calcite. Trace vertical and horizontal fractures have been healed with mudstone. Calcite veins have strong reaction with HCl.		C-1: 35.2' - 36.6', 1140-1150. 35.2' - 35.4' highly fractured zone with iron staining and calcite on surface C-2: 36.6' - 39.1', 1305-1320. 36.6' - 36.8' Fracture perpendicular to bedding plane healed with calcite.	
40	C-3	1.1' 44%	0%	38.6' - 38.8' Vertical fracture. Probably mechanically induced. 38.9' - 40.0' Multiple horizontal and vertical fractures. Some are healed with calcite. Most breaks are probably mechanically induced.		C-3: 39.1' - 41.6', 1334-1345. Vertical fracture wedged and blocked tip. Lost return from bottom.	
42	C-4	0.6' 85.7%	0%	40.0' - 40.2' Fracture along core axis that has been healed with mudstone.		C-4: 41.6' - 42.3', 1520-1526. Driller noted blocked tip on run due to vertical fracture.	
43	C-5	2.3' 100%	17.4%	41.6' - 42.3' Multiple horizontal and vertical fractures, iron and manganese oxide on fracture face. Some healed with calcite.		C-5: 42.3' - 44.6', 1535-1549. 43.9' Horizontal fracture with iron.	
44	C-6	2.0	27.5%	42.3' - 44.6' Very intensely fractured. 42.7' - 43.1' Vertical fracture healed with mudstone. Rip-up clasts present. Multiple horizontal and vertical fractures healed with calcite.			

EMDF Characterization Project
Oak Ridge, TN

BOREHOLE LOG

Boring Number GW-988

Remarks:

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
46	C-6	2.0' 100%	27.5%	Medium gray to medium dark gray (N5 - N4) to dark gray to grayish black (N3 - N2) INTERBEDDED LIMESTONE and SHALE. (Cont'd.) 46.2' Horizontal fracture (~1 inch thick) healed with calcite.		C-6: 44.6' - 46.6', 1559-1610. 44.6' - 46.6' Multiple hairline fractures healed with calcite.	
47	C-7	3.0' 85.7%	12.9%	Shale beds becoming dominant with depth. Contacts between shale and limestone are deformed, have a wavy appearance.		47.3' Fracture perpendicular to bedding plan healed with calcite.	
48						C-7: 46.6' - 50.1', 1620-1642.	
49						Driller noted no loss of water/circulation while drilling.	
50	C-8	1.5' 100%	0%	Below 50.0' shale and limestone content is approximately 50%. Rock is fresh, moderately to very intensely fractured. Fractures along bedding planes (45°) are mechanically induced. Multiple thin horizontal and vertical fractures that are healed with calcite. Shale has abundant slickensided surfaces along bedding planes.		C-8: 50.1' - 51.6', 1650-1710. 2/8/18 @ 1719 WL = 19.45 BGS. 2/9/18 @ 0835 DTW - 15.58 BGS.	
51							
52	C-9	4.0' 80%	36.4%	52.8' Fracture along bedding plane healed with calcite.			
53				53.2' - 53.4' Multiple hairline fractures perpendicular to bedding planes completely healed with calcite.			
54				Trace pyrite nodules and stringers within shale.		C-9: 51.6' - 56.6', 0933-1012.	
55				54.6' Fracture perpendicular to bedding plane healed with calcite.			
56				56.8' - 57.1' Shale and limestone are deformed with turbidation, approaching a brecciated appearance.			
57	C-10	5.0' 100%	17.2%	Below 57.0' bedding varies between 45° and 60°.		C-10: 56.6' - 61.6', 1029-1055.	
58							
59				59.0' - 59.1' Fracture perpendicular to bedding plane healed with calcite.			
60							
61				61.2' - 61.5' Hairline fractures perpendicular to bedding plane healed with calcite. 61.7' - 61.8' Fracture perpendicular to bedding plane healed with calcite.			
62	C-11	3.8' 76%	0%	From 62.2' - 62.3' fine glauconite nodules oriented along bedding plane. Only found in layers of limestone.		C-11: 61.6' - 66.6'. 1108-1150. Driller noted pressure fluctuations while drilling.	
63				63.6' - 63.8' Fine glauconite nodules oriented along bedding planes only within limestone. Pyrite nodules associated near glauconite grains/nodules.			
64				63.9' - 64.1' Fracture perpendicular to bedding plane healed with calcite.			
65				64.4' - 64.7' Fracture perpendicular to bedding plane healed with calcite.			
66				Below 65.0' limestone beds are up to 3" thick. Slickensides present perpendicular to bedding plane in shale. Shale beds becoming dominant.		No loss of water/circulation during drilling.	
67	C-12	2.3' 92%	14.8%	66.6' - 67.0' Multiple fractures along bedding plane healed with calcite.		C-12: 66.6' - 69.1', 1358-1417. Driller noted rock feeding poorly. Pulled run.	
68				67.2' - 67.4' 1/4" thick fracture healed with calcite. Calcite is mostly white, some pink/orange in color.			
69				68.2' - 68.5' Multiple horizontal and vertical hairline fractures filled with calcite.			
	C-13	1.5' 100%	0%				

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

EMDF Characterization Project
Oak Ridge, TN

BOREHOLE LOG

Boring Number GW-988

Remarks:

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
71	C-13	1.5' 100%	0%	At 69.7' bedding turns near vertical with a fracture going from 69.9' to 72.3'. Fracture is healed with mudstone and calcite. Some limestone and shale rip-up clasts present within the mudstone. Highly deformed along bedding planes with some small-scale folds observed. Abundant horizontal fractures healed with calcite. Most breaks were probably mechanically induced. From 71.8' - 72.3' very intensely fractured zone. Healed with mudstone. Some healed with calcite. Below 72.3' bedding turns back to 40° to 50°.		C-13: 69.1' - 70.6', 1428-1444. C-14: 70.6' - 71.6', 1454-1504. C-15: 71.6' - 73.6', 1513-1531. Driller noted approximately 5% water loss in circulation. C-16: 73.6' - 75.0', 1542 - 1552. 2/9/18 at 1600 DTW = 6.79 BGS. 2/10/18 @ 0755, DTW = 4.88'.	
72	C-14	1.0' 100%	0%				
73	C-15	2.0' 100%	0%				
74	C-16	1.3' 92.9%	0%				
75	NS						
76							
77							
78							
79				Bottom of Borehole = 78.5'. Piezometer GW-988 installed in borehole. See Monitoring Well Installation Report GW-988 for details.		On 2/22/18 used T3W rotary rig to ream corehole and advance borehole to 78.5' using 5 7/8" tricone bit with air and water circulation. Finished drilling at 1120.	
80							
81							
82							
83							
84							
85							
86							
87							
88							
89							
90							
91							
92							
93							
94							

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.

Well Number GW-988

Monitoring Well Installation Report

Site Name and Location: *EMDF Characterization Project, Oak Ridge, TN*	Completion Date: *3/8/18*
Coordinates: *29952.47N 38091.14E*	Borehole Depth (ft): *78.5*
Elevation Top of Casing (ft/MSL): *958.95*	Borehole Diameter (in):*10" (0'-36.0'), 5 7/8" (36.0'-78.5')*
Elevation Ground Surface (ft/MSL): *957.0*	Drilling Methods: *2 1/4" HSA, HQ3 Core w/water, 10" air hammer bit, 5 7/8" tricone bit w/air/water.*
Installed By: *Fred Reynolds/Tri-State Drilling*	Completed Drilling: *2/22/18*
Supervised By: *Shay Beanland/Eagon & Associates, Inc.*	Drilling Water Used (gals):

Well Design

Component	Materials	Depth (LSD)	Elevation
Well Protector	4" Square Steel Protector w/Locking Lid	-2.3 - 2.7	959.3 - 954.3
Riser	2" ID Schedule 40 PVC	-2.0 - 61.9	959.0 - 895.1
Surface Seal	3' x 3' Concrete Pad	-0.5 - 0.5	957.5 - 956.5
Conductor Casing	6" ID PVC Schedule 40, Flush Threaded	-0.4 - 36.0	957.4 - 921.0
Cement Grout	Cement Bentonite Grout	0.5 - 55.1	956.5 - 901.9
Bentonite Seal	Pel Plug 1/4" Coated Bentonite Pellets	55.1 - 59.6	901.9 - 897.4
Sand Pack	DSI "GP #2" Gravel Pack	59.6 - 73.2	897.4 - 883.8
Screen	2" ID Schedule 40 PVC, 10-Slot	61.9 - 71.9	895.1 - 885.1
Well Point Blank	2" ID Sch. 40 PVC Cap & Riser Section	71.9 - 73.2	885.1 - 883.8
Sand Pack Bottom	DSI "GP #2" Gravel Pack	73.2 - 74.0	883.8 - 883.0
Bentonite Seal	Pel Plug 1/4" Coated Bentonite Pellets	74.0 - 78.5	883.0 - 878.5


Well Development

Well Depth (ft,TOC):	Depth to Water (ft,TOC):	Well Volume (gals):	Volume Purged (gals):
75.20	*13.56*	*10*	*132.5*

Development Method:
Surge block, bailer, mega purger whale pump

Date	Time	Cumulative Volume Removed (gals)	Temp (°C)	Specific Conductivity (µmhos/cm)	pH (S.U.)	Turbidity (NTU)
3/1/18	1240	42.5	15.1	647	7.54	134.0
3/1/18	1305	57.5	14.9	759	7.25	29.0
3/1/18	1325	87.5	14.8	761	7.12	3.9
3/1/18	1335	102.5	14.9	768	7.10	3.5
3/1/18	1345	117.5	14.7	766	7.07	2.2
3/1/18	1400	132.5	14.7	769	7.05	2.4


Recovery Data



Sampling Equipment:

Comments:

Stainless steel centralizers installed at 27.5' and 55.5' below ground surface. Washed sand pack and pellets in using tremie pipe. Grout mixing and placement information provided by Tri-State Drilling. Screen slot interval 62.1 - 71.8 bgs.



Boring depth=78.5 ft.

MONITOR WELL INSTALLATION 2 OAK RIDGE .GPJ EAGON.GDT 4/4/18

This page intentionally left blank.

Eagon & Associates, Inc.

BOREHOLE LOG

Site Name and Location: **EMDF Characterization Project Oak Ridge, TN**	Drilling Methods: 4 1/4" ID HSA, HQ3 Core with water circulation.				Boring Number: GW-989
Drilling Firm: *Tri-State Drilling*	DATE	TIME	DEPTH DRILLED (ft)	WATER LEVEL (ft)	
Driller / Rig: *Shannon Snow/CME-550*					*Page 1 of 3*
Logged by: *David J. Sugar*	Sampling Methods: ST = Shelby Tube; WS = Waxed Sample; SP = Sand Pump; GP or DP = Direct Push; CT = Cuttings; SS = Split Spoon; CS = Continuous Sampler; C = Coring; NS = Not Sampled; B = Bailer				Start: *Time 1429, Date 2/27/18* / Finish: *Time 1645, Date 2/28/18*
Coordinates: *29950.44N 38082.67E*					
Surface Elevation: *955.7 ft/MSL*					
Surface Conditions / Weather: *Slopped surface, gravel pad / 60°-65°F, Sunny*					

Remarks: Borehole installed for the collection of geotech samples and installation of shallow piezometer.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
1–2	NS			See Borehole Log for adjacent boring GW-988 for detailed lithologic description and stratigraphic interpretation.		4 1/4" ID HSA, ran auger plug while augering.	
3–4	ST-1	1.85	1200 PSI	Description based on inspection of bottom of ST-1 recovery: Strong brown (7.5YR 5/6 - 5/8 and 4/6) and pale brown (2.5Y 7/3 - 7/4) mottled SILTY CLAY. Trace to some black mottling. Trace highly weathered fragments. Moist. high plasticity and toughness. SUBSOIL.		Auger cutting bucket sample BS-1 collected from 4.0' - 6.0'.	
5–6	NS						
7–8	ST-2	1.85	1000 PSI	Description based on inspection of bottom of ST-2 recovery: Thinly bedded yellow to olive yellow (7.5Y 7/6 - 6/6) SHALE (SAPROLITE). Completely weathered. Some dark grayish brown to very dark grayish brown (2.5Y 4/2 - 3/2) beds. Appears intact remnant bedding. Underlying contact may be higher or bottom of ST-2 may be a large rock fragment.		Plasticity and toughness are variable, generally low to medium.	
9–10	NS					Auger cutting bucket sample BS-2 collected from 8.0' - 10.0'.	
11–12	ST-3	1.9	1500 PSI	SHALE (SAPROLITE). Highly/completely weathered. Damp to moist.			
13–14	NS			Description based on inspection of bottom of ST-3 recovery: Light olive brown (2.5Y 5/3 - 5/4) highly weathered SHALE (SAPROLITE). Low bedding angle (may not be in place) or slightly disturbed sample at sampler tip.			
15–16	ST-4	1.95	1300 PSI				
17–18	NS			Description based on inspection of bottom of ST-4 recovery: Olive gray to olive (5Y 4/2 - 4/3 and 5/3 - 5/4) highly weathered SHALE (SAPROLITE). Relatively low bedding angle. Thinly bedded with dark reddish brown/black iron oxide on bedding surfaces. Moist.			
19							

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.

EMDF Characterization Project Oak Ridge, TN	**BOREHOLE LOG**	Boring Number GW-989

Remarks: Borehole installed for the collection of geotech samples and installation of shallow piezometer.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
21				SHALE (SAPROLITE). (Cont'd.)			
22				Below 22.0' auger cutting returns are very moist. No free water.			
23							
24							
25							
26	NS						
27							
28							
29				Below 30.0' auger cutting returns are wet.		C-1 32.0' - 35.6' 1630-1701.	
30				Contact with underlying interbedded shale and limestone is higher than 32.0'.		C-2 35.6 - 36.7' 0930-0941.	
31						C-3 36.7' - 40.0' 0952-1050.	
32				Change at 32.0'.		C-4 40.0' - 45.0' 1108-1130.	
33	C-1	2.9' 80%	13%	Interbedded dark gray to olive gray (5Y 4/1 - 4/2) SHALE and LIMESTONE. Some of the limestone seams may actually classify as calcareous siltstone. Thinly bedded, generally <0.1' beds and partings are not uncommon. Bedding angle is 45°. Limestone seams are hard and react strongly with HCl. Microcrystalline to fine crystalline. Shale seams are soft, do not react with HCl. Moderate to highly decomposed. Intensely fractured.		Contacts between limestone and shale beds are wavey/deformed. Soft sediment deformation trace bioturbidation. Approximately 40% to 60% limestone.	
34				With depth picking up gray color hues, becoming unweathered. Below 33.3' consistent gray to very dark gray (N 5/ - N 3/) color. Fresh to slightly decomposed. Limestone seams have lighter gray color hues. Becoming unweathered/competent.		32.0' - 33.6' Most bedding breaks are oxidized with iron oxide precipitates on fracture surfaces.	
35							
36	C-2	1.1' 100%	0%			34.1' - 34.3' Broken zone, bedding break and fracture perpendicular to bedding. Oxidized with iron oxide precipitates on fracture faces. End 2-27-18, 1701 at 35.6'. 2/28/18, 0810 WL = 5.4', 49°F, Light rain. Start coring at 0930.	
37	C-3	1.5' 45%	30%	33.5' - 34.4' Primarily limestone, trace shale partings and thin seams. Bedding contacts are deformed and bioturbated.			
38				Below 35.6' oxidized zones/fractures are rare and called out where observed. Continues to be thinly bedded with common mechanical breaks at shale/limestone bedding contacts. Secondary mineralization along breaks is generally not observed.		The increase in white calcite filled fractures below 36.0' appears to correlate with the increase in the bedding angle.	
39						41.9' - 42.3' Broken zone with iron oxide along bedding planes and perpendicular fractures. Secondary calcite does not appear to be present. Zone may account for some C-4 lost recovery.	
40				Below 36.0' bedding angle increases to 65° - 70°. Healed fractures (white calcite filled) increase, up to 1/4" width, generally oriented perpendicular to bedding, often more prominent within limestone beds and typically dissipate or terminate within shale beds. By 41.0' bedding is approaching vertical. Healed (calcite filled) fractures oriented perpendicular to bedding are prominent within limestone beds. Local deformation, contorted bedding (small scale folds) are present. Below 41.5' beds may be slightly overturned.			
41							
42	C-4	3.2' 64%	0%				
43				Below 42.3' some limestone beds are almost brecciated. At a minimum, highly deformed.		The core bit/lifter was stuffed, indicating that the majority of lost C-4 recovery was most likely from the bottom of the run.	
44				Below 42.8' considerable white calcite filled fractures, highly deformed.		Overdrilled corehole with 4 1/4" ID HSA.	

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.

EMDF Characterization Project Oak Ridge, TN	**BOREHOLE LOG**	Boring Number GW-989

Remarks: Borehole installed for the collection of geotech samples and installation of shallow piezometer.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
46				Bottom of Borehole = 45.0'. Piezometer GW-989 installed in borehole. See Monitoring Well Installation Report GW-989 for details.			
47							
48							
49							
50							
51							
52							
53							
54							
55							
56							
57							
58							
59							
60							
61							
62							
63							
64							
65							
66							
67							
68							
69							

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

This page intentionally left blank.

Eagon & Associates, Inc.

Well Number GW-989

Monitoring Well Installation Report

Site Name and Location: *EMDF Characterization Project, Oak Ridge, TN*	Completion Date: *3/8/18*
Coordinates: *29950.44N 38082.67E*	Borehole Depth (ft): *45.0*
Elevation Top of Casing (ft/MSL): *957.86*	Borehole Diameter (in):*7 1/2"*
Elevation Ground Surface (ft/MSL): *955.7*	Drilling Methods: *4 1/4" ID HSA, HQ3 Core with water circulation.*
Installed By: *Shannon Snow/Tri-State Drilling*	Completed Drilling: *2/28/18*
Supervised By: *David J. Sugar/Eagon & Associates, Inc.*	Drilling Water Used (gals): *~600*

Well Design

Component	Materials	Depth (LSD)	Elevation
Well Protector	4" Square Steel w/Locking Lid	-2.6 - 2.4	958.3 - 953.3
Riser	2" ID Schedule 40 PVC	-2.3 - 33.6	958.0 - 922.1
Surface Seal	3' x 3' Concrete	-0.5 - 0.5	956.2 - 955.2
Cement Grout	Cement Bentonite Grout	0.5 - 25.7	955.2 - 930.0
Bentonite Seal	Pel-Plug 1/4" Coated Bentonite Pellets	25.7 - 30.0	930.0 - 925.7
Sand Pack	DSI GP #2 Gravel Pack	30.0 - 44.9	925.7 - 910.8
Screen	2" ID Schedule 40 PVC, 10-Slot	33.6 - 43.6	922.1 - 912.1
Well Point Blank	2" ID Sch. 40 PVC Cap & Riser Section	43.6 - 44.9	912.1 - 910.8
Sand Pack Bottom	DSI GP #2 Gravel Pack	44.9 - 45.0	910.8 - 910.7


Well Development

Well Depth (ft,TOC):	Depth to Water (ft,TOC):	Well Volume (gals):	Volume Purged (gals):
47.21	*14.03*	*5.4*	*151.0*

Development Method:
Surge block, bailer, mega purger whale pump

Date	Time	Cumulative Volume Removed (gals)	Temp (°C)	Specific Conductivity (µmhos/cm)	pH (S.U.)	Turbidity (NTU)
3/5/18	0900	17.0	14.8	534	7.28	>1000
3/5/18	1126	49.5	14.8	341.3	8.10	351.0
3/5/18	1400	80.5	14.6	508	7.51	383.0
3/6/18	0904	124.0	14.5	323.8	7.72	142.0
3/6/18	1402	135.5	15.3	326.6	7.78	24.6
3/6/18	1459	151.0	15.6	329.3	7.79	8.1


Recovery Data



Sampling Equipment:

Comments:

Grout mixing and placement information provided by Tri-State Drilling. Screen slot interval 33.8 - 43.5 bgs.



MONITOR WELL INSTALLATION 2 OAK RIDGE .GPJ EAGON.GDT 4/4/18

This page intentionally left blank.

Eagon & Associates, Inc.

BOREHOLE LOG

Site Name and Location: **EMDF Characterization Project Oak Ridge, TN**	Drilling Methods: 2 1/4" HSA, HQ3 Core w/water, 10" air hammer bit, 5 7/8" tricone bit with air/water.				Boring Number: GW-992
Drilling Firm: *Tri-State Drilling*	DATE	TIME	DEPTH DRILLED (ft)	WATER LEVEL (ft)	
Driller / Rig: *Fred Reynolds/Mobile 42C*	2/16/18	1725	36.4	4.57	*Page 1 of 3*
Logged by: *Ryan Hansel*	Sampling Methods: ST = Shelby Tube; WS = Waxed Sample; SP = Sand Pump; GP or DP = Direct Push; CT = Cuttings; SS = Split Spoon; CS = Continuous Sampler; C = Coring; NS = Not Sampled; B = Bailer				Start: *Time 0855, Date 2/16/18*; Finish: *Time 1515, Date 2/17/18*
Coordinates: *29698.29N 38749.00E*					
Surface Elevation: *910.0 ft/MSL*					
Surface Conditions / Weather:					

Remarks:

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
1	NS			ROAD BASE. Change at 1.0'.		Ran 2 1/4" HSA (7" OD) w/center plug while augering. Continuous 2" OD, 2' drive split spoons, 140 lb hydraulic hammer.	
2	SS-1	1.3' 65%	3 4 5 3	Brown (7.5YR 5/4 - 4/4) CLAYEY SILT. Trace fine grained sand. Trace to little shale fragments (up to 1" diameter). Iron and manganese oxide on shale fragments. Massive. Shale fragments are oriented in same direction. Low plasticity. Slow to no dilatancy. Medium dry strength. Moist. Cohesive. No reaction with HCl. Very soft to soft. Weathered. RESIDUAL SOIL/COLLUVIUM.		On 2/18/18, used Ingersoll-Rand T3W rotary rig to ream borehole to 31.0' using 10" air hammer bit. Set permanent 6" PVC casing and sealed with cement bentonite grout.	ML
3							
4	SS-2	1.3' 65%	3 2 2 2	Below 4.3' shale clasts become trace to rare. Becomes moist to wet. No to slow dilatancy. Fine grained sand becomes few to little. Clay content decreases slightly.		SS-1 Lab results: Moisture Content 29.3%.	
5							
6	SS-3	2.0' 100%	WH 1 1 1			SS-2 Lab results: MC 23.9%; 7% Gravel; 36% Sand; 57% Fines. WH = weight of hammer.	
7				Below 7.0' clay content increases.			
8	SS-4	1.4' 70%	WH WH 4 6	Change at 8.0'. Olive (5Y 5/4 - 4/4) highly weathered SHALE (SAPROLITE). Shale clasts are highly weathered and comprised of silt and clay. Laminated to thinly bedded with iron and manganese oxide along bedding planes. Bedding planes are at 40°-50° angles. Very stiff to hard. Medium plasticity. High dry strength. Cohesive. No reaction with HCl. Dry to moist. SAPROLITE.		SS-4 Lab results: MC 37.1%.	CL
9							
10	SS-5	1.3' 65%	4 10 19 17			SS-5 Lab results: MC 13.4%.	
11							
12	SS-6	1.3' 65%	5 10 10 9	Below 11.0' becomes wet. Trace to few siltstone beds/clasts. Shale is becoming more competent with depth. All shale and siltstone has iron and manganese oxide. Wet. 11.7' - 11.9' Broken siltstone beds with manganese oxide on clast surfaces.			
13							
14	SS-7	1.1' 55%	4 6 5 2			SS-7 Lab results: MC 21.3%. Water on spoon.	
15							
16	SS-8	1.6' 80%	7 16 18 29	15.0' - 15.5' Shale is grayish blue green (5BG 5/2). Trace iron and manganese oxide. Below 15.0' shale clasts can barely be broken by hand. Dry.		SS-8 Lab results: MC 16.2%.	
17							
18	SS-9	1.6' 80%	8 19 18 19				
19							
	SS-10	1.5' 75%	9 13			SS-10 Lab results: MC 15.5%; 1% Gravel; 62% Sand; 37% Fines.	

BOREHOLE LOG V.2 OAK RIDGE.GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

EMDF Characterization Project
Oak Ridge, TN

BOREHOLE LOG

Boring Number GW-992

Remarks:

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
21	SS-10	1.5' 75%	11 9	Olive (5Y 5/4 - 4/4) highly weathered SHALE (SAPROLITE). (Cont'd.)			CL
22	SS-11	1.3' 65%	10 10 10 6	Below 20.0' shale (saprolite) becomes more weathered. Shale clasts are easily broken by hand. Abundant iron and manganese oxide on shale clasts. No reaction with HCl. Below 23.0' trace limestone clasts with calcite veins. Strong reaction with HCl.			
24	SS-12	1.7' 94.4%	2 8 23 50/3	24.0' - 24.8' Sandstone clasts completely decomposed to sand, abundant with iron and manganese oxide. Saturated. Below 25.0' shale (saprolite) becomes olive gray (5Y 5/2 - 4). Trace iron and manganese oxide on clast surfaces.		SS-12 Lab results: MC 17.6%.	
26	NS SS-13	1.3' 65%	30 28 30 29	Below 25.5' color becomes grayish blue green (5BG 5/2). Below 26.8' color becomes light olive gray (5Y 6/2).		SS-13 Lab results: MC 10.8%.	
28	SS-14	0.8' 80%	8 50/5	Change at 28.0'.			
31	C-1	2.6' 76.5%	22.9%	Gray to dark gray (N 5/ - 4/) INTERCLASTIC LIMESTONE. Strong. Thinly bedded. Clasts are made up of limestone and are elongated. Clast orientation is parallel to bedding planes. The matrix material is limestone with trace glauconite grains within matrix. Some soft sediment deformation of the limestone clasts and cross bedding. Slightly decomposed. Strong reaction with HCl. Moderate to intensely fractured. Multiple horizontal and vertical fractures that have been completely healed with calcite. Below 31.0' shale beds and partings that are increasing with depth. Change at 31.4'.		Auger refusal at 1052 at 28.0'. Pull augers and install temporary PQ surface casing. 28.0' - 28.2' Fracture perpendicular to bedding and a near vertical fracture with iron oxide. C-1: 28.0' - 31.4' 1407-1448. Weathered at top. Probably where return was lost. Measure C-1 from bottom.	
32	C-2	0.9' 90%	0%	Dark gray to very dark gray (N 4/ - 3/) SHALE. Trace glauconite. Laminated to thinly bedded. Strong. Fresh. Slightly disintegrated. Intense to very intensely fractured. Most breaks are along bedding planes and probably mechanically induced. Some fractures are shear with glauconite grains and striations along fracture. No reaction with HCl.		31.4' - 33.1' Vertical fracture with slickensides. Glauconite.	
33	C-3	0.7' 100%	0%			C-2: 31.4' - 32.4' 1456-1509. Blocking in tip/pull run.	
35	C-4	3.3' 100%	18.8%	33.1' - 33.4' Shale is very intensely fractured. Probably due to sampling/mechanically induced. 33.4' - 34.1' Interclastic limestone bed. Clasts are elongated. Matrix is made up of shale and limestone. Clasts are oriented parallel to the bedding planes. Some iron oxide staining along bedding planes associated with limestone beds. 34.1' - 34.4' Shale is dark greenish gray 10GY (4/1). Shale is becoming less fractured with depth.		C-3: 32.4' - 33.1' 1515-1530. Blocked tip. Pull run. 34.6' Vertical fracture with iron oxide. 33.7' - 34.0' Fracture perpendicular to bedding plane with iron oxide. C-4: 33.1' - 36.4' 1538-1615.	
37	C-5	2.3' 74.1%	0%	36.4' - 37.4' Trace limestone and glauconite beds and partings. Very intensely fractured. Some healed with calcite. Most are mechanically induced. Limestone bed from 37.5' - 38.2'.		2/16/18 at 1725 DTW = 4.57 BGS. 2/17/18 at 0803 DTW = 4.32 BGS.	
39	C-6	1.9' 100%	0%	37.5' - 37.9' and 38.0' - 38.2' Interclastic limestone beds. Clasts are elongated and oriented parallel to bedding planes. Matrix material is limestone with glauconite. Some soft sediment deformation and cross-bedding observed. Trace horizontal and vertical fractures healed with calcite. Shale beds near the limestone beds are dark greenish gray (10GY 4/1). Below 39.5' shale is fresh. Competent. Slightly to moderately fractured. Limestone beds and partings become trace to rare. Multiple breaks along bedding planes with slickensides. Breaks are probably drilling induced. 40.4' - 40.7' Vertical break with slickensides.		C-5: 36.4' - 39.5' 0819-0853. Driller noted tip blocked. Pulled run. 39.3' Fracture perpendicular to bedding plane healed with calcite. C-6: 39.5' - 41.4' 0900-0929.	
43	C-7	3.2' 88.9%	0%	41.8' - 44.3' Very intensely fractured. Multiple breaks along and perpendicular to the bedding planes. Some with slickensides. Probably mechanically induced. 44.3' - 45.0' Limestone bed with some soft sediment deformation. Trace shale beds within limestone. Moderately fractured with fracture healed by calcite.		C-7: 41.4' - 45.0' 0939-1033. 1046 Drillers get water.	

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.

EMDF Characterization Project Oak Ridge, TN	**BOREHOLE LOG**	Boring Number GW-992

Remarks:

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
46				Dark gray to very dark gray (N 4/ - 3/) SHALE. (Cont'd.) Below 45.0' trace limestone beds and partings. Limestone present with multiple horizontal and vertical fractures healed with calcite.		C-8: 45.0' - 49.5' 1104-1210. On start of C-8 cutting returns turned from light gray to brown. 1135 Drillers to get water. On C-8 inner core barrel did not lock in. Core in bottom of hole. Trip out to attempt core recovery at 1223. Low recovery on C-8. Makes difficulty in logging. C-9: 49.5' - 50.0' 1250-1859. DTW = 11.57 BGS.	
47	C-8	1.3' 28.9%	0%				
48							
49							
50	C-9	0.3'/60%	0%	Bottom of Borehole = 50.0'. Borehole sealed with cement bentonite grout due to damage to the surface casing at the beginning of reaming activities. Installation borehole for Piezometer GW-992 installed approximately 8' east of original borehole.		On 2/19/18, used Ingersoll-Rand T3W rotary rig to ream corehole to 50.0' using 5 7/8" tricone bit. Finished drilling at 1515.	
51							
52							
53							
54							
55							
56							
57							
58							
59							
60							
61							
62							
63							
64							
65							
66							
67							
68							
69							

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

This page intentionally left blank.

Eagon & Associates, Inc.

BOREHOLE LOG

Site Name and Location: **EMDF Characterization Project Oak Ridge, TN**	Drilling Methods: 10" Air Hammer, 5 7/8" and 5 5/8" Tricone.				Boring Number: GW-992R
Drilling Firm: *Tri-State Drilling*	DATE	TIME	DEPTH DRILLED (ft)	WATER LEVEL (ft)	
Driller / Rig: *Travis Morgan/Ingersoll-Rand T3W*	2/26/18	1730	54.2	24.22	*Page 1 of 3*
Logged by: *Nelson Novak*	Sampling Methods: ST = Shelby Tube; WS = Waxed Sample; SP = Sand Pump; GP or DP = Direct Push; CT = Cuttings; SS = Split Spoon; CS = Continuous Sampler; C = Coring; NS = Not Sampled; B = Bailer				Start / Finish
Coordinates: *29698.29N 38737.35E*					*Time 1422* / *Time 1635*
Surface Elevation: *908.9 ft/MSL*					*Date 2/20/18* / *Date 2/26/18*
Surface Conditions / Weather: *Damp gravel road / 60°F, Sunny*					

Remarks: Drilled approximately 8' east of borehole GW-992.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
1–19	NS (at 10)			GW-992R is a replacement well and was straight drilled. See Borehole Log GW-992 for a detailed lithologic description and stratigraphic interpretation.		Straight drilled to 32.0' using 10" hammer bit. Set permanent 6" PVC casing and sealed with cement bentonite grout.	

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

EMDF Characterization Project Oak Ridge, TN	**BOREHOLE LOG**	Boring Number GW-992R

Remarks: Drilled approximately 8' east of borehole GW-992.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
21							
22							
23							
24							
25							
26							
27							
28							
29							
30							
31							
32	NS						
33							
34							
35						Straight drilled to 34.6' with 5 5/8" tricone bit to get through permanent 6" casing. Once below 6" PVC casing, switched tricone bit to a larger size bit (5 7/8") and straight drilled to 55.5'.	
36							
37							
38							
39							
40							
41							
42							
43							
44							

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.

EMDF Characterization Project Oak Ridge, TN	**BOREHOLE LOG**	Boring Number GW-992R

Remarks: Drilled approximately 8' east of borehole GW-992.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
46							
47							
48							
49							
50	NS						
51							
52							
53							
54							
55							
56				Bottom of Borehole = 55.5'. Piezometer GW-992R installed in borehole. See Monitoring Well Installation Report GW-992R for details.			
57							
58							
59							
60							
61							
62							
63							
64							
65							
66							
67							
68							
69							

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

This page intentionally left blank.

Eagon & Associates, Inc.


Well Number GW-992R

Monitoring Well Installation Report

Site Name and Location: *EMDF Characterization Project, Oak Ridge, TN*	Completion Date: *3/8/18*
Coordinates: *29698.29N 38737.35E*	Borehole Depth (ft): *55.5*
Elevation Top of Casing (ft/MSL): *911.40*	Borehole Diameter (in):*10" (0'-32.0'), 5 7/8" (32.0'-55.5')*
Elevation Ground Surface (ft/MSL): *908.9*	Drilling Methods: *10" Air Hammer, 5 7/8" and 5 5/8" Tricone.*
Installed By: *Fred Reynolds/Tri-State Drilling*	Completed Drilling: *2/26/18*
Supervised By: *Shay Beanland/Eagon & Associates, Inc.*	Drilling Water Used (gals):

Well Design

Component	Materials	Depth (LSD)	Elevation
Well Protector	4" Square Steel Protector	-2.8 - 2.2	911.7 - 906.7
Riser	2" ID Schedule 40 PVC	-2.5 - 39.3	911.4 - 869.6
Surface Seal	3' x 3' Concrete Pad	-0.5 - 0.5	909.4 - 908.4
Conductor Casing	6" ID PVC Sch. 40 PVC, Flush Threaded	-0.4 - 32.0	909.3 - 876.9
Cement Grout	Cement Bentonite Grout	0.5 - 33.8	908.4 - 875.1
Bentonite Seal	Pel Plug 1/4" Coated Bentonite Pellets	33.8 - 37.2	875.1 - 871.7
Sand Pack	DSI "GP #2" Gravel Pack	37.2 - 45.7	871.7 - 863.2
Screen	2" ID Schedule 40 PVC, 10-Slot	39.3 - 44.4	869.6 - 864.5
Well Point Blank	2" ID Sch. 40 PVC Cap & Riser Section	44.4 - 45.7	864.5 - 863.2
Sand Pack Bottom	DSI "GP #2" Gravel Pack	45.7 - 48.2	863.2 - 860.7
Bentonite Seal	Enviro Plug Medium Chips	48.2 - 55.5	860.7 - 853.4




Well Development

Well Depth (ft,TOC):	Depth to Water (ft,TOC):	Well Volume (gals):	Volume Purged (gals):
48.21	*4.88*	*7.1*	*74.5*

Development Method:
Surge block, bailer, mega purger whale pump

Date	Time	Cumulative Volume Removed (gals)	Temp (°C)	Specific Conductivity (µmhos/cm)	pH (S.U.)	Turbidity (NTU)
3/3/18	1305	17.0	15.5	387	7.49	62.7
3/3/18	1320	32.0	15.1	380	7.57	7.0
3/3/18	1350	42.0	15.0	380	7.49	6.3
3/3/18	1405	57	15.1	375	7.52	6.8
3/3/18	1415	67	15.0	369	7.46	8.3
3/3/18	1430	74.5	15.2	368	7.46	6.0

Recovery Data



Sampling Equipment:

Comments:

Grout mixing and placement information provided by Tri-State Drilling. Screen slot interval 39.4 - 44.2 bgs.

MONITOR WELL INSTALLATION 2 OAK RIDGE .GPJ EAGON.GDT 4/4/18

This page intentionally left blank.

Eagon & Associates, Inc.

BOREHOLE LOG

Site Name and Location: **EMDF Characterization Project Oak Ridge, TN**	Drilling Methods: 4 1/4" ID HSA, HQ Core with water, 5 7/8" hammer bit.				Boring Number: GW-993
Drilling Firm: *Tri-State Drilling*	DATE	TIME	DEPTH DRILLED (ft)	WATER LEVEL (ft)	
Driller / Rig: *Fred Reynolds/Mobile B42C*					*Page 1 of 2*
Logged by: *Shay Beanland*	Sampling Methods: ST = Shelby Tube; WS = Waxed Sample; SP = Sand Pump; GP or DP = Direct Push; CT = Cuttings; SS = Split Spoon; CS = Continuous Sampler; C = Coring; NS = Not Sampled; B = Bailer				Start: *Time 0000, Date 2/22/18* / Finish: *Time 0818, Date 2/27/18*
Coordinates: *29690.50N 38724.90E*					
Surface Elevation: *909.7 ft/MSL*					
Surface Conditions / Weather: *Gravel pad, dry / 70°F, Partly cloudy*					

Remarks: Boring installed for collection of geotech samples and for installation of shallow piezometers.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
1–3	HSA			See Borehole Log for adjacent boring GW-992 for detailed lithologic description and stratigraphic interpretation.		Ran 4 1/4" ID HSA with center plug to target depths of Shelby tube samples. Pushed Shelby tubes. Advanced augers to target depth and switched to HQ Core with water. Cored to target depth, then reamed borehole with 5 7/8" hammer bit to depth.	
3–5	ST-1	1.6	700 PSI 750 PSI 750 PSI 750 PSI	Bottom of tube, sample is brown to strong brown (7.5YR 5/4 - 4/6) CLAYEY SILT. Few to little fine to coarse grained sand, primarily medium to coarse grained. Abundant shale fragments. Moist.		Pushed ST-1 from 3.0' - 5.0'. Let tube set in borehole from 940 to 945. Bulk Bucket Sample (BS-1) collected from 4.0' - 5.0' at 0952. Auger cuttings collected.	
5–7	ST-2	2.0	600 PSI 600 PSI 600 PSI 600 PSI			Pushed ST-2 from 5.0' - 7.0'. Let tube set in borehole from 0954 to 1003. Tube is wet. Bulk Bucket Sample (BS-2) collected from 6.0' - 7.0' at 1000. Auger cuttings collected.	
7–10	HSA			Bottom of tube, same material as above, but decrease in sand content to trace. Increase in moisture content to wet.			
10–11	ST-3	0.5	900 PSI			Pushed ST-3 from 10.5' - 11.1' until refusal. Let tube set in borehole from 1019 to 1025.	
11–19	HSA		1000/1 PSI	At bottom of tube, sample is olive (5Y 5/4 - 4/4) SHALE (SAPROLITE). Highly weathered. No reaction with HCl.			

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.

EMDF Characterization Project Oak Ridge, TN	**BOREHOLE LOG**	Boring Number GW-993

Remarks: Boring installed for collection of geotech samples and for installation of shallow piezometers.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
21							
22	HSA						
23							
24							
25				Interbedded gray (N 5/) LIMESTONE and dark gray (N 4/) SHALE. Overall interbedded structure is thinly to medium bedded. Shale is laminated where present. Limestone is interclastic above 27.0' and microcrystalline below 27.0'. Clasts are elongated and aligned parallel to bedding planes, which are at an 80° angle. Limestone is strong and shale weak Slickenside surfaces (depositional) along bedding plane breaks at 60° - 70° angles. Slightly decomposed, moderately disintegrated at top of core but becomes slightly disintegrated with depth. Very intensely to intensely fractured but some breaks are mechanically induced. Bedding plane angles range from 80°-90° to 40°-50° with depth. Fractures healed with calcite also are observed throughout limestone zones run perpendicular to bedding planes ranging in thickness from less than 1mm up to 8mm. Iron staining, iron oxide, and manganese oxide observed on several fracture surfaces and bedding planes, as noted in remarks. Change at 27.9'.		1110 - Switching over to core. C-1 25.0' - 25.0' 1239-1306. 1231 WL = 4.30 from ground surface, TD = 25.0'. C1 - Recovery lost is probably shale mainly from top of core run but within limestone beds too. Driller noted that it felt very soft when coring. 26.0' - 26.5' Multiple high angle fractures (>75° angles) with iron staining, iron and manganese oxide along fracture face. 26.0' - 26.2' limestone is slightly to moderately disintegrated along fracture face. 27.3' - 27.5' 40°-50° fractures, not along bedding planes, iron staining present. 27.8' - 28.1' Core is highly broken due to composition mudstone/shale and is likely due to coring. Iron staining along fractures, along bedding planes, and along fractures that are perpendicular to bedding angles. C2 Core is very intensely fractured and reduced to rubble in places due to drilling process. C2 28.0' - 31.0' 1310-1350. 28.1' - 28.6' Rubble zone, very intensely fractured, all pieces rounded. Iron staining, iron oxide, and manganese oxide observed along surfaces. Calcite precipitate also observed along fracture faces. On 2/27/18 used Ingersoll-Rand T4 rig to ream corehole and advance borehole to 35.5' using 5 7/8" hammer bit. Finished drilling at 0818.	
26	C-1	2.1' 67.7%	0%				
27							
28							
29	C-2	2.8' 100%	0%				
30				Dark gray (N 4/) SHALE. Laminated bedding. Trace limestone beds. Abundant slickenside surfaces (depositional). Upper 1' has iron oxide, manganese oxide, and calcite precipitate observed along fracture faces. Slightly to moderately decomposed becoming fresh and competent with depth. Weak to moderate field strength. Very intensely fractured along bedding plane surfaces, likely mechanical induced. Does not react with HCl. Change at 31.1'.			
31							
32	C-3	2.5' 73.5%	35.9%				
33				Gray (N 5/) INTERCLASTIC to MICROCRYSTALLINE LIMESTONE. Interclastic limestone changing to microcrystalline with depth; clasts decreasing to none at 32.0'. Clasts aligned parallel to bedding planes. Bedding planes are at 40°-60° angles. Little shale beds within limestone, up to 10mm thick, predominately less than 5mm. Bioturbation observed in shales. Fresh and competent. Strong field strength. Intensely to moderately fractured along bedding plane breaks likely mechanically induced. Some calcite precipitate observed along bedding planes. Breaks in beds are along bedding contacts of limestone and shale with slickenside surfaces observed along contacts (depositional). Calcite healed fractures running perpendicular to bedding planes. Soft sediment deformation observed. Reacts strongly with HCl.			
34							
35	NS			Bottom of Borehole = 35.5'. Piezometer GW-993 installed in borehole. See Monitoring Well Installation Report GW-993 for details.			
36							
37							
38							
39							
40							
41							
42							
43							
44							

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.


Well Number GW-993

Monitoring Well Installation Report

Site Name and Location: *EMDF Characterization Project, Oak Ridge, TN*	Completion Date: *3/8/18*
Coordinates: *29690.50N 38724.90E*	Borehole Depth (ft): *35.5*
Elevation Top of Casing (ft/MSL): *911.76*	Borehole Diameter (in):*5 7/8" (0'-35.5')*
Elevation Ground Surface (ft/MSL): *909.7*	Drilling Methods: *4 1/4" ID HSA, HQ Core with water, 5 7/8" hammer bit.*
Installed By: *Travis Morgan/Tri-State Drilling*	Completed Drilling: *2/27/18*
Supervised By: *Shay Beanland/Eagon & Associates, Inc.*	Drilling Water Used (gals):

Well Design

Component	Materials	Depth (LSD)	Elevation
Well Protector	4" Square Steel Protector w/Locking Lid	-2.4 - 2.6	912.1 - 907.1
Riser	2" ID Schedule 40 PVC	-2.1 - 23.0	911.8 - 886.8
Surface Seal	3' x 3' Concrete Pad	-0.5 - 0.5	910.2 - 909.2
Cement Grout	Cement Bentonite Grout	0.5 - 14.5	909.2 - 895.2
Bentonite Seal	Pel Plug 1/4" Coated Bentonite Pellets	14.5 - 19.8	895.2 - 889.9
Sand Pack	DSI "GP #2" Gravel Pack	19.8 - 34.3	889.9 - 875.4
Screen	2" ID Schedule 40 PVC, 10-Slot	23.0 - 33.0	886.8 - 876.7
Well Point Blank	2" ID Sch. 40 PVC Cap & Riser Section	33.0 - 34.3	876.7 - 875.4
Sand Pack Bottom	DSI "GP #2" Gravel Pack	34.3 - 35.5	875.4 - 874.2



Boring depth=35.5 ft.

Well Development

Well Depth (ft,TOC):	Depth to Water (ft,TOC):	Well Volume (gals):	Volume Purged (gals):
36.37	*5.45*	*5.3*	*89.5*

Development Method:
Surge block, bailer, mega purger whale pump

Date	Time	Cumulative Volume Removed (gals)	Temp (°C)	Specific Conductivity (µmhos/cm)	pH (S.U.)	Turbidity (NTU)
3/3/18	1425	79.5	15.2	308	7.29	80.4
3/3/18	1330	9.5	15.1	310	7.34	>1000
3/3/18	1340	24.5	14.9	292	7.27	269.0
3/3/18	1350	39.5	15.1	297	7.30	165.0
3/3/18	1400	54.5	15.2	295	7.26	141.0
3/3/18	1435	89.5	15.2	292	7.23	48.4

Recovery Data



Sampling Equipment:

Comments:

Grout mixing and placement information provided by Tri-State Drilling. Screen slot interval 23.2 - 32.9 bgs.

MONITOR WELL INSTALLATION 2 OAK RIDGE .GPJ EAGON.GDT 4/4/18

This page intentionally left blank.

Eagon & Associates, Inc.

BOREHOLE LOG

Site Name and Location: **EMDF Characterization Project Oak Ridge, TN**	Drilling Methods: 3 1/4" ID HSA, HQ3 Core with water circulation, 10" air hammer bit, 5 7/8" tricone bit with air/water.				Boring Number: GW-994
Drilling Firm: *Tri-State Drilling*	DATE	TIME	DEPTH DRILLED (ft)	WATER LEVEL (ft)	
Driller / Rig: *Shannon Snow/CME-550*					*Page 1 of 3*
Logged by: *David J. Sugar*	Sampling Methods: ST = Shelby Tube; WS = Waxed Sample; SP = Sand Pump; GP or DP = Direct Push; CT = Cuttings; SS = Split Spoon; CS = Continuous Sampler; C = Coring; NS = Not Sampled; B = Bailer				Start: *Time 0857, Date 2/16/18*
Coordinates: *29644.99N 38051.04E*					Finish: *Time 1253, Date 2/19/18*
Surface Elevation: *916.7 ft/MSL*					
Surface Conditions / Weather: *Flat gravel pad adjacent to haul road / 64°F, Light rain*					
Remarks:					

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
	NS			Gravel drilling pad.		3 1/4" ID HSA, continuous 2" OD, 2' drive split spoon, automatic 140 lb hammer.	
1	SS-1	0.7' 70%	2 3	Strong brown (7.5YR 5/6 - 5/8 and 4/6) CLAYEY SILT to SILTY CLAY. Trace medium to coarse sand. Trace fine gravel with depth, subrounded to subangular. Unsorted, massive to mottled appearance. High plasticity, toughness and dry strength. No dilatancy. Moist. Weathered. SUBSOIL.		Ran center plug while augering. No reaction with HCl. Trace roots.	CL
2							
3	SS-2	1.1' 55%	3 3 6 6			SS-2 Lab results: Moisture Content (MC) 22.8%. 1.0' - 1.3' Appears disturbed, probable soil fill associated with adjacent road.	
4							
5	SS-3	1.6' 80%	3 5 11 16	Below 4.3' mottled appearance with pale brown (2.5Y 7/3 - 7/4) areas, probably reduction associated with desiccation fractures. Below 5.1' slightly higher sand content, trace fine gravel, subangular to angular. Chert fragments. No roots observed below 5.1'.		On 2/18 used Ingersoll-Rand T-4 rotary rig to ream borehole to 35.0' using 10" hammer bit. Set permanent 6" conductor casing and sealed with cement-bentonite grout. SS-3 Lab results: MC 23.6%.	
6							
7	SS-4	1.4' 70%	5 9 16 18	Below 6.0' color changes to brown yellowish brown (10YR 5/3 - 5/6) consistent silty clay composition. 1/4" Diameter root at 8.1'. Change at 8.2'.		No reaction with HCl. SS-4 Lab results: MC 21.7%; 0.6% Gravel; 9.4% Sand; 90% Fines.	
8							
9	SS-5	2.0' 100%	10 16 19 29	Brown/grayish brown to dark grayish brown (10YR 5/2, 5/3 - 4/2) highly to completely weathered SHALE (SAPROLITE). Thinly bedded, approximate 45° bedding angle. Highly fractured with reddish to yellowish brown iron oxide coatings on fracture faces. Rock is easily pulverized and is moldable with added water. Low to medium plasticity. Low toughness, dilatancy. Soft rock classification/hard soil classification. Highly to completely weathered. Slightly moist to dry.		No reaction with HCl. Possibly ML-CL classification. Highly fractured. Below 10.0' black manganese oxide precipitate on fracture faces. SS-6 Lab results: MC 39.2%.	ML
10							
11	SS-6	2.0' 100%	13 15 12 20				
12						10.9' - 11.4' Yellowish brown to light yellowish brown (10YR 6/4 - 6/6) silty clay to clay seam, no rock structure, completely weathered limestone (?). Moist.	
13	SS-7	2.0' 100%	26 29 39 33	Below 12.0' color is highly variable but generally 10YR with the majority of the color in the grayish brown/dark grayish brown to yellowish brown/dark yellowish brown range (10YR 5/2 - 4/4 and 4/2 - 4/4) and light brownish gray/pale brown (10YR 6/2 - 6/3).			
14						Below 12.0' fractures have yellowish/reddish brown iron oxide precipitates.	
15	SS-8	1.7' 85%	9 23 15 16	14.6' - 14.8' Yellowish brown (10YR 6/4) silty clay to clay seam. No structure. Completely weathered limestone seam(?).		SS-8 Lab results: MC 24.4%. SS-10 Lab results: MC 16.6%.	
16							
17	SS-9	2.0' 100%	19 25 39 27	16.7' - 16.8' Yellowish brown to black (10YR 6/4 - 2/1) silty clay seam. Completely weathered limestone seam (?).		Bedding angle ~45°.	
18							
19	SS-10	1.4' 70%	9 28 51 29	Below 20.0' primarily light brownish gray, pale brown to grayish brown/brown (10YR 6/2 - 6/3 and 5/2 - 5/3) color.		Iron oxide continues to be associated with fractures and bedding breaks.	

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

EMDF Characterization Project
Oak Ridge, TN

BOREHOLE LOG

Boring Number GW-994

Remarks:

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
21	SS-11	2.0' 100%	27 32 36 37	Light brownish gray/pale brown to grayish brown/brown (10YR 6/2 - 6/3 and 5/2 - 5/3) highly to completely weathered SHALE (SAPROLITE). (Cont'd.)		No reaction with HCl. ~45° Bedding angle. Continues to be damp to slightly moist.	ML
22							
23	SS-12	1.3' 65%	6 9 3 5	22.8' - ~23.3' Dark grayish brown/olive brown (2.5Y 4/2 - 4/3) sandy zone. Structure is not apparent. Possible weathered glauconitic zone or sandy siltstone. Wet. First wet zone observed. Soft zone.		SS-12: Water on bottom 1.5' of split spoon sampler. Sample is very moist to wet.	
24							
25	SS-13	1.5' 75%	14 24 50 100	24.8' - 25.0' Reddish orange iron oxide, pronounced color, iron oxide precipitate/oxidation on fractures.		Below 24.0' split spoon sampler was wet/muddy on retrieval.	
26				Below 25.0' becomes layered with color variation greenish gray to dark greenish gray (N 6/ - N 4/) grayish brown to light olive brown (2.5Y 5/2 - 5/4) and very dark brown to very dark grayish brown (10YR 3/2 - 2/2).		SS-12 Lab results: MC 18.7%.	
27	SS-14	1.6' 80%	49 49 46 48	Underlying contact is transitional and subjective. May be as high as 25.0'.		SS-14 Lab results: MC 13.6%; 9.2% Gravel; 56.9% Sand; 33.9% Fines.	
28				Change at 28.0'.			
29	SS-15	1.4' 70%	19 52 100	Interbedded dark greenish gray (N 5/), grayish brown to light olive brown (2.5Y 5/2 - 5/4) and very dark brown to very dark grayish brown (10YR 3/2 - 2/2) SHALE and LIMESTONE. Some limestone seams may classify as calcareous siltstone. Thinly bedded. Soft to medium hard. Apparent bedding angle around 45° (disturbed from sampling process). Highly weathered and fractured. Carbonate not leached from interval. Limestone content is about 30%.		Limestone seam at contact (strong reaction with HCl). SS-15 Lab results: MC 13.3%.	
30	NS					28.3' - 28.6 Wet zone in weathered shale. Generally sample looks moist to very slightly moist.	
	SS-16	0.3'/100%	100/2				
31	NS			SS-16 Split spoon drove on limestone seam. Sample is broken from the sampling process.			
32						SS-17 Lab results: MC 15.9%.	
33	SS-17	1.5' 100%	17 83 100/4	SS-18 Recovery is mostly broken limestone with iron oxide possibly manganese oxide (dark brownish black).		1121 Finish split-spoon sampling. Bottom of augers at 34.0'. 1436 Start HQ3 core water circulation at 34.0' (cored over SS-18 interval C-1).	
34	NS			C-1 Core run from 34.0' - 34.6', overdrilled SS-18 interval. 0.6' Recovered, very broken sample, mostly limestone.			
	SS-18	0.6' 100%	73 100/1				
35	C-2	1.3' 62%	0%	Dark gray to very dark gray (N 4/ - 3/) SHALE and gray to dark gray (N 6/ - N 4/) LIMESTONE. Thinly bedded, beds are generally less than 0.2'. Core is highly broken, most correspond with bedding planes and are most likely mechanically induced. Moderate to intensely fractured. Moderate to strong field strength. Fresh to slightly decomposed. Trace healed calcite filled fractures oriented perpendicular to bedding.		Bedding is generally deformed, wavey. Shale does not react with HCl. Limestone has a strong reaction with HCl.	
36						SS-18 Lab results: MC 14.6%. C-2 34.6' - 36.7' 1454-1510. C-3 36.7' - 41.7' 1514-1545.	
37							
38				35.5' - 35.65' Gray to dark gray Interclastic Limestone seam.		37.6' - 38.1' Fracture, oriented 40° to bedding angle. Face has iron oxide weathering (yellow/reddish brown). Bedding angle ~45° - 50°.	
39	C-3	5.0' 100%	0%	37.4' - 38.1' Gray to dark gray (N 6/ - N 4/) Interclastic Limestone seam. Clasts are elliptical oriented along bedding, up to 1" along long axis, generally less than 1/2" on short axis. Strong reaction with HCl. Hard. Matrix is unweathered.			
40						41.8' - 42.6' Sample is highly broken, trace iron oxide on fracture faces. Too disturbed to determine orientation. At 42.8' fracture oriented perpendicular to bedding. Face is oxidized with iron oxide precipitates.	
41							
42				42.2' - 43.2' Thinly interbedded limestone and shale, mostly limestone, ~60° bedding angle, but orientation may be off.			
43	C-4	4.5' 90%	9%			44.9' - 45.4' Bedding breaks and fracture oriented perpendicular to bedding angle, faces are oxidized with iron oxide precipitate.	
44				44.5' - 44.7' Gray to dark gray limestone seam. Trace stylolites. Calcite filled fractures up to 2 mm width oriented perpendicular to bedding angle.		C-4 41.7' - 46.7' 1553-1610.	

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

EMDF Characterization Project Oak Ridge, TN	**BOREHOLE LOG**	Boring Number GW-994

Remarks:

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
46	C-4	4.5' 90%	9%	Interbedded dark gray to very dark gray (N 4/ - 3/) SHALE and gray to dark gray (N 6/ - N 4/) LIMESTONE. (Cont'd.) 44.8' - 46.0' Shale bed, unweathered/fresh. Trace calcite filled fractures oriented perpendicular to bedding.		Limestone reacts strong with HCl. Shale does not react. 45° Bedding angle.	
47 48 49	C-5	2.3' 70%	0%	Below 46.7' thinly bedded, broken along bedding planes. No weathering/iron oxide observed. Limestone beds, generally less than 0.1' with calcite filled fractures oriented perpendicular to bedding.		C-5 46.7' - 50.0' 1624-1656.	
50 51 52 53 54	NS						
55				Bottom of Borehole = 55.0'. Piezometer GW-994 installed in borehole. See Monitoring Well Installation Report GW-994 for details.		Finish drilling at 1656, 2/16/18. WL = 10.22 from GS at 1700 on 2/16/18. 2/17/18 WL = 6.25' from GS at 0830. On 2/19 used T3W rotary rig to ream corehole and advance borehole to 55.0' using 5 7/8" tricone bit with air and water circulation. Finished drilling at 1253.	
56 57 58 59 60 61 62 63 64 65 66 67 68 69							

BOREHOLE LOG V.2 OAK RIDGE.GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18


This page intentionally left blank.

Eagon & Associates, Inc.

Well Number GW-994

Monitoring Well Installation Report

Site Name and Location: *EMDF Characterization Project, Oak Ridge, TN*	Completion Date: *3/8/18*
Coordinates: *29644.99N 38051.04E*	Borehole Depth (ft): *55.0*
Elevation Top of Casing (ft/MSL): *918.89*	Borehole Diameter (in): *10" (0'-35.0'), 5 7/8" (35.0'-55')*
Elevation Ground Surface (ft/MSL): *916.7*	Drilling Methods: *3 1/4" ID HSA, HQ3 Core with water circulation, 10" air hammer bit, 5 7/8" tricone bit with air/water.*
Installed By: *Fred Reynolds/Tri-State Drilling*	Completed Drilling: *2/19/18*
Supervised By: *Shay Beanland/Eagon & Associates, Inc.*	Drilling Water Used (gals):



Well Design

Component	Materials	Depth (LSD)	Elevation
Well Protector	4" Square Steel Protector w/Locking Lid	-2.5 - 2.5	919.2 - 914.2
Riser	2" ID Schedule 40	-2.2 - 42.0	918.9 - 874.7
Surface Seal	3' x 3' Concrete Pad	-0.5 - 0.5	917.2 - 916.2
Conductor Casing	6" ID Sch. 40 PVC, Flush Threaded	-0.4 - 35.0	917.1 - 881.7
Cement Grout	Cement Bentonite Grout	0.5 - 32.3	916.2 - 884.4
Bentonite Seal	Pel Plug 1/4" Coated Bentonite Pellets	32.3 - 37.0	884.4 - 879.7
Sand Pack	DSI "GP #2" Gravel Pack	37.0 - 53.3	879.7 - 863.4
Screen	2" ID Schedule 40, 10-Slot	42.0 - 52.0	874.7 - 864.7
Well Point Blank	2" ID Sch. 40 PVC Cap & Riser Section	52.0 - 53.3	864.7 - 863.4
Sand Pack Bottom	DSI "GP #2" Gravel Pack	53.3 - 54.6	863.4 - 862.1
Natural Fill	Natural Fill	54.6 - 55.0	862.1 - 861.7


Well Development

Well Depth (ft,TOC):	Depth to Water (ft,TOC):	Well Volume (gals):	Volume Purged (gals):
55.54	*6.98*	*7.9*	*86.0*

Development Method:
Bailer, surge block, Tornado pump

Date	Time	Cumulative Volume Removed (gals)	Temp (°C)	Specific Conductivity (µmhos/cm)	pH (S.U.)	Turbidity (NTU)
3/1/18	1046	15.0	15.8	539.1	9.29	340.0
3/1/18	1107	40.0	15.5	315.9	8.53	92.1
3/1/18	1125	66.0	15.5	317.0	8.87	3.0
3/1/18	1137	76.0	15.6	312.5	8.73	1.9
3/1/18	1144	81.0	15.7	312.5	8.68	2.0
3/1/18	1152	86.0	15.6	310.5	8.63	4.3

Recovery Data



Sampling Equipment:

Comments:

Stainless steel centralizers set at 17' and 34' from ground surface. Washed sand pack and pellets in using tremie pipe. Grout mixing and placement information provided by Tri-State Drilling. Screen slot interval 42.2 - 51.9 bgs.

MONITOR WELL INSTALLATION 2 OAK RIDGE .GPJ EAGON.GDT 4/4/18

This page intentionally left blank.

Eagon & Associates, Inc.

BOREHOLE LOG

Site Name and Location: **EMDF Characterization Project Oak Ridge, TN**	Drilling Methods: 4 1/4" ID Hollow Stem Auger, HQ3 Core with water circulation.				Boring Number: GW-995
Drilling Firm: *Tri-State Drilling*	DATE	TIME	DEPTH DRILLED (ft)	WATER LEVEL (ft)	
Driller / Rig: *Shannon Snow/CME-550*					*Page 1 of 2*
Logged by: *David J. Sugar*	Sampling Methods:				Start / Finish
Coordinates: *29646.82N 38039.32E*	ST = Shelby Tube; WS = Waxed Sample; SP = Sand Pump; GP or DP = Direct Push; CT = Cuttings; SS = Split Spoon; CS = Continuous Sampler; C = Coring; NS = Not Sampled; B = Bailer				Time: 1435 / 0935
Surface Elevation: *916.3 ft/MSL*					Date: 2/26/18 / 2/27/18
Surface Conditions / Weather: *Moist/wet gravel pad / 53°F, Partly cloudy*					

Remarks: Borehole installed for the collection of geotech samples and installation of shallow piezometer.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
1–2	NS			See adjacent Borehole Log GW-994 for detailed lithologic descriptions and stratigraphic interpretations.		4 1/4" ID HSA, ran auger plug while augering.	CL
3–4	ST-1	1.95	900 PSI	Description based on inspection of bottom of ST-1 recovery. Strong brown (7.5 YR 5/6 - 5/8 and 4/6) and pale brown (2.5Y 7/3 - 7/4) mottled SILTY CLAY. Trace subangular to subrounded rock fragments. Highly weathered. Moist. High plasticity, toughness, and dry strength. SUBSOIL.		No reaction with HCl. Auger cutting bucket sample BS-1 collected from 4.0' - 6.0'.	
5–6	NS						
7–8	ST-2	2.0	1200 PSI	Description based on inspection of bottom of ST-2 recovery. Brown/grayish brown to dark grayish brown (10YR 5/2, 5/3 to 4/2). Highly to completely weathered SHALE (SAPROLITE). Approx. 45° angle bedding, appears in place. Reddish to yellowish brown iron oxide coats bedding breaks and fracture faces.		Auger cutting bucket sample BS-2 collected from 6.0' - 8.0'. No reaction with HCl. When crushed with water, does not completely come apart/crush. High plasticity and toughness is apparent.	
9–19	NS						

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.

EMDF Characterization Project
Oak Ridge, TN

BOREHOLE LOG

Boring Number GW-995

Remarks: Borehole installed for the collection of geotech samples and installation of shallow piezometer.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
21				Light brownish gray/pale brown to grayish brown/brown (10YR 6/2 - 6/3 and 5/2 - 5/3) highly to completely weathered SHALE (SAPROLITE). (Cont'd.)		Limestone not present from 25.0' - 25.5'. No reaction with HCl.	CL
22	NS						
23				Below 25.0' grayish brown/dark grayish brown to light olive brown (2.5Y 5/2 - 4/2, 4/3) SHALE (SAPROLITE). Highly broken sample (gravel size). Generally have iron/manganese oxide coatings on most faces. Highly disturbed.		Below 25.0' switch to HQ3 core, water circulation. Start coring at 1540.	
24				Below 25.5' relatively intact core, very weathered, broken along bedding planes, thinly bedded, iron oxide on bedding contacts.		C-1 Lost recovery is from the top and bottom of the run. First 0.5' of recovery is gravel size (brown) rock fragments. Core barrel tip (lifter) was stuffed.	
25				Below 25.9' mostly unweathered, fractures are typically oxidized.			
26				Change at 25.9'.			
27	C-1	2.9' 58%	0%	Gray to very dark gray (N 4/ - N 6/) and (5YR 4/1 - 3/1) INTERBEDDED SHALE and LIMESTONE. Thinly bedded, generally <0.1' beds, ~45° bedding angle. Approximately 30% limestone or calcareous siltstone (generally lighter gray color hues (N 6/ and N 5/).		Highly/intensely fractured. Shale does not react with HCl. Limestone reacts stronger with HCl.	
28				Below 26.0' most bedding breaks (generally at 0.1' - 0.2' intervals have secondary calcite on bedding surfaces. Breaks perpendicular to bedding are also common and most have secondary calcite on fracture surfaces.		Finish coring at 1608. Advance HSA over corehole to completion depth. C-1 25.0' - 30.0' 1540-1608.	
29				26.5' - 27.0' Trace yellowish/reddish brown iron oxide on fracture surfaces.			
30				Oxidation not observed below 27.0', but continues to be highly fractured and broken with secondary calcite along breaks.		End 2/26/18, 1700 at 33.0'. Begin 2/27/18, 0925, 38°F, sunny.	
31							
32	NS						
33							
34				Bottom of Borehole = 34.0'.		2/27/18 Completed drilling at 0935.	
35				Piezometer GW-995 installed in borehole. See Monitoring Well Installation Report GW-995 for details.			
36							
37							
38							
39							
40							
41							
42							
43							
44							

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.


Well Number GW-995

Monitoring Well Installation Report

Site Name and Location: *EMDF Characterization Project, Oak Ridge, TN*	Completion Date: *3/8/18*
Coordinates: *29646.82N 38039.32E*	Borehole Depth (ft): *34.0*
Elevation Top of Casing (ft/MSL): *918.76*	Borehole Diameter (in):*7 1/2"*
Elevation Ground Surface (ft/MSL): *916.3*	Drilling Methods: *4 1/4" ID Hollow Stem Auger, HQ3 Core with water circulation.*
Installed By: *Shannon Snow/Tri-State Drilling*	Completed Drilling: *2/27/18*
Supervised By: *David J. Sugar/Eagon & Associates, Inc.*	Drilling Water Used (gals): *~750*

Well Design

Component	Materials	Depth (LSD)	Elevation
Well Protector	4" Square Steel w/Locking Lid	-2.8 - 2.2	919.1 - 914.1
Riser	2" ID Schedule 40 PVC	-2.5 - 22.1	918.8 - 894.2
Surface Seal	3' x 3' Concrete	-0.5 - 0.5	916.8 - 915.8
Cement Grout	Cement Bentonite Grout	0.5 - 17.0	915.8 - 899.3
Bentonite Seal	Pel-Plug 1/4" Coated Bentonite Pellets	17.0 - 19.2	899.3 - 897.1
Sand Pack	DSI GP #2 Gravel Pack	19.2 - 33.4	897.1 - 882.9
Screen	2" ID Schedule 40 PVC, 10-Slot	22.1 - 32.1	894.2 - 884.2
Well Point Blank	2" ID Sch. 40 PVC Cap & Riser Section	32.1 - 33.4	884.2 - 882.9
Sand Pack Bottom	DSI GP #2 Gravel Pack	33.4 - 34.0	882.9 - 882.3



Boring depth=34.0 ft.


Well Development

Well Depth (ft,TOC):	Depth to Water (ft,TOC):	Well Volume (gals):	Volume Purged (gals):
35.85	*11.93*	*3.9*	*156.0*

Development Method:
Surge block, bailer, mega purger whale pump

Date	Time	Cumulative Volume Removed (gals)	Temp (°C)	Specific Conductivity (µmhos/cm)	pH (S.U.)	Turbidity (NTU)
3/2/18	0900	10.5	15.7	345	7.11	>1000
3/2/18	0940	33.0	15.0	342	7.12	>1000
3/2/18	1510	63.0	15.5	318	7.20	>1000
3/2/18	1610	96.0	15.2	320	7.16	273.0
3/2/18	1705	126.0	15.1	324	7.21	60.4
3/3/18	0815	156.0	15.1	317	7.15	5.6

Recovery Data



Sampling Equipment:

Comments:

Grout mixing and placement information provided by Tri-State Drilling. Screen slot interval 22.2 - 32.0 bgs.

MONITOR WELL INSTALLATION 2 OAK RIDGE .GPJ EAGON.GDT 4/4/18

This page intentionally left blank.

Eagon & Associates, Inc.

BOREHOLE LOG

Site Name and Location: **EMDF Characterization Project Oak Ridge, TN**	Drilling Methods: 2 1/4" HSA, HQ3 Core w/water, 10" air hammer bit, 5 7/8" tricone bit w/air/water.				Boring Number: GW-998
Drilling Firm: *Tri-State Drilling*	DATE	TIME	DEPTH DRILLED (ft)	WATER LEVEL (ft)	
Driller / Rig: *Fred Reynolds/Mobile 42C*	2/14/18	1654	19.0	1.41	*Page 1 of 2*
Logged by: *Ryan Hansel*	Sampling Methods: ST = Shelby Tube; WS = Waxed Sample; SP = Sand Pump; GP or DP = Direct Push; CT = Cuttings; SS = Split Spoon; CS = Continuous Sampler; C = Coring; NS = Not Sampled; B = Bailer				Start: *Time 1355, Date 2/14/18* / Finish: *Time 0919, Date 2/20/18*
Coordinates: *29021.82N 37742.36E*					
Surface Elevation: *877.7 ft/MSL*					
Surface Conditions / Weather: *Gravel pad, moist / 50°F, Cloudy, 0-5 SW*					

Remarks: Set up on cone located ~6' south of staked location.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
	NS			ROAD BASE. Change at 1.0'.		Ran 2 1/4" HSA (7" OD) w/center plug while augering. Continuous 2" OD, 2' drive split spoon, 140 lb hydraulic hammer.	
1							ML/CL
2	SS-1	1.2' 60%	3 3 4 6	Light olive brown to olive brown (2.5Y 5/3 - 4/2) CLAYEY SILT. Trace fine to coarse grained sand. Trace to little angular shale fragments (up to 1" diameter). Medium to stiff. Massive. Cohesive. Low plasticity. No dilatancy. Weathered. Iron and manganese oxide on surface of shale clasts. Moist. No reaction with HCl. RESIDUAL SOIL. Trace silt partings 3.2' - 3.3'. Strong reaction with HCl. Roots present. Shale clasts are becoming oriented in same direction.		On 2/18/18, used Ingersoll-Rand T3W rotary rig to ream borehole to 22.0' using 10" air hammer bit. Set permanent 6" PVC casing and sealed with cement bentonite grout.	
3							
4	SS-2	2.0' 100%	3 6 10 15	Underlying contact is transitional. Change at 4.0'. Grayish brown to dark grayish brown highly weathered SHALE (SAPROLITE). Shale fragments are weathered to silt and clay. Shale fragments have trace to little iron and manganese oxide on bedding surface. Laminated to thinly bedded (beds are 40°-50°). Very Stiff. Cohesive. Medium plasticity. No dilatancy. Weathered. Dry to moist. Moisture content decreasing with depth. SAPROLITE. 5.7' - 6.0' Saprolite has been weathered down to a silty clay. Abundant with iron and manganese oxide. Reddish brown to strong brown in color. (CL).			CL
5							
6	SS-3	2.0' 100%	9 11 12 16				
7							
8	SS-4	1.8' 90%	7 11 10 10	Shale is becoming harder with depth. Iron and manganese oxide present along bedding surfaces.		SS-1 Lab results: Moisture Content (MC) 18.9%. SS-2 Lab results: MC 22%.	
9				9.0' - 9.4' Shale (saprolite) has been weathered completely to a silty clay. Abundant with iron and manganese oxide. Reddish brown to strong brown in color. (CL).			
10	SS-5	1.6' 80%	6 12 12 9	9.4' - 9.6' Iron oxide present on bedding surfaces. Below 9.6' shale becomes brown (7.5YR 5/2 - 4/2) in color. Iron oxide becomes trace. Abundant manganese oxide staining on bedding surfaces.		SS-3 Lab results: MC 27.4%. SS-4 Lab results: MC 18.6%; 4.3% Gravel; 58.4% Sand; 37.3% Fines.	
11							
12	SS-6	1.5' 75%	2 4 3 10	Below 11.0' saprolite (shale) becomes grayish olive (10Y 5/2). Trace to few yellow fine grained silty sand partings. Saprolite is almost completely weathered to a silty clay. Little to some iron and manganese oxide along bedding surfaces. Wet.		SS-5 Lab results: MC 26%.	
13							
14	SS-7	1.5' 75%	3 16 9 9	Below 13.2' saprolite (shale) becomes harder. Sampling process has almost destroyed bedding structure. Below 14.0' becomes dark gray to very dark gray (N 4/ - 3/). Iron oxide becomes trace. Manganese oxide becomes trace. Trace subrounded siltstone clasts. Sampling method has partially destroyed structure.		SS-7 Lab results: MC 23.8%. After SS-8 driller noted ~12' of water on rods.	
15							
16	SS-8	1.5' 75%	7 11 9 6	Below 15.5' trace subrounded limestone clasts. Iron and manganese oxide on clast surfaces. Strong reaction with HCl. Limestone clasts are increasing with depth.		SS-9 Lab results: MC 15.4%. Measured contact from bottom of SS-9 due to high blow counts.	
17							
18	SS-9	1.6' 80%	4 7 48 50	Change at 18.6'.		Switch to HQ3 core with water.	
19	C-1	2.0' 95.2%	0%	Dark brown to very dark brown (7.5YR 3/2 - 2.5/2) SHALE. Laminated to thinly bedded. Trace limestone beds and partings. Soft sediment deformation along shale and limestone. Intact. Moderate field strength. Moderately decomposed. Moderately disintegrated.		1525 Auger refusal 19.0'. 1654 DTW = 1.41 BGS. Added 1/2 bag 3/8" bentonite chips to hole and installed PVC	

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.

EMDF Characterization Project Oak Ridge, TN	**BOREHOLE LOG**	Boring Number GW-998

Remarks: Set up on cone located ~6' south of staked location.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
21	C-1	2.0' 95.2%	0%	Strong reaction with HCl after scratched with knife. Intensely to very intensely fractured, most are along bedding planes and healed with calcite. Calcite veins are stained with iron and manganese oxide. Bedding is between 40° and 50°. 20.3' - 20.6' Fracture perpendicular to bedding plane healed with calcite, iron and manganese oxide. 20.6' - 20.8' Fracture perpendicular to bedding plane with iron and manganese oxide. Change at 22.2'.		temporary surface casing to 19.0'. 2/15/18 at 0840 DTW=2.51 BGS. C-1 19.0' - 21.1', 1041-1119. 21.1' - 22.2' Multiple breaks along bedding plane. All have iron and manganese oxide. Strong reaction with HCl on limestone (shale when scratched).	
22							
23	C-2	4.8' 96%	13.6%	Greenish gray (10Y 6/1 - 5/1) LIMESTONE. Trace to few thin beds of shale. Contacts with shale are wavy with soft sediment deformation. Thinly bedded, with beds at 40°-50° angles. Strong. Slightly decomposed. Slightly disintegrated. Intensely to moderately fractured. Most breaks are along bedding planes, probably mechanically induced. 22.5' - 22.6' Multiple breaks along and perpendicular to bedding plane with iron and manganese oxide. Change at 23.8'.		22.6' Fracture perpendicular to bedding plan with iron and manganese oxide. 23.6 - 23.9' Horizontal fractures with iron and manganese oxide. Shale beds increasing with size and quantity with depth.	
24							
25							
26				Laminated to thinly INTERBEDDED SHALE and LIMESTONE. Limestone is greenish gray (10Y 6/1 - 5/1). Massive. Microcrystalline. Strong. Shale is dark gray to very dark gray (N 4/ - 3/). Laminated to thinly bedded. Strong. Shale and limestone beds are wavy with soft sediment deformation and cross bedding. Slightly disintegrated. Slightly decomposed. Moderately to intensely fractured along bedding planes with some completely healed with calcite. Change at 26.2'.		C-2 21.1' - 26.1', 1041-1119. Becoming less weathered with depth. 26.0' Horizontal fracture with iron oxide.	
27							
28	C-3	4.2' 91.3%	12.6%	Greenish gray (10Y 6/1 - 5/1) LIMESTONE. Trace glauconite grains. Trace mudstone stringers. Massive. Microcrystalline. 26.8' - 27.0' subangular limestone clasts incorporated into limestone matrix. Strong. Slightly decomposed. Slightly disintegrated. Moderately fractured with some iron and manganese oxide on fracture faces. Below 28.0' shale beds present and increasing with depth. Change at 28.2'.		26.8' - 27.2' Vertical fracture with iron and manganese oxide. C-3 26.1' - 30.7', 1140-1220. Driller noted blocked tip in barrel. Pull run at 30.7'.	
29							
30							
31	C-4	0.4'/100%	0%			27.4' Fracture perpendicular to bedding plane with iron oxide.	
32	C-5	5.0' 100%	13.8%	Dark brown to very dark brown (7.5YR 3/2 - 2.5/2) SHALE. Trace to few limestone beds and partings. Laminated to thinly bedded, with beds at 40°-50° angles. Soft sediment deformation and turbidation. Abundant slickensides along bedding plane. Strong. Fresh to slightly decomposed. Moderately fractured with little calcite healing of fractures. Most breaks are along bedding planes. Strong reaction with HCl when scratched. Below 31.1' shale becomes olive green in color due to weathering. Iron oxide present. Change at 31.5'.		28.0', 28.1', 28.2' Fracture along bedding plane with iron and manganese oxide. C-4 30.7' - 31.1', 1225-1236. 31.6' Fracture along bedding plane with iron oxide. 0.05" Iron halo on each side. C-5 31.1' - 36.1', 1349-1425.	
33							
34				Gray to very dark gray (N 5/ - 3/) LIMESTONE. Massive with trace angular (40°-50°) shale beds and partings with soft sediment deformation. Trace glauconite grains. 31.6' - 32.0' limestone is oolitic. Oolites are round (~1mm diameter). Strong. Slightly decomposed. Very intensely fractured. Multiple fractures along and perpendicular to bedding plane. Some fractures are healed with mudstone. Change at 32.8'.		31.7' - 32.2' Multiple fractures along and perpendicular to bedding planes. Iron oxide present on all fractures. 31.7' - 31.9' Fracture healed with mudstone. 32.8' Break along bedding plane with iron and manganese oxide.	
35							
36							
37	C-6	3.0'	37.7%	Dark reddish brown (5YR 3/2 - 2.5/2) SHALE. Trace limestone beds and partings. Laminated to thinly bedded. Abundant slickensides along bedding plane. Fresh to slightly decomposed. Moderately to intensely fractured. Most breaks are along bedding plane and mechanically induced. Some are perpendicular to bedding and healed with calcite. Strong reaction with HCl when scratched. Below 37.0' limestone clasts/inclusions oriented with bedding and increasing with depth. Underlying contact is transitional. Change at 37.5'.		32.8' - 33.0' Shale is iron stained and discolored. C-6 36.1' - 40.0', 1435-1504. 36.2' Break along bedding plane with iron oxide. 38.0' - 38.4' Limestone is iron stained and discolored.	
38							
39							
40				Light brownish gray to grayish brown (10YR 4/2 - 5/2) LIMESTONE. Thinly bedded. Trace shale beds and partings. Trace marine fossils present along shale bedding breaks. Soft sediment deformation. Moderately decomposed. Slightly to moderately fractured. Most fractures along bedding plane have iron oxide on fracture faces. Strong reaction with HCl. 38.3' Fracture with iron oxide. 38.3' - 38.8' Fracture vertical along core axis with iron oxide. 39.6' Fracture perpendicular to bedding plane with iron and manganese oxide.		2/15/18, 1515, DTW = 11.70 BGS.	
41							
42	NS					On 2/20/18, used T3W rotary rig to ream corehole and advance to 45.0' using 5 7/8" tricone bit with water and air circulation. Finished drilling at 0919.	
43							
44				Bottom of Borehole at 45.0'. Piezometer GW-998 installed in borehole. See Monitoring Well Installation Report GW-998 for details.			

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.

Well Number GW-998

Monitoring Well Installation Report

Site Name and Location: *EMDF Characterization Project, Oak Ridge, TN*	Completion Date: *3/8/18*
Coordinates: *29021.82N 37742.36E*	Borehole Depth (ft): *45.0*
Elevation Top of Casing (ft/MSL): *880.18*	Borehole Diameter (in): *10" (0'-22.0'), 5 7/8" (22.0'-45.0')*
Elevation Ground Surface (ft/MSL): *877.7*	Drilling Methods: *2 1/4" HSA, HQ3 Core w/water, 10" air hammer bit, 5 7/8" tricone bit w/air/water.*
Installed By: *Shannon Snow/Tri-State Drilling*	Completed Drilling: *2/20/18*
Supervised By: *David J. Sugar/Eagon & Associates, Inc.*	Drilling Water Used (gals): *~1500*

Well Design

Component	Materials	Depth (LSD)	Elevation
Well Protector	4" Square Steel w/Locking Lid	-2.8 - 2.2	880.5 - 875.5
Riser	2" ID Schedule 40 PVC	-2.5 - 26.6	880.2 - 851.1
Surface Seal	3' x 3' Concrete	-0.5 - 0.5	878.2 - 877.2
Conductor Casing	6" ID Schedule 40 PVC, Flush Threaded	-0.4 - 22.0	878.1 - 855.7
Cement Grout	Cement Bentonite Grout	0.5 - 21.7	877.2 - 856.0
Bentonite Seal	Pel-Plug 1/4" Coated Bentonite Pellets	21.7 - 24.0	856.0 - 853.7
Sand Pack	DSI GP #2 Gravel Pack	24.0 - 37.9	853.7 - 839.8
Screen	2" ID Schedule 40 PVC, 10-Slot	26.6 - 36.6	851.1 - 841.1
Well Point Blank	2" ID Sch. 40 PVC Cap & Riser Section	36.6 - 37.9	841.1 - 839.8
Sand Pack Bottom	DSI GP #2 Gravel Pack	37.9 - 40.0	839.8 - 837.7
Bentonite Seal	Pel-Plug 1/4" Coated Bentonite Pellets	40.0 - 45.0	837.7 - 832.7


Well Development

Well Depth (ft,TOC):	Depth to Water (ft,TOC):	Well Volume (gals):	Volume Purged (gals):
40.37	*4.55*	*5.8*	*405.0*

Development Method:
Bailer, surge block, Tornado pump

Date	Time	Cumulative Volume Removed (gals)	Temp (°C)	Specific Conductivity (µmhos/cm)	pH (S.U.)	Turbidity (NTU)
2/26/18	1001	5	15.0	962	7.23	>1000
2/26/18	1020	30	15.7	412	7.09	>1000
2/26/18	1050	105	15.8	364	6.86	104.0
2/26/18	1130	205	15.7	356	6.81	80.6
2/26/18	1210	305	15.8	351	6.79	56.2
2/26/18	1250	405	15.8	345	6.87	33.8


Recovery Data



Sampling Equipment:

Comments:

Grout mixing and placement information provided by Tri-State Drilling. Screen slot interval 26.8 - 36.5 bgs.



Boring depth=45.0 ft.

MONITOR WELL INSTALLATION 2 OAK RIDGE .GPJ EAGON.GDT 4/4/18

This page intentionally left blank.

Eagon & Associates, Inc.

BOREHOLE LOG

Site Name and Location: **EMDF Characterization Project Oak Ridge, TN**	Drilling Methods: 4 1/4" ID HSA, HQ Core w/water.				Boring Number: GW-999
Drilling Firm: *Tri-State Drilling*	DATE	TIME	DEPTH DRILLED (ft)	WATER LEVEL (ft)	
Driller / Rig: *Fred Reynolds/Mobile B42C*					*Page 1 of 2*
Logged by: *Shay Beanland*	Sampling Methods: ST = Shelby Tube; WS = Waxed Sample; SP = Sand Pump; GP or DP = Direct Push; CT = Cuttings; SS = Split Spoon; CS = Continuous Sampler; C = Coring; NS = Not Sampled; B = Bailer				Start: *Time 1050, Date 2/20/18* / Finish: *Time 1045, Date 3/2/18*
Coordinates: *29025.01N 37750.58E*					
Surface Elevation: *877.6 ft/MSL*					
Surface Conditions / Weather: *Gravel pad, dry / 70°F, Sunny*					

Remarks: Boring installed for collection of geotech samples and for installation of shallow piezometer.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
1	HSA			See Borehole Log for adjacent boring GW-998 for detailed lithologic description and stratigraphic interpretation.		Ran 4 1/4" ID HSA with center plug to target depths of Shelby tube and bucket samples. Pushed Shelby tubes. Advanced augers to target depth and switched to HQ Core with water. Then reamed borehole with 4 1/4" ID HSA using CME 550. Pushed Shelby tube 2.0' down. Pressure noted in 'blows/6 in' column.	
2							
3	ST-1	1.7	800 PSI 900 PSI 900 PSI 1300 PSI				
4							
5	HSA			At 4.5' sample was light bluish gray SHALE (SAPROLITE). Fracture noted on bottom of sample with iron oxide and manganese oxide on surface, could be bedding plane surface.			
6	ST-2	0.85	1100 PSI	At 5.85' sample was gray (7.5YR 6/1 - 5/1) SAPROLITE. Iron and manganese oxide noted on bedding plane surfaces. Micaceous.		Pushed Shelby tube 0.85' before refusal.	
7	HSA		1500 PSI/ 0.35'				
8						Bulk sample collected from 4.0' - 4.5' of cuttings from augers.	
9						Bulk sample (BS-2) collected from 5.0' - 6.0'.	
10							
11	ST-3	2.0	850 PSI 900 PSI 1000 PSI			Pushed Shelby tube (ST-3) 2.0' from 10.5' to 12.5'. Shelby tube is wet.	
12							
13	HSA		1000 PSI	At 12.5' sample was light brownish gray to grayish brown (2.5Y 6/2 - 5/2) SHALE (SAPROLITE). Iron and manganese oxide observed in bedding plane surfaces. Wet.			
14							
15							
16							
17	SS-1	1.2	15 41 50/3	Gray to grayish brown (2.5Y 5/1 - 5/2) highly weathered SHALE (SAPROLITE). Laminated bedding structure. Easily crumbled with hand. Iron staining and precipitate throughout bedding planes. Weathered. Low to medium plasticity and toughness. Moist.		Below 17.0' reacts with HCl. Auger refusal at 19.1'. Spoon was bent when retrieved.	
18	HSA			Change at 18.5'.			
19	SS-2	0.9	7 15 50/3.5	Gray to olive gray (5Y 5/1 - 4/2) SHALE. Laminated bedding. Decrease in iron and manganese oxide along bedding planes to little. Below 19.0' olive gray (5Y 5/2 - 4/2) limestone. Very intensely fractured. Calcite precipitate/crystals along fracture surfaces. Wet.		1430-1500 Went for water to start coring. WL = 5.85 at 1511, TD = 19.1.	

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.

EMDF Characterization Project
Oak Ridge, TN

BOREHOLE LOG

Boring Number
GW-999

Remarks: Boring installed for collection of geotech samples and for installation of shallow piezometer.

Depth (feet)	Sample Method	Sample Recovery (feet or %)	Blows/6 in or RQD	SAMPLE DESCRIPTION	Graphic Log	Remarks	USCS
21	C-1	2.2' 100%	56.4%	Light gray to greenish gray (N 7/ - 10Y 6/1) LIMESTONE. Microcrystalline. Trace to few thin beds of shale. Shale beds are wavey with soft sediment deformation and bioturbation. Beds are at 40°-50° angles. Shale beds range in thickness from less than 1mm to up to 5mm in thickness. Trace glauconite crystals. Trace calcite seams/stringers along bedding planes. Trace calcite crystals. Field strength is strong. Slightly decomposed. Sightly disintegrated. Intensely to moderately fractured with iron and manganese oxide and calcite precipitate. 20.45' - 20.65' Shale bed. 20.75' - 21.1' Shale bed. Very intensely fractured along bedding plane/fracture surfaces. Trace iron staining observed throughout core, predominately along shale beds. Below 21.1' limestone becomes clastic with clasts elongated and oriented parallel to bedding plane. Bottom of Borehole = 22.0'. Piezometer GW-999 installed in borehole. See Monitoring Well Installation Report GW-999 for details.		Auger refusal at 19.1', split spoon sampled to 19.3'. Switching over to HQ Core. C-1: 19.3' - 21.5' 1645-1711. 19.7' - 19.9' 45° angle fracture with iron staining present on surface. 20.2' - 20.4' 40° angle fracture with iron staining along bedding plane. 20.45' - 20.6' 40° angle fracture along bedding plane. 20.6' - 20.75' 30° angle fracture, iron and manganese oxide along face, fractures along bedding plane. 21.1' - 21.25' 60° angle fracture. 2/20/18 Done for day at 1711. 2/21/18 at 0810 WL = 0.90', TD = 21.5'. Start augering hole at 0834 from 19.1'. 0855 Stopped augering, had only gone 2" with rig. Pulling rig off hole and setting temporary 6" casing to 19.0'. On 3/2/18 used CME-55 to overdrill corehole and advance borehole to 22.0' using 4 1/4" ID HSA augers. Completed drilling at 1045.	
22	NS						
23							
24							
25							
26							
27							
28							
29							
30							
31							
32							
33							
34							
35							
36							
37							
38							
39							
40							
41							
42							
43							
44							

BOREHOLE LOG V.2 OAK RIDGE .GPJ CONTAINER CRAFT TEMPLATE WITH PID.GDT 4/4/18

Eagon & Associates, Inc.

Well Number GW-999

Monitoring Well Installation Report

Site Name and Location: *EMDF Characterization Project, Oak Ridge, TN*	Completion Date: *3/8/18*
Coordinates: *29025.01N 37750.58E*	Borehole Depth (ft): *22.0*
Elevation Top of Casing (ft/MSL): *880.11*	Borehole Diameter (in):*7 1/2" (0'-22.0')*
Elevation Ground Surface (ft/MSL): *877.6*	Drilling Methods: *4 1/4" ID HSA, HQ Core w/water.*
Installed By: *Shannon Snow/Tri-State Drilling*	Completed Drilling: *3/2/18*
Supervised By: *Shay Beanland/Eagon & Associates, Inc.*	Drilling Water Used (gals):

Well Design

Component	Materials	Depth (LSD)	Elevation
Well Protector	4" Square Steel Protector w/Locking Lid	-2.8 - 2.2	880.4 - 875.4
Riser	2" ID Schedule 40	-2.5 - 10.3	880.1 - 867.4
Surface Seal	3' x 3' Concrete Pad	-0.5 - 1.0	878.1 - 876.6
Bentonite Seal	Enviro Plug Medium Chips	1.0 - 4.8	876.6 - 872.8
Bentonite Seal	Pel Plug 1/4" Coated Bentonite Pellets	4.8 - 8.3	872.8 - 869.4
Sand Pack	DSI "GP #2" Gravel Pack	8.3 - 21.6	869.4 - 856.0
Screen	2" ID Schedule 40, 10-Slot	10.3 - 20.3	867.4 - 857.3
Well Point Blank	2" ID Schedule 40 Cap & Riser Section	20.3 - 21.6	857.3 - 856.0
Natural Fill	Natural Fill	21.6 - 22.0	856.0 - 855.6


Well Development

Well Depth (ft,TOC):	Depth to Water (ft,TOC):	Well Volume (gals):	Volume Purged (gals):
24.10	*3.41*	*3.4*	*114.5*

Development Method:
Surge block, bailer, mega purger whale pump

Date	Time	Cumulative Volume Removed (gals)	Temp (°C)	Specific Conductivity (µmhos/cm)	pH (S.U.)	Turbidity (NTU)
3/5/18	1005	12.0	14.7	546	7.15	>1000
3/5/18	1015	24.5	15.3	461	7.13	>1000
3/5/18	1040	44.5	15.1	440	7.15	>1000
3/5/18	1100	64.5	15.1	432	7.08	97.4
3/5/18	1140	94.5	15.4	425	6.98	27.9
3/5/18	1200	114.5	15.6	422	6.95	23.4


Recovery Data



Sampling Equipment:

Comments:

Grout mixing and placement information provided by Tri-State Drilling. Screen slot interval 10.4 - 20.1 bgs.




MONITOR WELL INSTALLATION 2 OAK RIDGE.GPJ EAGON.GDT 4/4/18

This page intentionally left blank.

PHASE I CHARACTERIZATION
ENVIRONMENTAL MANAGEMENT DISPOSAL FACILITY
CENTRAL BEAR CREEK VALLEY SITE (7c)

This page intentionally left blank.

GW-978





B-97

GW-978 56.1' – 71.5' Sand Pack Interval
59.5' – 69.6' Screened Interval

GW-978





B-98

GW-978 56.1' – 71.5' Sand Pack Interval
59.5' – 69.6' Screened Interval

GW-979





GW-979 21.2' – 37.8' Sand Pack Interval
26.3' – 36.3' Screened Interval

21.1'- 21.3' Very intensely fractured along bedding planes and some at an angle perpendicular to bedding direction. Iron staining throughout.

B-99

GW-980

B-100





GW-980R 55.0' – 72.3' Sand Pack Interval
59.9' – 70.0' Screened Interval


67.0'- 67.3' Bedding plane break with apparent depositional slickensides. Trace calcite coating and fine pyrite crystals

59.2'- 60.1' Zone with healed (calcite filled) fractures, generally oriented perpendicular to bedding angle. At 59.2', 59.5', and 59.8' fractures are open but appear broken by the drilling process

GW-981

B-101






GW-981 20.0' – 34.0' Sand Pack Interval
22.1' – 32.1' Screened Interval

24.0'- 24.9' Broken zone, fractures oriented perpendicular to bedding (possibly associated with healed fractures where the calcite infilling has been removed). Trace thin secondary calcite on fracture faces.

25.4'- 26.3' High angle fracture, jagged/rough face. Trace secondary calcite and possibly celestite.

GW-982

B-102





GW-982 99.2' – 114.5' Sand Pack Interval
102.1' – 112.1' Screened Interval

102.0' – 102.3' Fracture zone/bedding breaks. Faces are oxidized with iron oxide coatings. Continues to be intensely fractured. Bedding angle is near 45°.

107.6' – 107.9' Fracture 90° to bedding plane. Face has thin coating of calcite. No oxidation.

GW-986

B-103





GW-986 38.6' – 48.0' Sand Pack Interval
41.0' – 46.0' Screened Interval

At 49.8' Fracture (appears mechanically broken) ~ 2mm calcite filled, broken face is striated at orientation of 30° from the fracture angle

At 50.5' Horizontal break, rough face. Trace pyrite.

GW-987





GW-987 13.3' – 27.9' Sand Pack Interval
16.1' – 26.1' Screened Interval

17.5' – 20.0' Interval highly fractured. Primarily along bedding planes, trace fractures oriented perpendicular to bedding. Fracture faces are generally coated with manganese oxide precipitates.

B-104

GW-987

B-105







GW-987 13.3' – 27.9' Sand Pack Interval
16.1' – 26.1' Screened Interval

21.4' – 21.7' Dark yellowish brown to black iron oxide/manganese oxide on bedding breaks

GW-987





B-106

GW-987 13.3' – 27.9' Sand Pack Interval
16.1' – 26.1' Screened Interval

22.4' – 22.8' Several bedding breaks with oxidation (yellowish brown) faces. Fracture perpendicular to bedding angle is also oxidized

At 23.2'Secondary calcite on bedding break, thin coating.

GW-988






GW-988 59.6' – 74.0' Sand Pack Interval
61.9' – 71.9' Screened Interval

70.0' – 70.6' Vertical fracture along the bedding plane that appears to turn from 60° to near vertical. Fractures are fresh.

B-107

GW-989






B-108


GW-989 30.0' – 45.0' Sand Pack Interval
33.6' – 43.6' Screened Interval

34.1' – 34.3' Broken zone, bedding breaks and fractures perpendicular to bedding. Oxidized with iron oxide precipitates on fracture faces.

32.0' – 33.6' Most bedding breaks are oxidized with iron oxide precipitates on fracture surfaces.

GW-989





B-109


GW-989 30.0' – 45.0' Sand Pack Interval
33.6' – 43.6' Screened Interval

32.0' – 33.6' Most bedding breaks are oxidized with iron oxide precipitates on fracture surfaces.

34.1' – 34.3' Broken zone, bedding breaks and fractures perpendicular to bedding. Oxidized with iron oxide precipitates on fracture faces.

GW-989






B-110

GW-989 30.0' – 45.0' Sand Pack Interval
33.6' – 43.6' Screened Interval

41.9' – 42.3' Broken zone with iron oxide along bedding planes and perpendicular fractures. Oxidized with iron oxide precipitates on fracture faces.

GW-993





GW-993 19.8' – 35.5' Sand Pack Interval
23.0' – 33.0' Screened Interval

26.0' – 26.7' Multiple high angle fractures with iron and manganese oxide precipitate.

27.3' – 27.5' 40-50 degree fracture, iron staining present.

B-111

GW-993





GW-993 19.8' – 35.5' Sand Pack Interval
23.0' – 33.0' Screened Interval

27.8' – 28.1' Core is highly broken due to composition (mudstone/shale) and sampling procedure. Iron staining along fractures, along bedding planes, and along fractures perpendicular to bedding angles.

28.1' – 28.6' Rubble zone, very intensely fractured, all pieces rounded due to composition and sampling procedure. Iron staining, iron oxide, and manganese oxide observed along fracture faces. Calcite precipitate also observed along fracture faces.

GW-994





B-113

GW-994 37.0' – 54.6' Sand Pack Interval
42.0' – 52.0' Screened Interval

37.6' – 38.1' Fracture oriented 90° to bedding angle. Face has iron oxide weathering

GW-994

B-114



37.6' – 38.1' Fracture oriented 90° to bedding angle. Face has iron oxide weathering

44.9' – 45.4' Bedding breaks and fractures oriented perpendicular to bedding angle. Faces oxidized with iron oxide precipitates.

At 42.8 fracture oriented perpendicular to bedding. Face is oxidized with iron oxide precipitates.

GW-994 37.0' – 54.6' Sand Pack Interval
42.0' – 52.0' Screened Interval

GW-995





GW-995 19.2' – 34.0' Sand Pack Interval
22.1' – 32.1' Screened Interval

Below 25.5' Core is very weathered, broken along bedding planes, iron oxide on bedding planes

B-115

GW-995


B-116



GW-995 19.2' – 34.0' Sand Pack Interval
22.1' – 32.1' Screened Interval

26.5' – 27.0' Trace yellowish/reddish brown iron oxide on fracture surfaces

GW-998





GW-998 24.0' – 40.0' Sand Pack Interval
26.6' – 36.6' Screened Interval

26.8' – 27.2' Vertical fracture with iron and manganese oxide precipitates.


At 27.4' Fracture perpendicular to bedding plane with iron and manganese oxide precipitates.

At 28.0', 28.1', and 28.2' Fractures along bedding planes with iron and manganese oxide precipitates.

B-117

GW-998





B-118

GW-998 24.0’ – 40.0’ Sand Pack Interval
26.6’ – 36.6’ Screened Interval

At 31.6’ Fracture along bedding plane with iron oxide precipitates.

31.7’ -32.2’ Multiple fractures along and perpendicular to bedding plane with iron oxide present on all fractures.

At 32.8’ Break along bedding plane with iron and manganese oxide precipitates.

GW-998





GW-998 24.0' – 40.0' Sand Pack Interval
26.6' – 36.6' Screened Interval

At 36.2' Break along bedding plane with iron oxide precipitate.

38.0' and 38.4' Limestone is iron stained and discolored.

38.3' and 38.8' Fracture vertical along core axis with iron oxide.

B-119

GW-998




B-120

GW-998 24.0' – 40.0' Sand Pack Interval
26.6' – 36.6' Screened Interval

At 39.6' Fracture perpendicular to bedding plane with iron and manganese oxide.

GW-999





GW-999 8.3' – 21.6' Sand Pack Interval
10.3' – 20.3' Screened Interval

19.7' - 19.9' 45 deg. fracture with iron staining.

20.2' – 20.4' 40 deg. fracture with iron staining.

20.6' – 20.75' 30 deg. fracture with iron and manganese oxide.

B-121

This page intentionally left blank.

APPENDIX C


SLUG TEST DATA

This page intentionally left blank.

TABLE C.1.
SUMMARY OF SLUG TESTING RESULTS
PHASE I CHARACTERIZATION ENVIRONMENTAL MANAGEMENT DISPOSAL FACILITY
CENTRAL BEAR CREEK VALLEY SITE (7c)

Well No.	Screen Depth (feet)	Saturated Thickness[2] (feet)	Type of Test	Bouwer-Rice Calculated Hydraulic Conductvity cm/sec
GW-979	26.3 - 36.3	9.7	Bar In	4.17×10^{-4}
			Bar Out	4.96×10^{-4}
			Average	4.56×10^{-4}
GW-981	22.1 - 32.1	9.7	Bar In	6.39×10^{-5}
			Bar Out	4.61×10^{-5}
			Average	5.50×10^{-5}
GW-983	79.2 - 89.2	9.7	Bar In	5.04×10^{-3}
			Bar Out	4.96×10^{-3}
			Average	5.00×10^{-3}
GW-987	16.1 - 26.1	9.7	Bar In	9.52×10^{-5}
			Bar Out	9.75×10^{-5}
			Average	9.64×10^{-5}
GW-989	33.6 - 43.6	9.7	Bar In	1.42×10^{-4}
			Bar Out	6.68×10^{-5}
			Geometric Mean	9.74×10^{-5}
GW-993[1]	23.0 - 33.0	9.7	Bar In	5.88×10^{-4}
			Bar Out	6.98×10^{-4}
			Average	6.43×10^{-4}
GW-995	22.1 - 32.1	9.8	Bar In	1.85×10^{-4}
			Bar Out	1.84×10^{-4}
			Average	1.85×10^{-4}
GW-999	10.3 - 20.3	9.7	Bar In	5.14×10^{-4}
			Bar Out	4.54×10^{-4}
			Average	4.84×10^{-4}

[1] Average borehole radius of screened interval in GW-993 assumed to be 17.4 inches based on volume of sand pack required.
[2] Saturated thickness equals the actual measured slotted interval of 10-foot screen section. Length of filter pack disregarded.



GW-979 FALLING HEAD SLUG TEST

Data Set: F:\Aqtesolve\Oak Ridge\GW-979 Bar In.aqt
Date: 04/02/18 Time: 13:50:32

PROJECT INFORMATION

Company: EAGON & ASSOCIATES, INC.
Client: EMDF Characterization Project
Location: Oak Ridge, TN
Test Well: GW-979
Test Date: 3/6/18

AQUIFER DATA


Saturated Thickness: 9.7 ft
Anisotropy Ratio (Kz/Kr): 0.5

WELL DATA (GW-979)

Initial Displacement: 1.44 ft
Total Well Penetration Depth: 9.7 ft
Casing Radius: 0.0833 ft
Static Water Column Height: 21.24 ft
Screen Length: 9.7 ft
Well Radius: 0.2448 ft

SOLUTION

Aquifer Model: Confined
Solution Method: Bouwer-Rice
K = 0.0004169 cm/sec
y0 = 1.341 ft



GW-979 RISING HEAD SLUG TEST

Data Set: F:\Aqtesolve\Oak Ridge\GW-979 Bar Out.aqt
Date: 04/02/18 Time: 13:54:13

PROJECT INFORMATION

Company: EAGON & ASSOCIATES, INC.
Client: EMDF Characterization Project
Location: Oak Ridge, TN
Test Well: GW-979
Test Date: 3/6/18

AQUIFER DATA


Saturated Thickness: 9.7 ft
Anisotropy Ratio (Kz/Kr): 0.5

WELL DATA (GW-979)

Initial Displacement: 1.552 ft
Total Well Penetration Depth: 9.7 ft
Casing Radius: 0.0833 ft
Static Water Column Height: 21.27 ft
Screen Length: 9.7 ft
Well Radius: 0.2448 ft

SOLUTION

Aquifer Model: Confined
Solution Method: Bouwer-Rice
K = 0.0004963 cm/sec
y0 = 1.485 ft



GW-981 FALLING HEAD SLUG TEST

Data Set: F:\Aqtesolve\Oak Ridge\GW-981 Bar In.aqt
Date: 04/02/18 Time: 13:55:39

PROJECT INFORMATION

Company: EAGON & ASSOCIATES, INC.
Client: EMDF Characterization Project
Location: Oak Ridge, TN
Test Well: GW-981
Test Date: 3/7/18

AQUIFER DATA


Saturated Thickness: 9.7 ft
Anisotropy Ratio (Kz/Kr): 0.5

WELL DATA (GW-981)

Initial Displacement: 1.01 ft
Total Well Penetration Depth: 9.7 ft
Casing Radius: 0.0833 ft
Static Water Column Height: 10.96 ft
Screen Length: 9.7 ft
Well Radius: 0.3125 ft

SOLUTION

Aquifer Model: Confined
Solution Method: Bouwer-Rice
K = 6.392E-5 cm/sec
y0 = 0.8843 ft



GW-981 RISING HEAD SLUG TEST

Data Set: F:\Aqtesolve\Oak Ridge\GW-981 Bar Out.aqt
Date: 04/02/18 Time: 13:56:17

PROJECT INFORMATION

Company: EAGON & ASSOCIATES, INC.
Client: EMDF Characterization Project
Location: Oak Ridge, TN
Test Well: GW-981
Test Date: 3/7/18

AQUIFER DATA


Saturated Thickness: 9.7 ft
Anisotropy Ratio (Kz/Kr): 0.5

WELL DATA (GW-981)

Initial Displacement: 1.196 ft
Total Well Penetration Depth: 9.7 ft
Casing Radius: 0.0833 ft
Static Water Column Height: 11.03 ft
Screen Length: 9.7 ft
Well Radius: 0.3125 ft

SOLUTION

Aquifer Model: Confined
Solution Method: Bouwer-Rice
K = 4.613E-5 cm/sec
y0 = 0.8893 ft



GW-983 FALLING HEAD SLUG TEST

Data Set: F:\Aqtesolve\Oak Ridge\GW-983 Bar In.aqt
Date: 04/02/18 Time: 13:56:48

PROJECT INFORMATION

Company: EAGON & ASSOCIATES, INC.
Client: EMDF Characterization Project
Location: Oak Ridge, TN
Test Well: GW-983
Test Date: 3/6/18

AQUIFER DATA


Saturated Thickness: 9.7 ft
Anisotropy Ratio (Kz/Kr): 0.5

WELL DATA (GW-983)

Initial Displacement: 0.673 ft
Total Well Penetration Depth: 9.7 ft
Casing Radius: 0.0833 ft
Static Water Column Height: 26.14 ft
Screen Length: 9.7 ft
Well Radius: 0.2447 ft

SOLUTION

Aquifer Model: Confined
Solution Method: Bouwer-Rice
K = 0.005039 cm/sec
y0 = 0.6725 ft



GW-983 RISING HEAD SLUG TEST

Data Set: F:\Aqtesolve\Oak Ridge\GW-983 Bar Out.aqt
Date: 04/02/18 Time: 13:57:24

PROJECT INFORMATION

Company: EAGON & ASSOCIATES, INC.
Client: EMDF Characterization Project
Location: Oak Ridge, TN
Test Well: GW-983
Test Date: 3/6/18

AQUIFER DATA

Saturated Thickness: 9.7 ft Anisotropy Ratio (Kz/Kr): 0.5


WELL DATA (GW-983)

Initial Displacement: 1.279 ft Static Water Column Height: 26.16 ft
Total Well Penetration Depth: 9.7 ft Screen Length: 9.7 ft
Casing Radius: 0.0833 ft Well Radius: 0.2447 ft

SOLUTION

Aquifer Model: Confined Solution Method: Bouwer-Rice

K = 0.004961 cm/sec y0 = 1.15 ft



GW-987 FALLING HEAD SLUG TEST

Data Set: F:\Aqtesolve\Oak Ridge\GW-987 Bar In.aqt
Date: 04/02/18 Time: 10:37:23

PROJECT INFORMATION

Company: EAGON & ASSOCIATES, INC.
Client: EMDF Characterization Project
Location: Oak Ridge, TN
Test Well: GW-987
Test Date: 3/6/18

AQUIFER DATA


Saturated Thickness: 9.7 ft
Anisotropy Ratio (Kz/Kr): 0.5

WELL DATA (GW-987)

Initial Displacement: 1.425 ft
Total Well Penetration Depth: 9.7 ft
Casing Radius: 0.0833 ft
Static Water Column Height: 19.45 ft
Screen Length: 9.7 ft
Well Radius: 0.3125 ft

SOLUTION

Aquifer Model: Confined
Solution Method: Bouwer-Rice
K = 9.52E-5 cm/sec
y0 = 1.195 ft



GW-987 RISING HEAD SLUG TEST

Data Set: F:\Aqtesolve\Oak Ridge\GW-987 Bar Out.aqt
Date: 04/02/18 Time: 10:37:25

PROJECT INFORMATION

Company: EAGON & ASSOCIATES, INC.
Client: EMDF Characterization Project
Location: Oak Ridge, TN
Test Well: GW-987
Test Date: 3/7/18

AQUIFER DATA


Saturated Thickness: 9.7 ft
Anisotropy Ratio (Kz/Kr): 0.5

WELL DATA (GW-987)

Initial Displacement: 1.451 ft
Total Well Penetration Depth: 9.7 ft
Casing Radius: 0.0833 ft
Static Water Column Height: 18.84 ft
Screen Length: 9.7 ft
Well Radius: 0.3125 ft

SOLUTION

Aquifer Model: Confined
Solution Method: Bouwer-Rice
K = 9.748E-5 cm/sec
y0 = 1.201 ft



GW-989 FALLING HEAD SLUG TEST

Data Set: F:\Aqtesolve\Oak Ridge\GW-989 Bar In.aqt
Date: 04/02/18 Time: 10:37:28

PROJECT INFORMATION

Company: EAGON & ASSOCIATES, INC.
Client: EMDF Characterization Project
Location: Oak Ridge, TN
Test Well: GW-989
Test Date: 3/7/18

AQUIFER DATA


Saturated Thickness: 9.7 ft
Anisotropy Ratio (Kz/Kr): 0.5

WELL DATA (GW-989)

Initial Displacement: 1.346 ft
Total Well Penetration Depth: 9.7 ft
Casing Radius: 0.0833 ft
Static Water Column Height: 31.59 ft
Screen Length: 9.7 ft
Well Radius: 0.3125 ft

SOLUTION

Aquifer Model: Confined
Solution Method: Bouwer-Rice
K = 0.000142 cm/sec
y0 = 1.364 ft



GW-989 RISING HEAD SLUG TEST

Data Set: F:\Aqtesolve\Oak Ridge\GW-989 Bar Out.aqt
Date: 04/02/18 Time: 10:40:11

PROJECT INFORMATION

Company: EAGON & ASSOCIATES, INC.
Client: EMDF Characterization Project
Location: Oak Ridge, TN
Test Well: GW-989
Test Date: 3/7/18

AQUIFER DATA


Saturated Thickness: 9.7 ft
Anisotropy Ratio (Kz/Kr): 0.5

WELL DATA (GW-989)

Initial Displacement: 1.487 ft
Total Well Penetration Depth: 9.7 ft
Casing Radius: 0.0833 ft
Static Water Column Height: 31.61 ft
Screen Length: 9.7 ft
Well Radius: 0.3125 ft

SOLUTION

Aquifer Model: Confined
Solution Method: Bouwer-Rice
K = 6.684E-5 cm/sec
y0 = 1.305 ft



GW-993 FALLING HEAD SLUG TEST R(W) = 0.725

Data Set: F:\Aqtesolve\Oak Ridge\GW-993 Bar In r(w) = 0.725.aqt
Date: 04/02/18 Time: 13:58:11

PROJECT INFORMATION

Company: EAGON & ASSOCIATES, INC.
Client: EMDF Characterization Project
Location: Oak Ridge, TN
Test Well: GW-993
Test Date: 3/7/18

AQUIFER DATA


Saturated Thickness: 9.7 ft
Anisotropy Ratio (Kz/Kr): 0.5

WELL DATA (GW-993)

Initial Displacement: 0.63 ft
Total Well Penetration Depth: 9.7 ft
Casing Radius: 0.0833 ft
Static Water Column Height: 28.46 ft
Screen Length: 9.7 ft
Well Radius: 0.725 ft

SOLUTION

Aquifer Model: Confined
Solution Method: Bouwer-Rice
K = 0.0005875 cm/sec
y0 = 0.5567 ft



GW-993 RISING HEAD SLUG TEST R(W) = 0.725

Data Set: F:\Aqtesolve\Oak Ridge\GW-993 Bar Out r(w) = 0.725.aqt
Date: 04/02/18 Time: 13:58:47

PROJECT INFORMATION

Company: EAGON & ASSOCIATES, INC.
Client: EMDF Characterization Project
Location: Oak Ridge, TN
Test Well: GW-993
Test Date: 3/7/18

AQUIFER DATA


Saturated Thickness: 9.7 ft
Anisotropy Ratio (Kz/Kr): 0.5

WELL DATA (GW-993)

Initial Displacement: 0.679 ft
Total Well Penetration Depth: 9.7 ft
Casing Radius: 0.0833 ft
Static Water Column Height: 28.51 ft
Screen Length: 9.7 ft
Well Radius: 0.725 ft

SOLUTION

Aquifer Model: Confined
Solution Method: Bouwer-Rice
K = 0.0006977 cm/sec
y0 = 0.6329 ft



GW-995 FALLING HEAD SLUG TEST

Data Set: F:\Aqtesolve\Oak Ridge\GW-995 Bar In.aqt
Date: 04/02/18 Time: 10:40:40

PROJECT INFORMATION

Company: EAGON & ASSOCIATES, INC.
Client: EMDF Characterization Project
Location: Oak Ridge, TN
Test Well: GW-995
Test Date: 3/5/18

AQUIFER DATA


Saturated Thickness: 9.8 ft
Anisotropy Ratio (Kz/Kr): 0.5

WELL DATA (GW-995)

Initial Displacement: 1.443 ft
Total Well Penetration Depth: 9.8 ft
Casing Radius: 0.0833 ft
Static Water Column Height: 24.05 ft
Screen Length: 9.8 ft
Well Radius: 0.3125 ft

SOLUTION

Aquifer Model: Confined
Solution Method: Bouwer-Rice
K = 0.0001854 cm/sec
y0 = 1.295 ft



GW-995 RISING HEAD SLUG TEST

Data Set: F:\Aqtesolve\Oak Ridge\GW-995 Bar Out.aqt
Date: 04/02/18 Time: 10:40:43

PROJECT INFORMATION

Company: EAGON & ASSOCIATES, INC.
Client: EMDF Characterization Project
Location: Oak Ridge, TN
Test Well: GW-995
Test Date: 3/5/18

AQUIFER DATA


Saturated Thickness: 9.8 ft Anisotropy Ratio (Kz/Kr): 0.5

WELL DATA (GW-995)

Initial Displacement: 1.453 ft
Total Well Penetration Depth: 9.8 ft
Casing Radius: 0.0833 ft
Static Water Column Height: 24.07 ft
Screen Length: 9.8 ft
Well Radius: 0.3125 ft

SOLUTION

Aquifer Model: Confined
Solution Method: Bouwer-Rice
K = 0.0001837 cm/sec
y0 = 1.256 ft



GW-999 FALLING HEAD SLUG TEST

Data Set: F:\Aqtesolve\Oak Ridge\GW-999 Bar In.aqt
Date: 04/02/18 Time: 14:00:42

PROJECT INFORMATION

Company: EAGON & ASSOCIATES, INC.
Client: EMDF Characterization Project
Location: Oak Ridge, TN
Test Well: GW-999
Test Date: 3/6/18

AQUIFER DATA


Saturated Thickness: 9.7 ft
Anisotropy Ratio (Kz/Kr): 0.5

WELL DATA (GW-999)

Initial Displacement: 1.305 ft
Total Well Penetration Depth: 9.7 ft
Casing Radius: 0.0833 ft
Static Water Column Height: 18.3 ft
Screen Length: 9.7 ft
Well Radius: 0.3125 ft

SOLUTION

Aquifer Model: Confined
Solution Method: Bouwer-Rice
K = 0.0005143 cm/sec
y0 = 1.27 ft



GW-999 RISING HEAD SLUG TEST

Data Set: F:\Aqtesolve\Oak Ridge\GW-999 Bar Out.aqt
Date: 04/02/18 Time: 14:01:31

PROJECT INFORMATION

Company: EAGON & ASSOCIATES, INC.
Client: EMDF Characterization Project
Location: Oak Ridge, TN
Test Well: GW-999
Test Date: 3/6/18

AQUIFER DATA

Saturated Thickness: 9.7 ft
Anisotropy Ratio (Kz/Kr): 0.5

WELL DATA (GW-999)

Initial Displacement: 1.432 ft
Total Well Penetration Depth: 9.7 ft
Casing Radius: 0.0833 ft
Static Water Column Height: 18.33 ft
Screen Length: 9.7 ft
Well Radius: 0.3125 ft

SOLUTION

Aquifer Model: Confined
Solution Method: Bouwer-Rice
K = 0.0004542 cm/sec
y0 = 1.346 ft

This page intentionally left blank.

APPENDIX D

FLUTe™ TESTS

This page intentionally left blank.

APPENDIX D

FLUTe Tests

This page intentionally left blank.

Results of FLUTe profiling for hole no. GW-978 for *Strata-G Oak Ridge*

Water Table depth	10.75	ft BGS
Hole depth	82.08	ft BGS
liner length	85	ft BGS
casing depth	27	ft BGS
hole diameter	6	inches
liner diameter	0	inches
date of measurement	2/19/2018	

The profile was measured to a depth of 76.845 ft

The flow rate per unit driving pressure was 0.01 **gal/min/ft**

The transmissivity for the remainder of the hole is: 0.020705 cm sq./sec

The average conductivity for the remaining 5.2346 ft of the hole is 1.30E-04 cm/sec

Total borehole transmissivity is 0.161636 cm2/s

Comments:

Contact for questions about data or reduction


carl Keller
Phone: 505-455-1300

Note: the flow rate curve is the liner velocity multiplied by the borehole cross section


A drop in flow rate is usually associated with loss into the hole wall.
The magnitude of the drop in velocity is a direct measure of the loss into the hole wall.
The agreement between the black monotonic fit and the yellow smoothed flow/velocity curve of the first graph is an indication of the data reliability.
The transmissivity curve of the second graph is calculated from the monotonic flow rate curve.


GW-978


Monotonic curve (black over yellow) is corrected for the transient




GW-978


"borehole transmissivity below the depth"
0
0.05
0.1
0.15
0.2
depth (ft. BGS)
0
10
20
30
40
50
60
70
80
90
Transmissivity in cm²/s


Discrete interval T
Transmissivity over defined interval
(cm²/s)
0
0.02
Depth (ft. BGS)
0
10
20
30
40
50
60
70
80
90
interval
~resolution limit
(cm2/s)


Discrete interval Conductivity
(cm/s)
1E-06
1E-05
0.0001
0.001
0.01
depth (ft. BGS)
0
10
20
30
40
50
60
70
80
90
interval conductivity (C)
resolution limit

GW-978



The first graph shows the head profile calculated over the interval of measurement. The assumption is that the head is constant between the "stopping elevations", the depth at which the liner is stopped to allow equilibration below the liner.

The bold red squares indicate that the calculation is unreliable because it depends of the measurement of a very low transmissivity in the measurement interval. That is because the FLUTe transmissivity profiling method does not measure the transmissivity to better than 1% of the transmissvity below the depth of the liner.

The estimated heads for the red square intervals are based on the either the equilibrium heads measured or assumed to lie between the more reliable head in the higher flow zone above and below the low transmissivity interval. It is reasonable to assume that the head in the low T interval with be between the higher flow zones above and below the low T interval.

The first, and deepest, interval is very reliable because the transducer is allowed to equilibrate in that interval totally isolated by the bottom of the borehole and the liner above. It is also a low transmissivity interval because the liner is halted with only a low remaining transmissivity.

The Second graph is the transmissivity distribution from the FLUTe T profile which is used in the head profile.
The Third graph is the flow calculated into and out of the open borehole using the transmissivity of each interval, the head calculated, and the open hole blended head.
The Fourth graph is the a synthetic flow log based on the third graph data. The flow is plotted at the boundaries of the measurement intervals.

GW-978

Reverse head profile Borehole no. GW-978 Oak Ridge Strata G **date:** **2/19/2018**

interval depths (ft)	head in the interval (ft bgs)	blended head	top of interval	bottom of interval	Water table in formation (ft bgs)	interval	mid point of intervals (ft)	flow into/out of hole (liters/hr)	synthetic flow meter rate gal/min at boundaries	low T intervals	boundries of meas. i		range of plot		DTi used in the calculation (cm2/s)	If below not equal to 1.0, DTi was modified	Best estimates for low T intervals
82.08	10.75	10.75	76.845	82.08	10.75	1	80.46	6.03709585	0.0265	0	82.08	82.08	0	100	0.020705418	1	
76.845	10.75	10.75	65	76.845	12.5196905	2	70.9225	3.561968762	0.0421	0	76.845	76.845	0	100	0.036575691	1	13.1617324
76.845	12.51969	10.75	58	65	11.8847998	3	61.5	8.367427113	0.0788	0	65	65	0	100	0.050088902	1	13.1617324
65	12.51969	10.75	47	58	15.0609197	4	52.5	-6.35009474	0.0509	15.06091965	58	58	0	100	0.034994892	4	13.1617324
65	11.8848	10.75	36	47	14.34278	5	41.5	-3.49309741	0.0356	14.34277995	47	47	0	100	0.034026639	3	13.1617324
58	11.8848	10.75	25	36	15.5734649	6	30.5	-8.12329957	0.0000	0	36	36	0	100	0.034174829	1	
58	15.06092	10.75	0	25	#DIV/0!	7	12.5	#DIV/0!	#DIV/0!	#DIV/0!	25	25	0	100	0	1	
47	15.06092	10.75	0	0	#DIV/0!	8	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
47	14.34278	10.75	0	0	#DIV/0!	9	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
36	14.34278	10.75	0	0	#DIV/0!	10	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
36	15.57346	10.75	0	0	#DIV/0!	11	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
25	15.57346	10.75	0	0	#DIV/0!	12	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
25	#DIV/0!	10.75	0	0	#DIV/0!	13	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	14	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	15	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	16	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	17	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	18	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	19	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	20	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	21	0	#DIV/0!	0.0000	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!																
0	#DIV/0!																
0	#DIV/0!		total hole depth		82.08	ft bgs											
0	#DIV/0!		hole diameter		0	in.											
0	#DIV/0!		casing depth		0	ft bgs	**integral of hole flow**										
0	#DIV/0!		casing diam.		0	in.	is 0??	**#DIV/0!**									
0	#DIV/0!																

This page intentionally left blank.

Results of FLUTe profiling for hole no. GW-982 for *Strata-G Oak Ridge*

Water Table depth	52.375	ft BGS
Hole depth	125.3	ft BGS
liner length	130	ft BGS
casing depth	50	ft BGS
hole diameter	6	inches
liner diameter	6.5	inches
date of measurement	2/19/2019	

The profile was measured to a depth of 53.741 ft

The flow rate per unit driving pressure was 0.00217 **gal/min/ft**

The transmissivity for the remainder of the hole is: 0.0045 cm sq./sec

The average conductivity for the remaining 71.559 ft of the hole is 2.06E-06 cm/sec

Total borehole transmissivity is 0.051813 cm2/s

Comments:

Contact for questions about data or reduction


carl Keller	
Phone:	505-455-1300

Note: the flow rate curve is the liner velocity multiplied by the borehole cross section


A drop in flow rate is usually associated with loss into the hole wall.
The magnitude of the drop in velocity is a direct measure of the loss into the hole wall.
The agreement between the black monotonic fit and the yellow smoothed flow/velocity curve of the first graph is an indication of the data reliability.
The transmissivity curve of the second graph is calculated from the monotonic flow rate curve.


GW-982


Monotonic curve (black over yellow) is corrected for the transient



GW-982


"borehole transmissivity below the depth"
0
0.02
0.04
0.06
52
52.5
53
53.5
54
54.5
55
55.5
56
depth (ft. BGS)
Transmissivity in cm²/s


Discrete interval T
Transmissivity over defined interval
(cm²/s)
0
0.02
0.04
0.06
52
52.5
53
53.5
54
54.5
55
55.5
56
Depth (ft. BGS)
interval
~resolution limit
(cm2/s)


Discrete interval Conductivity
(cm/s)
1E-06
1E-05
0.0001
0.001
0.01
52
52.5
53
53.5
54
54.5
55
55.5
56
depth (ft. BGS)
interval conductivity (C)
resolution limit

This page intentionally left blank.

Results of FLUTe profiling for hole no. GW-986 for ***Strata-G Oak Ridge***

Water Table depth	5	ft BGS
Hole depth	59.42	ft BGS
liner length	65	ft BGS
casing depth	20	ft BGS
hole diameter	6	inches
liner diameter	6.5	inches
date of measurement	2/23/2018	

The profile was measured to a depth of 49.173 ft

The flow rate per unit driving pressure was 0.01538 **gal/min/ft**

The transmissivity for the remainder of the hole is: 0.031841 cm sq./sec

The average conductivity for the remaining 10.247 ft of the hole is 1.02E-04 cm/sec

Total borehole transmissivity is 0.098617 cm2/s

Comments:

Contact for questions about data or reduction

carl Keller


Phone: 505-455-1300

Note: the flow rate curve is the liner velocity multiplied by the borehole cross section


A drop in flow rate is usually associated with loss into the hole wall.
The magnitude of the drop in velocity is a direct measure of the loss into the hole wall.
The agreement between the black monotonic fit and the yellow smoothed flow/velocity curve of the first graph is an indication of the data reliability.
The transmissivity curve of the second graph is calculated from the monotonic flow rate curve.


GW-986


Monotonic curve (black over yellow) is corrected for the transient



GW-986



"borehole transmissivity below the depth"
0
0.05
0.1
0.15
0
10
20
30
40
50
60
depth (ft. BGS)
Transmissivity in cm²/s


Discrete interval T
Transmissivity over defined interval
(cm²/s)
0
0.005
0.01
0
10
20
30
40
50
60
Depth (ft. BGS)
interval
~resolution limit
(cm2/s)


Discrete interval Conductivity
(cm/s)
1E-06
1E-05
0.0001
0.001
0.01
0
10
20
30
40
50
60
depth (ft. BGS)
interval conductivity (C)
resolution limit

GW-986

FLUTe formation head profile for GW-986



The first graph shows the head profile calculated over the interval of measurement. The assumption is that the head is constant between the "stopping elevations", the depth at which the liner is stopped to allow equilibration below the liner.

The bold red squares indicate that the calculation is unreliable because it depends of the measurement of a very low transmissivity in the measurement interval. That is because the FLUTe transmissivity profiling method does not measure the transmissivity to better than 1% of the transmissvity below the depth of the liner.

The estimated heads for the red square intervals are based on the either the equilibrium heads measured or assumed to lie between the more reliable head in the higher flow zone above and below the low transmissivity interval. It is reasonable to assume that the head in the low T interval with be between the higher flow zones above and below the low T interval.

The first, and deepest, interval is very reliable because the transducer is allowed to equilibrate in that interval totally isolated by the bottom of the borehole and the liner above. It is also a low transmissivity interval because the liner is halted with only a low remaining transmissivity.

The Second graph is the transmissivity distribution from the FLUTe T profile which is used in the head profile.
The Third graph is the flow calculated into and out of the open borehole using the transmissivity of each interval, the head calculated, and the open hole blended head.
The Fourth graph is the a synthetic flow log based on the third graph data. The flow is plotted at the boundaries of the measurement intervals.

GW-986

Reverse head profile Borehole no. GW-986 O. Ridge date: **2/23/2018**

interval depths (ft)	head in the interval (ft bgs)	blended head	top of interval	bottom of interval	Water table in formation (ft bgs)	interval	mid point of intervals (ft)	flow into/out of hole (liters/hr)	synthetic flow meter rate gal/min at boundaries	low T intervals	boundries of meas. i		range of plot		DTi used in the calculation (cm2/s)	If below not equal to 1.0, DTi was modified	Best estimates for low T intervals
59.42	5	5	49	59.42	5	1	54.295	1.927215	0.0085	0	59.42	59.42	0	100	0.031840557	1	
49	5	5	39	49	6.29331233	2	44	-1.2967647	0.0028	0	49	49	0	100	0.015933604	1	#DIV/0!
49	6.293312	5	35	39	5.70049765	3	37	-0.1215002	0.0022	5.700497648	39	39	0	100	0.007437049	1	#DIV/0!
39	6.293312	5	30	35	5.95886618	4	32.5	-0.6129673	-0.0005	0	35	35	0	100	0.013716775	1	#DIV/0!
39	5.700498	5	19	30	5.51968049	5	24.5	0.10401723	0.0000	0	30	30	0	100	0.029689104	1	#DIV/0!
35	5.700498	5	0	19	#DIV/0!	6	9.5	#DIV/0!	#DIV/0!	#DIV/0!	19	19	0	100	0	1	
35	5.958866	5	0	0	#DIV/0!	7	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
30	5.958866	5	0	0	#DIV/0!	8	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
30	5.51968	5	0	0	#DIV/0!	9	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
19	5.51968	5	0	0	#DIV/0!	10	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
19	5.51968	5	0	0	#DIV/0!	11	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	5	0	0	#DIV/0!	12	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	5	0	0	#DIV/0!	13	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	14	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	15	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	16	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	17	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	18	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	19	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	20	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	21	0	#DIV/0!	0.0000	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!																
0	#DIV/0!																
0	#DIV/0!		total hole depth		59.42	ft bgs											
0	#DIV/0!		hole diameter		0	in.											
0	#DIV/0!		casing depth		0	ft bgs	**integral of hole flow**										
0	#DIV/0!		casing diam.		0	in.	is 0??	**#DIV/0!**									
0	#DIV/0!																

This page intentionally left blank.

GW-988

Results of FLUTe profiling for hole no. GW-988 for ***Strata-G Oak Ridge***

Water Table depth	13.9	ft BGS
Hole depth	79	ft BGS
liner length	85	ft BGS
casing depth	36.5	ft BGS
hole diameter	6	inches
liner diameter	6.5	inches
date of measurement	2/22/2018	

The profile was measured to a depth of 75.365 ft

The flow rate per unit driving pressure was 0.02739 **gal/min/ft**

The transmissivity for the remainder of the hole is: 0.056714 cm sq./sec

The average conductivity for the remaining 3.6346 ft of the hole is 5.12E-04 cm/sec

Total borehole transmissivity is 0.106479 cm2/s

Comments:

Contact for questions about data or reduction


carl Keller	
Phone:	505-455-1300

Note: the flow rate curve is the liner velocity multiplied by the borehole cross section


A drop in flow rate is usually associated with loss into the hole wall.
The magnitude of the drop in velocity is a direct measure of the loss into the hole wall.
The agreement between the black monotonic fit and the yellow smoothed flow/velocity curve of the first graph is an indication of the data reliability.
The transmissivity curve of the second graph is calculated from the monotonic flow rate curve.


GW-988


Monotonic curve (black over yellow) is corrected for the transient



GW-988



"borehole transmissivity below the depth"
0
0.05
0.1
0.15
depth (ft. BGS)
0
10
20
30
40
50
60
70
80
Transmissivity in cm²/s



Discrete interval T
Transmissivity over defined interval
(cm²/s)
0
0.005
0.01
Depth (ft. BGS)
0
10
20
30
40
50
60
70
80
interval
~resolution limit
(cm2/s)



Discrete interval Conductivity
(cm/s)
1E-06
1E-05
0.0001
0.001
0.01
depth (ft. BGS)
0
10
20
30
40
50
60
70
80
interval conductivity (C)
resolution limit


GW-988

FLUTe formation head profile for GW-988









The first graph shows the head profile calculated over the interval of measurement. The assumption is that the head is constant between the "stopping elevations", the depth at which the liner is stopped to allow equilibration below the liner.

The bold red squares indicate that the calculation is unreliable because it depends of the measurement of a very low transmissivity in the measurement interval. That is because the FLUTe transmissivity profiling method does not measure the transmissivity to better than 1% of the transmissvity below the depth of the liner.

The estimated heads for the red square intervals are based on the either the equilibrium heads measured or assumed to lie between the more reliable head in the higher flow zone above and below the low transmissivity interval. It is reasonable to assume that the head in the low T interval with be between the higher flow zones above and below the low T interval.

The first, and deepest, interval is very reliable because the transducer is allowed to equilibrate in that interval totally isolated by the bottom of the borehole and the liner above. It is also a low transmissivity interval because the liner is halted with only a low remaining transmissivity.

The Second graph is the transmissivity distribution from the FLUTe T profile which is used in the head profile.
The Third graph is the flow calculated into and out of the open borehole using the transmissivity of each interval, the head calculated, and the open hole blended head.
The Fourth graph is the a synthetic flow log based on the third graph data. The flow is plotted at the boundaries of the measurement intervals.

GW-988

Reverse head profile Borehole no. GW-988 Oak Ridge Strata G date: **2/22/2018**

interval depths (ft)	head in the interval (ft bgs)	blended head	top of interval	bottom of interval	Water table in formation (ft bgs)	interval	mid point of intervals (ft)	flow into/out of hole (liters/hr)	synthetic flow meter rate gal/min at boundaries	low T intervals	boundries of meas. i	range of	plot		DTi used in the calculation (cm2/s)	If below not equal to 1.0, DTi was modified	Best estimates for low T intervals
79	13.9	13.9	75.36541	79	13.9	1	77.1825	0.099569377	0.0004	0	79	79	0	100	0.056713747	1	
75.36541	13.9	13.9	60	75.36541	13.996706	2	67.68271	-0.10711975	0.0000	13.99670602	75.36541	75.36541	0	100	0.012096122	1	#DIV/0!
75.36541	13.99671	13.9	30	60	13.9141733	3	45	0.007550369	0.0000	0	60	60	0	100	0.037669134	1	#DIV/0!
60	13.99671	13.9	0	30	#DIV/0!	4	15	#DIV/0!	#DIV/0!	#DIV/0!	30	30	0	100	0	1	#DIV/0!
60	13.91417	13.9	0	0	#DIV/0!	5	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	#DIV/0!
30	13.91417	13.9	0	0	#DIV/0!	6	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
30	#DIV/0!	13.9	0	0	#DIV/0!	7	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	13.9	0	0	#DIV/0!	8	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	13.9	0	0	#DIV/0!	9	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	13.9	0	0	#DIV/0!	10	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	13.9	0	0	#DIV/0!	11	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	13.9	0	0	#DIV/0!	12	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	13.9	0	0	#DIV/0!	13	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	14	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	15	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	16	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	17	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	18	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	19	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	20	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	21	0	#DIV/0!	0.0000	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!																
0	#DIV/0!																
0	#DIV/0!		total hole depth		79	ft bgs											
0	#DIV/0!		hole diameter		0	in.											
0	#DIV/0!		casing depth		0	ft bgs	**integral of hole flow**										
0	#DIV/0!		casing diam.		0	in.	is 0??	**#DIV/0!**									
0	#DIV/0!																

This page intentionally left blank.

Results of FLUTe pr+O1:Y40ofiling for hole

no. GW-992 for ***Strata G Oak Ridge***

Water Table depth	1.5	ft BGS
Hole depth	54.833	ft BGS
liner length	60	ft BGS
casing depth	31	ft BGS
hole diameter	6	inches
liner diameter	6.5	inches
date of measurement	2/27/2018	

The profile was measured to a depth of 51.124 ft

The flow rate per unit driving pressure was 0.02047 **gal/min/ft**

The transmissivity for the remainder of the hole is: 0.042393 cm sq./sec

The average conductivity for the remaining 3.7092 ft of the hole is 3.75E-04 cm/sec

Total borehole transmissivity is 0.107572 cm2/s

Comments:

Contact for questions about data or reduction


carl Keller	
Phone:	505-455-1300

Note: the flow rate curve is the liner velocity multiplied by the borehole cross section


A drop in flow rate is usually associated with loss into the hole wall.
The magnitude of the drop in velocity is a direct measure of the loss into the hole wall.
The agreement between the black monotonic fit and the yellow smoothed flow/velocity curve of the first graph is an indication of the data reliability.
The transmissivity curve of the second graph is calculated from the monotonic flow rate curve.


GW-992


Monotonic curve (black over yellow) is corrected for the transient



GW-992



"borehole transmissivity below the depth"
0
0.05
0.1
0.15
depth (ft. BGS)
0
10
20
30
40
50
60
Transmissivity in cm²/s



Discrete interval T
Transmissivity over defined interval
(cm²/s)
0
0.005
0.01
0.015
Depth (ft. BGS)
0
10
20
30
40
50
60
interval
resolution limit
(cm2/s)



Discrete interval Conductivity
(cm/s)
1E-06
1E-05
0.0001
0.001
0.01
depth (ft. BGS)
0
10
20
30
40
50
60
interval conductivity (C)
resolution limit


GW-992

FLUTe formation head profile for GW-992









The first graph shows the head profile calculated over the interval of measurement. The assumption is that the head is constant between the "stopping elevations", the depth at which the liner is stopped to allow equilibration below the liner.

The bold red squares indicate that the calculation is unreliable because it depends of the measurement of a very low transmissivity in the measurement interval. That is because the FLUTe transmissivity profiling method does not measure the transmissivity to better than 1% of the transmissvity below the depth of the liner.

The estimated heads for the red square intervals are based on the either the equilibrium heads measured or assumed to lie between the more reliable head in the higher flow zone above and below the low transmissivity interval. It is reasonable to assume that the head in the low T interval with be between the higher flow zones above and below the low T interval.

The first, and deepest, interval is very reliable because the transducer is allowed to equilibrate in that interval totally isolated by the bottom of the borehole and the liner above. It is also a low transmissivity interval because the liner is halted with only a low remaining transmissivity.

The Second graph is the transmissivity distribution from the FLUTe T profile which is used in the head profile.
The Third graph is the flow calculated into and out of the open borehole using the transmissivity of each interval, the head calculated, and the open hole blended head.
The Fourth graph is the a synthetic flow log based on the third graph data. The flow is plotted at the boundaries of the measurement intervals.

GW-992

Reverse head profile Borehole no. GW-992 RHP profle Oak Ridg **date:** **2/27/2018**

interval depths (ft)	head in the interval (ft bgs)	blended head	top of interval	bottom of interval	Water table in formation (ft bgs)	interval	mid point of intervals (ft)	flow into/out of hole (liters/hr)	synthetic flow meter rate gal/min at boundaries	low T intervals	boundries of meas. i		range of plot		DTi used in the calculation (cm2/s)	If below not equal to 1.0, DTi was modified	Best estimates for low T intervals
54.833	1.6185	1.5	51.123	54.833	1.6185	1	52.978	1.89554973	0.0083	0	54.833	54.833	0	100	0.04239261	1	
51.123	1.6185	1.5	46	51.123	1.6185	2	48.5615	e	0.0083	1.6185	51.123	51.123	0	100	0.00058122	1	#DIV/0!
51.123	1.6185	1.5	37	46	1.99391215	3	41.5	0.1058208	0.0088	0	46	46	0	100	0.03005474	1	#DIV/0!
46	1.6185	1.5	29	37	2.56087528	4	33	-2.0273595	-0.0001	0	37	37	0	100	0.03454306	1	#DIV/0!
46	1.993912	1.5	0	29	#DIV/0!	5	14.5	#DIV/0!	#DIV/0!	#DIV/0!	29	29	0	100	0	1	#DIV/0!
37	1.993912	1.5	0	0	#DIV/0!	6	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
37	2.560875	1.5	0	0	#DIV/0!	7	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
29	2.560875	1.5	0	0	#DIV/0!	8	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
29	#DIV/0!	1.5	0	0	#DIV/0!	9	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	1.5	0	0	#DIV/0!	10	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	1.5	0	0	#DIV/0!	11	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	1.5	0	0	#DIV/0!	12	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	1.5	0	0	#DIV/0!	13	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	14	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	15	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	16	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	17	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	18	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	19	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	20	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	21	0	#DIV/0!	0.0000	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!																
0	#DIV/0!																
0	#DIV/0!		total hole depth		54.833	ft bgs											
0	#DIV/0!		hole diameter		0	in.											
0	#DIV/0!		casing depth		0	ft bgs	**integral of hole flow**										
0	#DIV/0!		casing diam.		0	in.	is 0??	**#DIV/0!**									
0	#DIV/0!																

This page intentionally left blank.

Results of FLUTe profiling for hole no. GW-994 for *Strata-G Oak Ridge*

Water Table depth	7.06	ft BGS
Hole depth	54.75	ft BGS
liner length	60	ft BGS
casing depth	35	ft BGS
hole diameter	6	inches
liner diameter	6.5	inches
date of measurement	2/21/1987	

The profile was measured to a depth of 52.024 ft

The flow rate per unit driving pressure was 0.03347 **gal/min/ft**

The transmissivity for the remainder of the hole is: 0.069317 cm sq./sec

The average conductivity for the remaining 2.7264 ft of the hole is 8.34E-04 cm/sec

Total borehole transmissivity is 0.098448 cm2/s

Comments:

Contact for questions about data or reduction


carl Keller	
Phone:	505-455-1300

Note: the flow rate curve is the liner velocity multiplied by the borehole cross section


A drop in flow rate is usually associated with loss into the hole wall.
The magnitude of the drop in velocity is a direct measure of the loss into the hole wall.
The agreement between the black monotonic fit and the yellow smoothed flow/velocity curve of the first graph is an indication of the data reliability.
The transmissivity curve of the second graph is calculated from the monotonic flow rate curve.


GW-994


Monotonic curve (black over yellow) is corrected for the transient



GW-994



"borehole transmissivity below the depth"
0
0.05
0.1
0.15
0
10
20
30
40
50
60
depth (ft. BGS)
Transmissivity in cm²/s



Discrete interval T
Transmissivity over defined interval (cm²/s)
0
0.02
0
10
20
30
40
50
60
Depth (ft. BGS)
interval
~resolution limit (cm2/s)



Discrete interval Conductivity
(cm/s)
1E-06
1E-05
0.0001
0.001
0.01
0
10
20
30
40
50
60
depth (ft. BGS)
interval conductivity (C)
resolution limit


GW-994

FLUTe formation head profile for GW-994









The first graph shows the head profile calculated over the interval of measurement. The assumption is that the head is constant between the "stopping elevations", the depth at which the liner is stopped to allow equilibration below the liner.

The bold red squares indicate that the calculation is unreliable because it depends of the measurement of a very low transmissivity in the measurement interval. That is because the FLUTe transmissivity profiling method does not measure the transmissivity to better than 1% of the transmissvity below the depth of the liner.

The estimated heads for the red square intervals are based on the either the equilibrium heads measured or assumed to lie between the more reliable head in the higher flow zone above and below the low transmissivity interval. It is reasonable to assume that the head in the low T interval with be between the higher flow zones above and below the low T interval.

The first, and deepest, interval is very reliable because the transducer is allowed to equilibrate in that interval totally isolated by the bottom of the borehole and the liner above. It is also a low transmissivity interval because the liner is halted with only a low remaining transmissivity.

The Second graph is the transmissivity distribution from the FLUTe T profile which is used in the head profile.
The Third graph is the flow calculated into and out of the open borehole using the transmissivity of each interval, the head calculated, and the open hole blended head.
The Fourth graph is the a synthetic flow log based on the third graph data. The flow is plotted at the boundaries of the measurement intervals.

GW-994

Reverse head profile Borehole no. GW-994 Oak Ridge Strata G date: **2/22/2018**

interval depths (ft)	head in the interval (ft bgs)	blended head	top of interval	bottom of interval	Water table in formation (ft bgs)	interval	mid point of intervals (ft)	flow into/out of hole (liters/hr)	synthetic flow meter rate gal/min at boundaries	low T intervals	boundries of meas. i		range of plot		DTi used in the calculation (cm2/s)	If below not equal to 1.0, DTi was modified	Best estimates for low T intervals
54.75	7.06	7.06	52.02362	54.75	7.06	1	53.38681	519.1099214	2.2768	0	54.75	54.75	0	100	0.060535883	1	
52.02362	7.06	7.06	48	52.02362	7.94175274	2	50.01181	148.9073127	2.9299	7.941752744	52.02362	52.02362	0	100	0.017562951	2	#DIV/0!
52.02362	7.941753	7.06	30	48	8.58422717	3	39	244.9294767	4.0042	0	48	48	0	100	0.029130553	1	#DIV/0!
48	7.941753	7.06	0	30	#DIV/0!	4	15	#DIV/0!	#DIV/0!	#DIV/0!	30	30	0	100	0	1	#DIV/0!
48	8.584227	7.06	0	0	#DIV/0!	5	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	#DIV/0!
30	8.584227	7.06	0	0	#DIV/0!	6	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
30	#DIV/0!	7.06	0	0	#DIV/0!	7	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	7.06	0	0	#DIV/0!	8	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	7.06	0	0	#DIV/0!	9	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	7.06	0	0	#DIV/0!	10	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	7.06	0	0	#DIV/0!	11	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	7.06	0	0	#DIV/0!	12	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	7.06	0	0	#DIV/0!	13	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	14	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	15	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	16	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	17	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	18	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	19	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	20	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	21	0	#DIV/0!	0.0000	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!																
0	#DIV/0!																
0	#DIV/0!		total hole depth		54.75	ft bgs											
0	#DIV/0!		hole diameter		6	in.											
0	#DIV/0!		casing depth		0	ft bgs	**integral of hole flow**										
0	#DIV/0!		casing diam.		6	in.	is 0??	**#DIV/0!**									
0	#DIV/0!																

This page intentionally left blank.

Results of FLUTe profiling for hole no. GW-998 for *Strata-G Oak Ridge*

Water Table depth	1.45	ft BGS
Hole depth	45.08	ft BGS
liner length	50	ft BGS
casing depth	20	ft BGS
hole diameter	6	inches
liner diameter	6.5	inches
date of measurement	2/21/2018	

The profile was measured to a depth of 39.922 ft

The flow rate per unit driving pressure was 0.02745 **gal/min/ft**

The transmissivity for the remainder of the hole is: 0.05684 cm sq./sec

The average conductivity for the remaining 5.1581 ft of the hole is 3.62E-04 cm/sec

Total borehole transmissivity is 0.19806 cm2/s

Comments:

large flow zone at 21-24 ft

Contact for questions about data or reduction

carl Keller


Phone: 505-455-1300

Note: the flow rate curve is the liner velocity multiplied by the borehole cross section


A drop in flow rate is usually associated with loss into the hole wall.
The magnitude of the drop in velocity is a direct measure of the loss into the hole wall.
The agreement between the black monotonic fit and the yellow smoothed flow/velocity curve of the first graph is an indication of the data reliability.
The transmissivity curve of the second graph is calculated from the monotonic flow rate curve.


GW-998


Monotonic curve (black over yellow) is corrected for the transient



GW-998



"borehole transmissivity below the depth"
0
0.05
0.1
0.15
0.2
0.25
depth (ft. BGS)
0
5
10
15
20
25
30
35
40
45
Transmissivity in cm²/s


Discrete interval T
Transmissivity over defined interval
(cm²/s)
0
0.02
0.04
Depth (ft. BGS)
0
5
10
15
20
25
30
35
40
45
interval
~resolution limit
(cm2/s)


Discrete interval Conductivity
(cm/s)
1E-06
1E-05
0.0001
0.001
0.01
depth (ft. BGS)
0
5
10
15
20
25
30
35
40
45
interval conductivity (C)
resolution limit

GW-998

FLUTe formation head profile for GW-998



The first graph shows the head profile calculated over the interval of measurement. The assumption is that the head is constant between the "stopping elevations", the depth at which the liner is stopped to allow equilibration below the liner.

The bold red squares indicate that the calculation is unreliable because it depends of the measurement of a very low transmissivity in the measurement interval. That is because the FLUTe transmissivity profiling method does not measure the transmissivity to better than 1% of the transmissvity below the depth of the liner.

The estimated heads for the red square intervals are based on the either the equilibrium heads measured or assumed to lie between the more reliable head in the higher flow zone above and below the low transmissivity interval. It is reasonable to assume that the head in the low T interval with be between the higher flow zones above and below the low T interval.

The first, and deepest, interval is very reliable because the transducer is allowed to equilibrate in that interval totally isolated by the bottom of the borehole and the liner above. It is also a low transmissivity interval because the liner is halted with only a low remaining transmissivity.

The Second graph is the transmissivity distribution from the FLUTe T profile which is used in the head profile.
The Third graph is the flow calculated into and out of the open borehole using the transmissivity of each interval, the head calculated, and the open hole blended head.
The Fourth graph is the a synthetic flow log based on the third graph data. The flow is plotted at the boundaries of the measurement intervals.

GW-998

Reverse head profile Borehole no. GW-998 Oak Ridge Strata G date: **2/21/2018**


interval depths (ft)	head in the interval (ft bgs)	blended head	top of interval	bottom of interval	Water table in formation (ft bgs)	interval	mid point of intervals (ft)	flow into/out of hole (liters/hr)	synthetic flow meter rate gal/min at boundaries	low T intervals	boundries of meas. i		range of	plot	DTi used in the calculation (cm2/s)	If below not equal to 1.0, DTi was modified	Best estimates for low T intervals
45.08	1.45	1.45	40.2	45.08	1.45	1	42.64	-1.74266785	-0.0076	0	45.08	45.08	0	100	0.056839968	1	
40.2	1.45	1.45	37	40.2	1.60586612	2	38.6	-0.71643114	-0.0108	1.605866123	40.2	40.2	0	100	0.015	1.5	#DIV/0!
40.2	1.605866	1.45	32	37	1.35262602	3	34.5	-0.90525555	-0.0148	0	37	37	0	100	0.045320456	1	#DIV/0!
37	1.605866	1.45	20	32	0.81364878	4	26	3.36435454	0.0000	0	32	32	0	100	0.085899113	1	#DIV/0!
37	1.352626	1.45	0	20	#DIV/0!	5	10	#DIV/0!	#DIV/0!	#DIV/0!	20	20	0	100	0	1	#DIV/0!
32	1.352626	1.45	0	0	#DIV/0!	6	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
32	0.813649	1.45	0	0	#DIV/0!	7	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
20	0.813649	1.45	0	0	#DIV/0!	8	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
20	#DIV/0!	1.45	0	0	#DIV/0!	9	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	1.45	0	0	#DIV/0!	10	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	1.45	0	0	#DIV/0!	11	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	1.45	0	0	#DIV/0!	12	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	1.45	0	0	#DIV/0!	13	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	14	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	15	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	16	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	17	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	18	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	19	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	20	0	#DIV/0!	#DIV/0!	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!	0	0	0	#DIV/0!	21	0	#DIV/0!	0.0000	#DIV/0!	0	0	0	100	0	1	
0	#DIV/0!																
0	#DIV/0!																
0	#DIV/0!		total hole depth		45.08	ft bgs											
0	#DIV/0!		hole diameter		0	in.											
0	#DIV/0!		casing depth		0	ft bgs	**integral of hole flow**										
0	#DIV/0!		casing diam.		0	in.	is 0??	**#DIV/0!**									
0	#DIV/0!																


This page intentionally left blank.


APPENDIX E


GROUNDWATER ELEVATION PLOTS


This page intentionally left blank.



GW-978
Elevation (ft amsl)
Precipitation (inches)
960
955
950
945
940
935
930
925
920
915
910
5.0
4.5
4.0
3.5
3.0
2.5
2.0
1.5
1.0
0.5
0.0
2/14/18
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-978
Extrapolated GW-978 (GW-440)
Precipitation (in)



Water Level Comparison
GW-978 WL Elevation (ft amsl)
GW-440 WL Elevation (ft amsl)
960
955
950
945
940
935
930
925
920
915
910
870
865
860
855
850
845
840
835
830
825
820
2/14/18
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-978
GW-440



GW-979
Elevation (ft amsl)
Precipitation (inches)
970
965
960
955
950
945
940
935
930
925
920
5.0
4.5
4.0
3.5
3.0
2.5
2.0
1.5
1.0
0.5
0.0
2/14/18
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-979
Extrapolated GW-979 (GW-440)
Precipitation (in)



Water Level Comparison
GW-979 WL Elevation (ft amsl)
GW-440 WL Elevation (ft amsl)
960
955
950
945
940
935
930
925
920
915
910
875
870
865
860
855
850
845
840
835
830
825
2/14/18
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-979
GW-440



GW-980R
Elevation (ft amsl)
Precipitation (inches)
960
955
950
945
940
935
930
925
920
915
910
5.0
4.5
4.0
3.5
3.0
2.5
2.0
1.5
1.0
0.5
0.0
2/14/18
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-980R
Extrapolated GW-980R (GW-078)
Precipitation (in)



Water Level Comparison
GW-980R WL Elevation (ft amsl)
GW-078 WL Elevation (ft amsl)
960
955
950
945
940
935
930
925
920
915
910
940
935
930
925
920
915
910
905
900
895
890
2/14/18
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-980R
GW-078



GW-981
Elevation (ft amsl)
Precipitation (inches)
970
965
960
955
950
945
940
935
930
925
920
5.00
4.50
4.00
3.50
3.00
2.50
2.00
1.50
1.00
0.50
0.00
2/14/18
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-981
Extrapolated GW-981 (GW-078)
Precipitation (in)



Water Level Comparison
GW-981 WL Elevation (ft amsl)
GW-078 WL Elevation (ft amsl)
960
955
950
945
940
935
930
925
920
915
910
930
925
920
915
910
905
900
895
890
885
880
2/14/18
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-981
GW-078



GW-982
Elevation (ft amsl)
Precipitation (inches)
975
970
965
960
955
950
945
940
935
930
925
5.0
4.5
4.0
3.5
3.0
2.5
2.0
1.5
1.0
0.5
0.0
2/14/18
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-982
Extrapolated GW-982
Precipitation (in)



GW-983
Elevation (ft amsl)
Precipitation (inches)
975
970
965
960
955
950
945
940
935
930
925
5.0
4.5
4.0
3.5
3.0
2.5
2.0
1.5
1.0
0.5
0.0
2/14/18
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-983
Extrapolated GW-983
Precipitation (in)



GW-986
Elevation (ft amsl)
Precipitation (inches)
950
945
940
935
930
925
920
915
910
905
900
5.0
4.5
4.0
3.5
3.0
2.5
2.0
1.5
1.0
0.5
0.0
2/14/18
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-986
Extrapolated GW-986 (GW-437)
Precipitation (in)



Water Level Comparison
GW-986 WL Elevation (ft amsl)
GW-437 WL Elevation (ft amsl)
950
945
940
935
930
925
920
915
910
905
900
910
905
900
895
890
885
880
875
870
865
860
2/14/18
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-986
GW-437



GW-987
Elevation (ft amsl)
Precipitation (inches)
960
955
950
945
940
935
930
925
920
915
910
5.0
4.5
4.0
3.5
3.0
2.5
2.0
1.5
1.0
0.5
0.0
2/14/18
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-987
Extrapolated GW-987 (GW-437)
Precipitation (in)



Water Level Comparison
GW-987 WL Elevation (ft amsl)
GW-437 WL Elevation (ft amsl)
960
955
950
945
940
935
930
925
920
915
910
910
905
900
895
890
885
880
875
870
865
860
2/14/18
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-987
GW-437



GW-988
Elevation (ft amsl)
Precipitation (inches)
960
955
950
945
940
935
930
925
920
915
910
5.0
4.5
4.0
3.5
3.0
2.5
2.0
1.5
1.0
0.5
0.0
2/14/18
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-988
Extrapolated GW-988 (GW-437)
Precipitation (in)



Water Level Comparison
GW-988 WL Elevation (ft amsl)
GW-437 WL Elevation (ft amsl)
960
955
950
945
940
935
930
925
920
915
910
910
905
900
895
890
885
880
875
870
865
860
2/14/18
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-988
GW-437



GW-989
Elevation (ft amsl)
Precipitation (inches)
960
955
950
945
940
935
930
925
920
915
910
5
5
4
4
3
3
2
2
1
1
0
2/14/18
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-989
Extrapolated GW-989 (GW-437)
Precipitation (in)



Water Level Comparison
GW-989 WL Elevation (ft amsl)
GW-437 WL Elevation (ft amsl)
970
965
960
955
950
945
940
935
930
925
920
910
905
900
895
890
885
880
875
870
865
860
2/14/18
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-989
GW-437



GW-992R
Elevation (ft amsl)
Precipitation (inches)
930
925
920
915
910
905
900
895
890
885
880
5.0
4.5
4.0
3.5
3.0
2.5
2.0
1.5
1.0
0.5
0.0
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
Date
GW-992R
Extrapolated GW-992R (GW-078)
Precipitation (in)



Water Level Comparison
GW-992R WL Elevation (ft amsl)
GW-078 WL Elevation (ft amsl)
930
925
920
915
910
905
900
895
890
885
880
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-992R
GW-078



GW-993
Elevation (ft amsl)
Precipitation (Inches)
930
925
920
915
910
905
900
895
890
5.0
4.5
4.0
3.5
3.0
2.5
2.0
1.5
1.0
0.5
0.0
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-993
Extrapolated GW-993 (GW-078)
Precipitation (in)



Water Level Comparison
GW-993 WL Elevation (ft amsl)
GW-078 WL Elevation (ft amsl)
940
935
930
925
920
915
910
905
900
895
890
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-993
GW-078



GW-994
Elevation (ft amsl)
Precipitation (inches)
930
925
920
915
910
905
900
895
890
885
880
5.0
4.5
4.0
3.5
3.0
2.5
2.0
1.5
1.0
0.5
0.0
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-994
Extrapolated GW-994 (GW-078)
Precipitation (in)



Water Level Comparison
GW-994 WL Elevation (ft amsl)
GW-078 WL Elevation (ft amsl)
930
925
920
915
910
905
900
895
890
885
880
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-994
GW-078



GW-995
Elevation (ft amsl)
Precipitation (inches)
930
925
920
915
910
905
900
895
890
885
880
5.0
4.5
4.0
3.5
3.0
2.5
2.0
1.5
1.0
0.5
0.0
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-995
Extrapolated GW-995 (GW-078)
Precipitation (in)


Water Level Comparison
GW-995 WL Elevation (ft amsl)
GW-078 WL Elevation (ft amsl)
940
935
930
925
920
915
910
905
900
895
890
945
940
935
930
925
920
915
910
905
900
895
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-995
GW-078


GW-998
Elevation (ft amsl)
Precipitation (inches)
900
895
890
885
880
875
870
865
860
855
850
5.0
4.5
4.0
3.5
3.0
2.5
2.0
1.5
1.0
0.5
0.0
2/14/18
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-998
Extrapolated GW-998 (GW-438)
Precipitation (in)


Water Level Comparison
GW-998 WL Elevation (ft amsl)
GW-438 WL Elevation (ft amsl)
900
895
890
885
880
875
870
865
860
855
850
890
885
880
875
870
865
860
855
850
845
840
2/14/18
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-998
GW-438


GW-999
Elevation (ft amsl)
Precipitation (inches)
890
885
880
875
870
865
860
855
850
5.0
4.5
4.0
3.5
3.0
2.5
2.0
1.5
1.0
0.5
0.0
2/14/18
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-999
Extrapolated GW-999 (GW-438)
Precipitation (in)


Water Level Comparison
GW-999 WL Elevation (ft amsl)
GW-438 WL Elevation (ft amsl)
900
895
890
885
880
875
870
865
860
855
850
2/14/18
2/19/18
2/24/18
3/1/18
3/6/18
3/11/18
3/16/18
3/21/18
3/26/18
3/31/18
GW-999
GW-438

This page intentionally left blank.

APPENDIX F

GEOTECHNICAL LABORATORY REPORTS

This page intentionally left blank.

Appendix F – Laboratory Test Results

This Page Intentionally Left Blank.

Appendix F.1 – Soil Index Testing

This Page Intentionally Left Blank.

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: ASM:FH18-W00338

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Material Details

Source	Geotechnical Drilling Samples	**Sampled From**	Split Spoon
Description	Native Existing Material	**Location**	Oak Ridge, Tennessee
Specification	USCS	**Sampling Method**	Split Spoon

Sample Details

Sample ID	FH18-W00338-S0	FH18-W00338-S0	FH18-W00338-S0	FH18-W00338-S0	FH18-W00338-S0	FH18-W00338-S0
Field Sample ID	GW978-SS1 [1]	GW978-SS3 [2]	GW978-SS4 [3]	GW978-SS5 [4]	GW978-SS8 [5]	GW978-SS9 [6]
Date Sampled	2/10/2018	2/10/2018	2/10/2018	2/10/2018	2/10/2018	2/10/2018

Other Test Results

Description	Method	Results						Limits
Water Content (%)	ASTM D 2216	21.8	19.3	24.0	21.0	11.5	11.7	
Method		B	B	B	B	B	B	
Group Symbol	ASTM D 2487			CL				
Group Name				Sandy lean clay				
Approximate maximum grain size	ASTM D 4318							
Material retained on 425µm (No. 40) (%)				12.1				
Method of Removal								
Grooving Tool Type				Metal				
Specimen preparation method				Wet				
Drying Method				Air				
Special selection process				Quartered				
Rolling Method for PL				Hand				
As Received Water Content (%)				24.0				
Liquid Limit Device Type				Manual				
Liquid Limit				45				
Plastic Limit				21				
Plasticity Index				24				
Liquid Limit Procedure				Multipoint (A)				
Method	ASTM D 6913			Method B				
Sample Obtained While				Air-Dried				
Group Name				Sandy lean clay				
Group Symbol				CL				
Composite Sieving Used				No				
Dispersion Method				Dispersant by hand				
Prior Testing				Atterberg limits				

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: ASM:FH18-W00338

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Material Details

Source	Geotechnical Drilling Samples	**Sampled From**	Split Spoon
Description	Native Existing Material	**Location**	Oak Ridge, Tennessee
Specification	USCS	**Sampling Method**	Split Spoon

Sample Details

Sample ID	FH18-W00338-S07
Field Sample ID	GW978-SS10
Date Sampled	2/10/2018

Other Test Results

Description	Method	Results	Limits
Water Content (%)	ASTM D 2216	11.1	
Method		B	

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00338-S03

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Sample Details

Sample ID	FH18-W00338-S03
Field Sample ID	GW978-SS4
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/10/2018
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A


Atterberg Limit:

Liquid Limit: 45
Plastic Limit: 21
Plasticity Index: 24

Sample Description:

Brown mottled sandy lean clay (CL)

Particle Size Distribution



COBBLES	GRAVEL		SAND			FINES (65.3%)	
	Coarse	Fine	Coarse	Medium	Fine		
(0.0%)	(0.0%)	(0.5%)	(3.1%)	(8.5%)	(22.6%)	Silt	Clay

Grading: ASTM D 6913

Drying by: Oven
Date Tested: 2/15/2018
Tested By: David Cook

Sieve Size	% Passing	Limits
3/8in	100.0	
No.4	99.5	
No.8	97.2	
No.10	96.4	
No.16	93.6	
No.30	89.7	
No.40	87.9	
No.50	85.9	
No.100	80.3	
No.200	65.3	

D85: 0.2684 **D60:** N/A **D50:** N/A
D30: N/A **D15:** N/A **D10:** N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00338-S03

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Sample Details

Sample ID	FH18-W00338-S03
Field Sample ID	GW978-SS4
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/10/2018
Date Completed	
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A
Dispersion Method	

Other Test Results

Description	Method	Result	Limits
Water Content (%)	ASTM D 2216	24.0	
Method		B	
Date Tested		2/15/2018	
Group Symbol	ASTM D 2487	CL	
Group Name		Sandy lean clay	
Date Tested		2/20/2018	
Approximate maximum grain size	ASTM D 4318		
Material retained on 425µm (No. 40) (%)		12.1	
Method of Removal			
Grooving Tool Type		Metal	
Specimen preparation method		Wet	
Drying Method		Air	
Special selection process		Quartered	
Rolling Method for PL		Hand	
As Received Water Content (%)		24.0	
Liquid Limit Device Type		Manual	
Liquid Limit		45	
Plastic Limit		21	
Plasticity Index		24	
Liquid Limit Procedure		Multipoint (A)	
Date Tested		2/15/2018	
Method	ASTM D 6913	Method B	
Sample Obtained While		Air-Dried	
Group Name		Sandy lean clay	
Group Symbol		CL	
Composite Sieving Used		No	

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00338-S03

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Sample Details

Sample ID	FH18-W00338-S03
Field Sample ID	GW978-SS4
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/10/2018
Date Completed	
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A
Dispersion Method	

Other Test Results

Description	Method	Result	Limits
Dispersion Method		Dispersant by hand	
Prior Testing		Atterberg limits	

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: ASM:FH18-W00381

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Material Details

Source	Geotechnical Drilling Samples	**Sampled From**	Split Spoon
Description	Native Existing Material	**Location**	Oak Ridge, Tennessee
Specification	Unified Soil Classification System	**Sampling Method**	Split Spoon

Sample Details

Sample ID	FH18-W00381-S0	FH18-W00381-S0	FH18-W00381-S0	FH18-W00381-S0	FH18-W00381-S0	FH18-W00381-S0
Field Sample ID	GW980-SS2[1]	GW980-SS3[2]	GW980-SS4[3]	GW980-SS6[4]	GW980-SS8[5]	GW980-SS9[6]
Date Sampled	2/13/2018	2/13/2018	2/13/2018	2/13/2018	2/13/2018	2/13/2018

Particle Size Distribution

Method: ASTM D 422

Description: Analysis of Particle Size Distribution in Soils. Sieving for Particles >75µm, Hydrometer

Drying by: Oven

Washed: Sample Washed

Sieve Size	% Passing	Limits
1½in (37.5mm)	100	
1in (25.0mm)	91	
½in (12.5mm)	83	
3/8in (9.5mm)	74	
No.4 (4.75mm)	55	
No.10 (2.0mm)	40	
No.40 (425µm)	31	
No.100	27	
No.200 (75µm)	23	

Other Test Results

Description	Method	Results						Limits
Water Content (%)	ASTM D 2216	13.8	15.1	15.0	12.6	14.5	10.2	
Method		B	B	B	B	B	B	
Dispersion device	ASTM D 422	Dispersion Cup and Mixer						
Dispersion time (min)		1						
Shape								
Hardness								
Approximate maximum grain size	ASTM D 4318							
Material retained on 425µm (No. 40) (%)								
Method of Removal								
Grooving Tool Type			Plastic					
Specimen preparation method			Wet					
Drying Method			Air					
Special selection process			Quartering					
Rolling Method for PL			Hand					
As Received Water Content (%)			15.1					
Liquid Limit Device Type			Manual					
Liquid Limit			N/A					
Plastic Limit			NP					
Plasticity Index			NP					
Liquid Limit Procedure			Multipoint (A)					

Comments

NP = Non Plastic

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: ASM:FH18-W00381

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

AASHTO ACCREDITATION PROGRAM

Reviewed By: Timothy A. Moore, Jr.

Material Details

Source	Geotechnical Drilling Samples	**Sampled From**	Split Spoon
Description	Native Existing Material	**Location**	Oak Ridge, Tennessee
Specification	USCS	**Sampling Method**	Split Spoon

Sample Details

Sample ID	FH18-W00381-S07	FH18-W00381-S08	FH18-W00381-S09
Field Sample ID	GW980-SS10	GW980-SS12	GW980-SS13
Date Sampled	2/13/2018	2/13/2018	2/13/2018

Other Test Results

Description	Method	Results			Limits
Water Content (%)	ASTM D 2216	4.3	11.7	12.3	
Method		B	B	B	

Comments

NP = Non Plastic

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00381-S01

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.


Sample Details

Sample ID	FH18-W00381-S01
Field Sample ID	GW980-SS2
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/13/2018
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	Unified Soil Classification System
Sampling Method	Split Spoon
Contractor	N/A

Sample Description:

Brown silty sand with gravel (SM)

Particle Size Distribution



COBBLES	GRAVEL		SAND			FINES	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
(0.0%)	(12.8%)	(32.2%)	(15.0%)	(9.0%)	(8.0%)	(17.6%)	(5.4%)

Grading: ASTM D 422

Drying by: Oven
Date Tested: 2/28/2018
Tested By: Sheila Bowers

Sieve Size	% Passing	Limits
1½in	100	
1in	91	
½in	83	
3/8in	74	
No.4	55	
No.10	40	
No.40	31	
No.100	27	
No.200	23	
28.9 µm	13.4	
19.1 µm	10.7	
11.6 µm	8.1	
8.3 µm	7.3	
6.0 µm	5.9	
3.0 µm	4.5	
1.3 µm	2.7	

D85: 14.8651 **D60:** 5.7005 **D50:** 3.5602
D30: 0.3276 **D15:** 0.0339 **D10:** 0.0167
Cu: 341.34 **Cc:** 1.13

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00381-S01

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Sample Details

Sample ID	FH18-W00381-S01
Field Sample ID	GW980-SS2
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/13/2018
Date Completed	
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	Unified Soil Classification System
Sampling Method	Split Spoon
Contractor	N/A
Dispersion Method	

Other Test Results

Description	Method	Result	Limits
Water Content (%)	ASTM D 2216	13.8	
Method		B	
Date Tested		2/26/2018	
Dispersion device	ASTM D 422	Dispersion Cup and Mixer	
Dispersion time (min)		1	
Shape			
Hardness			

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: ASM:FH18-W00342

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

AASHTO ACCREDITATION PROGRAM

Reviewed By: Timothy A. Moore, Jr.

Material Details

Source	Geotechnical Drilling Samples	**Sampled From**	Split Spoon
Description	Native Existing Material	**Location**	Oak Ridge, Tennessee
Specification	USCS	**Sampling Method**	Split Spoon

Sample Details

Sample ID	FH18-W00342-S0	FH18-W00342-S0	FH18-W00342-S0	FH18-W00342-S0	FH18-W00342-S0	FH18-W00342-S0
Field Sample ID	GW982-SS2[1]	GW982-SS3[2]	GW982-SS4[3]	GW982-SS5[4]	GW982-SS8[5]	GW982-SS10[6]
Date Sampled	2/7/2018	2/7/2018	2/7/2018	2/7/2018	2/7/2018	2/7/2018

Other Test Results

Description	Method	Results						Limits
Water Content (%)	ASTM D 2216	11.0	13.1	12.5	12.3	13.9	10.8	
Method		B	B	B	B	B	B	
Group Symbol	ASTM D 2487				CL			
Group Name					Sandy lean clay			
Approximate maximum grain size	ASTM D 4318							
Material retained on 425µm (No. 40) (%)					28.3			
Method of Removal								
Grooving Tool Type					Metal			
Specimen preparation method					Wet			
Drying Method					Air			
Special selection process					Quartered			
Rolling Method for PL					Hand			
As Received Water Content (%)					12.3			
Liquid Limit Device Type					Manual			
Liquid Limit					33			
Plastic Limit					23			
Plasticity Index					10			
Liquid Limit Procedure					Multipoint (A)			
Method	ASTM D 6913				Method B	Method B		
Sample Obtained While					Air-Dried	Air-Dried		
Group Name					Sandy lean clay	N/A		
Group Symbol					CL	N/A		
Composite Sieving Used					No	No		
Dispersion Method					Dispersant by hand	Dispersant by hand		
Prior Testing					Atterberg limits	Atterberg limits		

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: ASM:FH18-W00342

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

AASHTO ACCREDITATION PROGRAM

Reviewed By: Timothy A. Moore, Jr.

Material Details

Source	Geotechnical Drilling Samples	**Sampled From**	Split Spoon
Description	Native Existing Material	**Location**	Oak Ridge, Tennessee
Specification	USCS	**Sampling Method**	Split Spoon

Sample Details

Sample ID	FH18-W00342-S07	FH18-W00342-S08	FH18-W00342-S09	FH18-W00342-S10	FH18-W00342-S11
Field Sample ID	GW982-SS13	GW982-SS16	GW982-SS18	GW982-SS21	GW982-SS23
Date Sampled	2/7/2018	2/8/2018	2/8/2018	2/8/2018	2/8/2018

Other Test Results

Description	Method	Results					Limits
Water Content (%)	ASTM D 2216	11.9	4.7	8.9	7.0	5.5	
Method		B	B	B	B	B	
Group Symbol	ASTM D 2487				SC		
Group Name					Clayey sand		
Approximate maximum grain size	ASTM D 4318						
Material retained on 425µm (No. 40) (%)					54.5		
Method of Removal							
Grooving Tool Type					Metal		
Specimen preparation method					Wet		
Drying Method					Air		
Special selection process					Quartered		
Rolling Method for PL					Hand		
As Received Water Content (%)					7.0		
Liquid Limit Device Type					Manual		
Liquid Limit					28		
Plastic Limit					19		
Plasticity Index					9		
Liquid Limit Procedure					Multipoint (A)		
Method	ASTM D 6913				Method B		
Sample Obtained While					Air-Dried		
Group Name					Clayey sand		
Group Symbol					SC		
Composite Sieving Used					No		
Dispersion Method					Dispersant by hand		
Prior Testing					Atterberg limits		

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00342-S04

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Sample Details

Sample ID	FH18-W00342-S04
Field Sample ID	GW982-SS5
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/7/2018
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A


Atterberg Limit:

Liquid Limit: 33
Plastic Limit: 23
Plasticity Index: 10

Sample Description:

Brown sandy lean clay (CL)

Particle Size Distribution



COBBLES	GRAVEL		SAND			FINES (50.8%)	
	Coarse	Fine	Coarse	Medium	Fine		
(0.0%)	(0.0%)	(2.2%)	(7.8%)	(18.3%)	(20.9%)	Silt	Clay

Grading: ASTM D 6913

Drying by: Oven
Date Tested: 2/15/2018
Tested By: David Cook

Sieve Size	% Passing	Limits
3/8in	100.0	
No.4	97.8	
No.8	91.0	
No.10	90.0	
No.16	83.3	
No.30	75.0	
No.40	71.7	
No.50	68.4	
No.100	61.1	
No.200	50.8	

D85: 1.3490 **D60:** 0.1393 **D50:** N/A
D30: N/A **D15:** N/A **D10:** N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00342-S04

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Sample Details

Sample ID	FH18-W00342-S04
Field Sample ID	GW982-SS5
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/7/2018
Date Completed	
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A
Dispersion Method	

Other Test Results

Description	Method	Result	Limits
Water Content (%)	ASTM D 2216	12.3	
Method		B	
Date Tested		2/15/2018	
Group Symbol	ASTM D 2487	CL	
Group Name		Sandy lean clay	
Date Tested		2/20/2018	
Approximate maximum grain size	ASTM D 4318		
Material retained on 425µm (No. 40) (%)		28.3	
Method of Removal			
Grooving Tool Type		Metal	
Specimen preparation method		Wet	
Drying Method		Air	
Special selection process		Quartered	
Rolling Method for PL		Hand	
As Received Water Content (%)		12.3	
Liquid Limit Device Type		Manual	
Liquid Limit		33	
Plastic Limit		23	
Plasticity Index		10	
Liquid Limit Procedure		Multipoint (A)	
Date Tested		2/15/2018	
Method	ASTM D 6913	Method B	
Sample Obtained While		Air-Dried	
Group Name		Sandy lean clay	
Group Symbol		CL	
Composite Sieving Used		No	

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00342-S04

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Sample Details

Sample ID	FH18-W00342-S04
Field Sample ID	GW982-SS5
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/7/2018
Date Completed	
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A
Dispersion Method	

Other Test Results

Description	Method	Result	Limits
Dispersion Method		Dispersant by hand	
Prior Testing		Atterberg limits	

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00342-S05

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.


Sample Details

Sample ID	FH18-W00342-S05
Field Sample ID	GW982-SS8
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/7/2018
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A

Sample Description:

Dark brown clayey sand with unweathered shale

Particle Size Distribution



COBBLES	GRAVEL		SAND			FINES (29.3%)	
	Coarse	Fine	Coarse	Medium	Fine		
(0.0%)	(0.0%)	(4.8%)	(4.8%)	(9.4%)	(51.7%)	Silt	Clay

Grading: ASTM D 6913

Drying by: Oven
Date Tested: 2/15/2018
Tested By: David Cook

Sieve Size	% Passing	Limits
½in	100.0	
3/8in	98.6	
No.4	95.2	
No.8	91.2	
No.10	90.4	
No.16	87.5	
No.30	83.2	
No.40	81.0	
No.50	77.1	
No.100	44.4	
No.200	29.3	

D85: 0.7964 **D60:** 0.2088 **D50:** 0.1689
D30: 0.0774 **D15:** N/A **D10:** N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00342-S05

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Sample Details

Sample ID	FH18-W00342-S05
Field Sample ID	GW982-SS8
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/7/2018
Date Completed	
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A
Dispersion Method	

Other Test Results

Description	Method	Result	Limits
Water Content (%)	ASTM D 2216	13.9	
Method		B	
Date Tested		2/15/2018	
Method	ASTM D 6913	Method B	
Sample Obtained While		Air-Dried	
Group Name		N/A	
Group Symbol		N/A	
Composite Sieving Used		No	
Dispersion Method		Dispersant by hand	
Prior Testing		Atterberg limits	

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00342-S10

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Sample Details

Sample ID	FH18-W00342-S10
Field Sample ID	GW982-SS21
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/8/2018
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A


Atterberg Limit:

Liquid Limit: 28
Plastic Limit: 19
Plasticity Index: 9

Sample Description:

Brown clayey sand (SC)

Particle Size Distribution



COBBLES	GRAVEL		SAND			FINES (28.5%)	
(0.0%)	Coarse (0.0%)	Fine (14.7%)	Coarse (15.3%)	Medium (24.5%)	Fine (17.0%)	Silt	Clay

Grading: ASTM D 6913

Drying by: Oven
Date Tested: 2/15/2018
Tested By: David Cook

Sieve Size	% Passing	Limits
¾in	100.0	
½in	98.6	
3/8in	96.2	
No.4	85.3	
No.8	71.6	
No.10	70.0	
No.16	60.4	
No.30	49.8	
No.40	45.5	
No.50	41.5	
No.100	34.5	
No.200	28.5	

D85: 4.6778 **D60:** 1.1503 **D50:** 0.6077
D30: 0.0892 **D15:** N/A **D10:** N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00342-S10

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Sample Details

Sample ID	FH18-W00342-S10
Field Sample ID	GW982-SS21
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/8/2018
Date Completed	
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A
Dispersion Method	

Other Test Results

Description	Method	Result	Limits
Water Content (%)	ASTM D 2216	7.0	
Method		B	
Date Tested		2/15/2018	
Group Symbol	ASTM D 2487	SC	
Group Name		Clayey sand	
Date Tested		2/20/2018	
Approximate maximum grain size	ASTM D 4318		
Material retained on 425µm (No. 40) (%)		54.5	
Method of Removal			
Grooving Tool Type		Metal	
Specimen preparation method		Wet	
Drying Method		Air	
Special selection process		Quartered	
Rolling Method for PL		Hand	
As Received Water Content (%)		7.0	
Liquid Limit Device Type		Manual	
Liquid Limit		28	
Plastic Limit		19	
Plasticity Index		9	
Liquid Limit Procedure		Multipoint (A)	
Date Tested		2/15/2018	
Method	ASTM D 6913	Method B	
Sample Obtained While		Air-Dried	
Group Name		Clayey sand	
Group Symbol		SC	
Composite Sieving Used		No	

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00342-S10

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Sample Details

Sample ID	FH18-W00342-S10
Field Sample ID	GW982-SS21
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/8/2018
Date Completed	
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A
Dispersion Method	

Other Test Results

Description	Method	Result	Limits
Dispersion Method		Dispersant by hand	
Prior Testing		Atterberg limits	

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: ASM:FH18-W00388

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

AASHTO ACCREDITATION PROGRAM

Reviewed By: Timothy A. Moore, Jr.

Material Details

Source	Geotechnical Drilling Samples	**Sampled From**	Split Spoon
Description	Native Existing Material	**Location**	Oak Ridge, Tennessee
Specification	USCS	**Sampling Method**	Split Spoon

Sample Details

Sample ID	FH18-W00388-S0	FH18-W00388-S0	FH18-W00388-S0	FH18-W00388-S0	FH18-W00388-S0	FH18-W00388-S0
Field Sample ID	GW986-SS2[1]	GW986-SS3[2]	GW986-SS4[3]	GW986-SS6[4]	GW986-SS7[5]	GW986-SS9[6]
Date Sampled	2/15/2018	2/15/2018	2/15/2018	2/15/2018	2/15/2018	2/15/2018

Other Test Results

Description	Method	Results						Limits
Water Content (%)	ASTM D 2216	20.4	21.1	14.6	8.4	8.7	4.3	
Method		B	B	B	B	B	B	
Approximate maximum grain size	ASTM D 4318							
Material retained on 425µm (No. 40) (%)								
Method of Removal								
Grooving Tool Type		Metal						
Specimen preparation method		Wet						
Drying Method		Air						
Special selection process		Quartering						
Rolling Method for PL		Hand						
As Received Water Content (%)		20.4						
Liquid Limit Device Type		Manual						
Liquid Limit		37						
Plastic Limit		18						
Plasticity Index		19						
Liquid Limit Procedure		Multipoint (A)						
Method	ASTM D 6913			Method B				
Sample Obtained While				Air-Dried				
Group Name				Clayey sand				
Group Symbol				SC				
Composite Sieving Used				No				
Dispersion Method				Dispersant by hand				
Prior Testing				Moisture				

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00388-S03

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.


Sample Details

Sample ID	FH18-W00388-S03
Field Sample ID	GW986-SS4
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/15/2018
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A

Sample Description:

Brown clayey sand (SC)

Particle Size Distribution



COBBLES	GRAVEL		SAND			FINES (39.4%)	
	Coarse	Fine	Coarse	Medium	Fine		
(0.0%)	(0.0%)	(7.8%)	(12.4%)	(20.8%)	(19.6%)	Silt	Clay

Grading: ASTM D 6913

Drying by: Oven
Date Tested: 3/2/2018
Tested By: David Cook

Sieve Size	% Passing	Limits
½in	100.0	
3/8in	99.3	
No.4	92.2	
No.8	81.5	
No.10	79.8	
No.16	72.0	
No.30	62.7	
No.40	59.0	
No.50	55.4	
No.100	47.9	
No.200	39.4	

D85: 2.9667 **D60:** 0.4665 **D50:** 0.1821
D30: N/A **D15:** N/A **D10:** N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00388-S03

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Sample Details

Sample ID	FH18-W00388-S03
Field Sample ID	GW986-SS4
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/15/2018
Date Completed	
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A
Dispersion Method	

Other Test Results

Description	Method	Result	Limits
Water Content (%)	ASTM D 2216	14.6	
Method		B	
Date Tested		2/26/2018	
Method	ASTM D 6913	Method B	
Sample Obtained While		Air-Dried	
Group Name		Clayey sand	
Group Symbol		SC	
Composite Sieving Used		No	
Dispersion Method		Dispersant by hand	
Prior Testing		Moisture	

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: ASM:FH18-W00343

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Material Details

Source	Geotechnical Drilling Samples	**Sampled From**	Split Spoon
Description	Native Existing Material	**Location**	Oak Ridge, Tennessee
Specification	USCS	**Sampling Method**	Split Spoon

Sample Details

Sample ID	FH18-W00343-S0	FH18-W00343-S0	FH18-W00343-S0	FH18-W00343-S0	FH18-W00343-S0	FH18-W00343-S0
Field Sample ID	GW988-SS2[1]	GW988-SS3[2]	GW988-SS4[3]	GW988-SS6[4]	GW988-SS8[5]	GW988-SS11[6]
Date Sampled	2/7/2018	2/7/2018	2/7/2018	2/7/2018	2/7/2018	2/7/2018

Other Test Results

Description	Method	Results						Limits
Water Content (%)	ASTM D 2216	34.6	25.1	33.6	29.8	26.2	21.5	
Method		B	B	B	B	B	B	
Group Symbol	ASTM D 2487			ML				
Group Name				Sandy silt				
Approximate maximum grain size	ASTM D 4318							
Material retained on 425µm (No. 40) (%)				24.3				
Method of Removal								
Grooving Tool Type				Metal				
Specimen preparation method				Wet				
Drying Method				Air				
Special selection process				Quartered				
Rolling Method for PL				Hand				
As Received Water Content (%)				33.6				
Liquid Limit Device Type				Manual				
Liquid Limit				41				
Plastic Limit				27				
Plasticity Index				14				
Liquid Limit Procedure				Multipoint (A)				
Method	ASTM D 6913			Method B				
Sample Obtained While				Air-Dried				
Group Name				Sandy silt				
Group Symbol				ML				
Composite Sieving Used				No				
Dispersion Method				Dispersant by hand				
Prior Testing				Atterberg limits				

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: ASM:FH18-W00343

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

AASHTO ACCREDITATION PROGRAM

Reviewed By: Timothy A. Moore, Jr.

Material Details

Source	Geotechnical Drilling Samples	**Sampled From**	Split Spoon
Description	Native Existing Material	**Location**	Oak Ridge, Tennessee
Specification	USCS	**Sampling Method**	Split Spoon

Sample Details

Sample ID	FH18-W00343-S0	FH18-W00343-S0	FH18-W00343-S0
Field Sample ID	GW988-SS13 7	GW988-SS16 8	GW988-SS18 9
Date Sampled	2/7/2018	2/7/2018	2/7/2018

Other Test Results

Description	Method	Results			Limits
Water Content (%)	ASTM D 2216	16.0	9.9	9.9	
Method		B	B	B	
Group Symbol	ASTM D 2487		SC		
Group Name			Clayey sand		
Approximate maximum grain size	ASTM D 4318				
Material retained on 425µm (No. 40) (%)			48.6		
Method of Removal					
Grooving Tool Type			Metal		
Specimen preparation method			Wet		
Drying Method			Air		
Special selection process			Quartered		
Rolling Method for PL			Hand		
As Received Water Content (%)			9.9		
Liquid Limit Device Type			Manual		
Liquid Limit			32		
Plastic Limit			19		
Plasticity Index			13		
Liquid Limit Procedure			Multipoint (A)		
Method	ASTM D 6913		Method B		
Sample Obtained While			Air-Dried		
Group Name			Clayey sand		
Group Symbol			SC		
Composite Sieving Used			No		
Dispersion Method			Dispersant by hand		
Prior Testing			Atterberg limits		

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00343-S03

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Sample Details

Sample ID	FH18-W00343-S03
Field Sample ID	GW988-SS4
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/7/2018
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A


Atterberg Limit:

Liquid Limit: 41
Plastic Limit: 27
Plasticity Index: 14

Sample Description:

Brown mottled sandy silt (ML)

Particle Size Distribution



COBBLES	GRAVEL		SAND			FINES (57.4%)	
	Coarse	Fine	Coarse	Medium	Fine		
(0.0%)	(0.0%)	(0.6%)	(5.2%)	(18.5%)	(18.3%)	Silt	Clay

Grading: ASTM D 6913

Drying by: Oven
Date Tested: 2/16/2018
Tested By: David Cook

Sieve Size	% Passing	Limits
3/8in	100.0	
No.4	99.4	
No.8	95.4	
No.10	94.2	
No.16	88.4	
No.30	79.8	
No.40	75.7	
No.50	71.8	
No.100	64.5	
No.200	57.4	

D85: 0.9031 **D60:** 0.0967 **D50:** N/A
D30: N/A **D15:** N/A **D10:** N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00343-S03

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Sample Details

Sample ID	FH18-W00343-S03
Field Sample ID	GW988-SS4
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/7/2018
Date Completed	
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A
Dispersion Method	

Other Test Results

Description	Method	Result	Limits
Water Content (%)	ASTM D 2216	33.6	
Method		B	
Date Tested		2/16/2018	
Group Symbol	ASTM D 2487	ML	
Group Name		Sandy silt	
Date Tested		2/20/2018	
Approximate maximum grain size	ASTM D 4318		
Material retained on 425µm (No. 40) (%)		24.3	
Method of Removal			
Grooving Tool Type		Metal	
Specimen preparation method		Wet	
Drying Method		Air	
Special selection process		Quartered	
Rolling Method for PL		Hand	
As Received Water Content (%)		33.6	
Liquid Limit Device Type		Manual	
Liquid Limit		41	
Plastic Limit		27	
Plasticity Index		14	
Liquid Limit Procedure		Multipoint (A)	
Date Tested		2/16/2018	
Method	ASTM D 6913	Method B	
Sample Obtained While		Air-Dried	
Group Name		Sandy silt	
Group Symbol		ML	
Composite Sieving Used		No	

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00343-S03

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Sample Details

Sample ID	FH18-W00343-S03
Field Sample ID	GW988-SS4
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/7/2018
Date Completed	
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A
Dispersion Method	

Other Test Results

Description	Method	Result	Limits
Dispersion Method		Dispersant by hand	
Prior Testing		Atterberg limits	

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00343-S08

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Sample Details

Sample ID	FH18-W00343-S08
Field Sample ID	GW988-SS16
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/7/2018
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A


Atterberg Limit:

Liquid Limit: 32
Plastic Limit: 19
Plasticity Index: 13

Sample Description:

Gray clayey sand (SC)

Particle Size Distribution



COBBLES	GRAVEL		SAND			FINES (29.8%)	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
(0.0%)	(0.0%)	(3.3%)	(12.3%)	(33.0%)	(21.6%)		

Grading: ASTM D 6913

Drying by: Oven
Date Tested: 2/16/2018
Tested By: David Cook

Sieve Size	% Passing	Limits
3/8in	100.0	
No.4	96.7	
No.8	86.6	
No.10	84.4	
No.16	72.1	
No.30	57.1	
No.40	51.4	
No.50	46.2	
No.100	37.3	
No.200	29.8	

D85: 2.0923 **D60:** 0.6838 **D50:** 0.3870
D30: 0.0764 **D15:** N/A **D10:** N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00343-S08

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Sample Details

Sample ID	FH18-W00343-S08
Field Sample ID	GW988-SS16
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/7/2018
Date Completed	
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A
Dispersion Method	

Other Test Results

Description	Method	Result	Limits
Water Content (%)	ASTM D 2216	9.9	
Method		B	
Date Tested		2/16/2018	
Group Symbol	ASTM D 2487	SC	
Group Name		Clayey sand	
Date Tested		2/20/2018	
Approximate maximum grain size	ASTM D 4318		
Material retained on 425µm (No. 40) (%)		48.6	
Method of Removal			
Grooving Tool Type		Metal	
Specimen preparation method		Wet	
Drying Method		Air	
Special selection process		Quartered	
Rolling Method for PL		Hand	
As Received Water Content (%)		9.9	
Liquid Limit Device Type		Manual	
Liquid Limit		32	
Plastic Limit		19	
Plasticity Index		13	
Liquid Limit Procedure		Multipoint (A)	
Date Tested		2/16/2018	
Method	ASTM D 6913	Method B	
Sample Obtained While		Air-Dried	
Group Name		Clayey sand	
Group Symbol		SC	
Composite Sieving Used		No	

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00343-S08

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Sample Details

Sample ID	FH18-W00343-S08
Field Sample ID	GW988-SS16
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/7/2018
Date Completed	
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A
Dispersion Method	

Other Test Results

Description	Method	Result	Limits
Dispersion Method		Dispersant by hand	
Prior Testing		Atterberg limits	

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: ASM:FH18-W00402

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Material Details

Source	Geotechnical Drilling Samples	**Sampled From**	Split Spoon
Description	Native Existing Material	**Location**	Oak Ridge, Tennessee
Specification	USCS	**Sampling Method**	Split Spoon

Sample Details

Sample ID	FH18-W00402-S0	FH18-W00402-S0	FH18-W00402-S0	FH18-W00402-S0	FH18-W00402-S0	FH18-W00402-S0
Field Sample ID	GW992-SS1[1]	GW992-SS2[2]	GW992-SS4[3]	GW992-SS5[4]	GW992-SS7[5]	GW992-SS8[6]
Date Sampled	2/16/2018	2/16/2018	2/16/2018	2/16/2018	2/16/2018	2/16/2018

Other Test Results

Description	Method	Results						Limits
Water Content (%)	ASTM D 2216	29.3	23.9	37.1	13.4	21.3	16.2	
Method		B	B	B	B	B	B	
Approximate maximum grain size	ASTM D 4318							
Material retained on 425µm (No. 40) (%)								
Method of Removal								
Grooving Tool Type		Metal						
Specimen preparation method		Wet						
Drying Method		Air						
Special selection process		Quartering						
Rolling Method for PL		Hand						
As Received Water Content (%)		29.3						
Liquid Limit Device Type		Manual						
Liquid Limit		38						
Plastic Limit		20						
Plasticity Index		18						
Liquid Limit Procedure		Multipoint (A)						
Dispersion device	ASTM D 422		Dispersion Cup and Mixer					
Dispersion time (min)			1					
Shape								
Hardness								

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: ASM:FH18-W00402

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Material Details

Source	Geotechnical Drilling Samples	**Sampled From**	Split Spoon
Description	Native Existing Material	**Location**	Oak Ridge, Tennessee
Specification	Unified Soil Classification System	**Sampling Method**	Split Spoon

Sample Details

Sample ID	FH18-W00402-S07	FH18-W00402-S08	FH18-W00402-S09
Field Sample ID	GW992-SS10	GW992-SS12	GW992-SS13
Date Sampled	2/16/2018	2/16/2018	2/16/2018

Particle Size Distribution

Method:
ASTM D 422

Description:
Analysis of Particle Size Distribution in Soils. Sieving for Particles >75µm, Hydrometer

Drying by:
Oven

Washed:
Sample Washed

Sieve Size	% Passing	Limits
1½in (37.5mm)		
1in (25.0mm)		
½in (12.5mm)		
3/8in (9.5mm)	100	
No.4 (4.75mm)	99	
No.10 (2.0mm)	86	
No.40 (425µm)	54	
No.100	41	
No.200 (75µm)	37	

Other Test Results

Description	Method	Results			Limits
Water Content (%)	ASTM D 2216	15.5	17.6	10.8	
Method		B	B	B	
Dispersion device	ASTM D 422	Dispersion Cup and Mixer			
Dispersion time (min)		1			
Shape					
Hardness					

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00402-S02

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.


Sample Details

Sample ID	FH18-W00402-S02
Field Sample ID	GW992-SS2
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/16/2018
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	Unified Soil Classification System
Sampling Method	Split Spoon
Contractor	N/A

Sample Description:

Brown / orange sandy lean clay (CL)

Particle Size Distribution



COBBLES	GRAVEL		SAND			FINES	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
(0.0%)	(0.5%)	(6.5%)	(13.0%)	(13.0%)	(10.0%)	(30.0%)	(27.0%)

Grading: ASTM D 422

Drying by: Oven
Date Tested: 2/28/2018
Tested By: Sheila Bowers

Sieve Size	% Passing	Limits
1½in	100	
1in	100	
½in	99	
3/8in	98	
No.4	93	
No.10	80	
No.40	67	
No.100	61	
No.200	57	
23.4 µm	40.6	
15.5 µm	37.5	
9.5 µm	32.7	
7.0 µm	29.6	
5.1 µm	27.2	
2.6 µm	22.2	
1.2 µm	16.7	

D85: 2.7894 **D60:** 0.1261 **D50:** 0.0456
D30: 0.0073 **D15:** N/A **D10:** N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00402-S02

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

AASHTO ACCREDITATION PROGRAM

Reviewed By: Timothy A. Moore, Jr.

Sample Details

Sample ID	FH18-W00402-S02
Field Sample ID	GW992-SS2
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/16/2018
Date Completed	
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	Unified Soil Classification System
Sampling Method	Split Spoon
Contractor	N/A
Dispersion Method	

Other Test Results

Description	Method	Result	Limits
Water Content (%)	ASTM D 2216	23.9	
Method		B	
Date Tested		3/1/2018	
Dispersion device	ASTM D 422	Dispersion Cup and Mixer	
Dispersion time (min)		1	
Shape			
Hardness			

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00402-S07

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.


Sample Details

Sample ID	FH18-W00402-S07
Field Sample ID	GW992-SS10
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/16/2018
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	Unified Soil Classification System
Sampling Method	Split Spoon
Contractor	N/A

Sample Description:

Brown clayey sand

Particle Size Distribution



COBBLES	GRAVEL		SAND			FINES	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
(0.0%)	(0.0%)	(1.0%)	(13.0%)	(32.0%)	(17.0%)	(24.3%)	(12.7%)

Grading: ASTM D 422

Drying by: Oven
Date Tested: 2/28/2018
Tested By: Sheila Bowers

Sieve Size	% Passing	Limits
3/8in	100	
No.4	99	
No.10	86	
No.40	54	
No.100	41	
No.200	37	
29.1 µm	24.8	
19.0 µm	21.5	
11.3 µm	18.1	
8.2 µm	15.6	
5.8 µm	13.9	
3.0 µm	9.8	
1.2 µm	8.1	

D85: 1.9055 **D60:** 0.5682 **D50:** 0.3085
D30: 0.0436 **D15:** 0.0073 **D10:** 0.0031
Cu: 183.41 **Cc:** 1.08

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00402-S07

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Sample Details

Sample ID	FH18-W00402-S07
Field Sample ID	GW992-SS10
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/16/2018
Date Completed	
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	Unified Soil Classification System
Sampling Method	Split Spoon
Contractor	N/A
Dispersion Method	

Other Test Results

Description	Method	Result	Limits
Water Content (%)	ASTM D 2216	15.5	
Method		B	
Date Tested		3/1/2018	
Dispersion device	ASTM D 422	Dispersion Cup and Mixer	
Dispersion time (min)		1	
Shape			
Hardness			

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: ASM:FH18-W00403

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

AASHTO ACCREDITATION PROGRAM

Reviewed By: Timothy A. Moore, Jr.

Material Details

Source	Geotechnical Drilling Samples	**Sampled From**	Split Spoon
Description	Native Existing Material	**Location**	Oak Ridge, Tennessee
Specification	USCS	**Sampling Method**	Split Spoon

Sample Details

Sample ID	FH18-W00403-S0	FH18-W00403-S0	FH18-W00403-S0	FH18-W00403-S0	FH18-W00403-S0	FH18-W00403-S0
Field Sample ID	GW994-SS2[1]	GW994-SS3[2]	GW994-SS4[3]	GW994-SS6[4]	GW994-SS8[5]	GW994-SS10[6]
Date Sampled	2/16/2018	2/16/2018	2/16/2018	2/16/2018	2/16/2018	2/16/2018

Other Test Results

Description	Method	Results						Limits
Water Content (%)	ASTM D 2216	22.8	23.6	21.7	39.2	24.4	16.6	
Method		B	B	B	B	B	B	
Approximate maximum grain size	ASTM D 4318							
Material retained on 425µm (No. 40) (%)								
Method of Removal								
Grooving Tool Type		Metal						
Specimen preparation method		Wet						
Drying Method		Air						
Special selection process		Quartering						
Rolling Method for PL		Hand						
As Received Water Content (%)		22.8						
Liquid Limit Device Type		Manual						
Liquid Limit		47						
Plastic Limit		18						
Plasticity Index		29						
Liquid Limit Procedure		Multipoint (A)						
Method	ASTM D 6913			Method B				
Sample Obtained While				Air-Dried				
Group Name				Lean clay				
Group Symbol				CL				
Composite Sieving Used				No				
Dispersion Method				Dispersant by hand				
Prior Testing				Moisture				

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: ASM:FH18-W00403

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Material Details

Source	Geotechnical Drilling Samples	**Sampled From**	Split Spoon
Description	Native Existing Material	**Location**	Oak Ridge, Tennessee
Specification	USCS	**Sampling Method**	Split Spoon

Sample Details

Sample ID	FH18-W00403-S0	FH18-W00403-S0	FH18-W00403-S0	FH18-W00403-S1	FH18-W00403-S1
Field Sample ID	GW994-SS127	GW994-SS148	GW994-SS159	GW994-SS170	GW994-SS181
Date Sampled	2/16/2018	2/16/2018	2/16/2018	2/16/2018	2/16/2018

Other Test Results

Description	Method	Results					Limits
Water Content (%)	ASTM D 2216	18.7	13.6	13.3	15.9	14.6	
Method		B	B	B	B	B	
Method	ASTM D 6913		Method B				
Sample Obtained While			Air-Dried				
Group Name							
Group Symbol							
Composite Sieving Used			No				
Dispersion Method			Dispersant by hand				
Prior Testing			Moisture				

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00403-S03

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.


Sample Details

Sample ID	FH18-W00403-S03
Field Sample ID	GW994-SS4
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/16/2018
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A

Sample Description:

Brown mottled lean clay (CL)

Particle Size Distribution



COBBLES	GRAVEL		SAND			FINES (90.0%)	
(0.0%)	Coarse (0.0%)	Fine (0.6%)	Coarse (1.0%)	Medium (1.5%)	Fine (6.9%)	Silt	Clay

Grading: ASTM D 6913

Drying by: Oven
Date Tested: 3/2/2018
Tested By: David Cook

Sieve Size	% Passing	Limits
½in	100.0	
3/8in	99.7	
No.4	99.4	
No.8	98.6	
No.10	98.4	
No.16	97.7	
No.30	97.1	
No.40	96.9	
No.50	96.4	
No.100	94.6	
No.200	90.0	

D85: N/A **D60:** N/A **D50:** N/A
D30: N/A **D15:** N/A **D10:** N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00403-S03

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Sample Details

Sample ID	FH18-W00403-S03
Field Sample ID	GW994-SS4
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/16/2018
Date Completed	
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A
Dispersion Method	

Other Test Results

Description	Method	Result	Limits
Water Content (%)	ASTM D 2216	21.7	
Method		B	
Date Tested		3/1/2018	
Method	ASTM D 6913	Method B	
Sample Obtained While		Air-Dried	
Group Name		Lean clay	
Group Symbol		CL	
Composite Sieving Used		No	
Dispersion Method		Dispersant by hand	
Prior Testing		Moisture	

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00403-S08

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.


Sample Details

Sample ID	FH18-W00403-S08
Field Sample ID	GW994-SS14
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/16/2018
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A

Sample Description:

Brown clayey sand

Particle Size Distribution



COBBLES	GRAVEL		SAND			FINES (33.9%)	
	Coarse	Fine	Coarse	Medium	Fine		
(0.0%)	(0.0%)	(9.2%)	(15.4%)	(25.2%)	(16.3%)	Silt	Clay

Grading: ASTM D 6913

Drying by: Oven
Date Tested: 3/2/2018
Tested By: David Cook

Sieve Size	% Passing	Limits
½in	100.0	
3/8in	97.3	
No.4	90.8	
No.8	77.6	
No.10	75.4	
No.16	64.6	
No.30	54.2	
No.40	50.2	
No.50	46.4	
No.100	39.7	
No.200	33.9	

D85: 3.4931 **D60:** 0.8749 **D50:** 0.4173
D30: N/A **D15:** N/A **D10:** N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00403-S08

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Sample Details

Sample ID	FH18-W00403-S08
Field Sample ID	GW994-SS14
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/16/2018
Date Completed	
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A
Dispersion Method	

Other Test Results

Description	Method	Result	Limits
Water Content (%)	ASTM D 2216	13.6	
Method		B	
Date Tested		3/1/2018	
Method	ASTM D 6913	Method B	
Sample Obtained While		Air-Dried	
Group Name			
Group Symbol			
Composite Sieving Used		No	
Dispersion Method		Dispersant by hand	
Prior Testing		Moisture	

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: ASM:FH18-W00404

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

AASHTO ACCREDITATION PROGRAM

Reviewed By: Timothy A. Moore, Jr.

Material Details

Source	Geotechnical Drilling Samples	**Sampled From**	Split Spoon
Description	Native Existing Material	**Location**	Oak Ridge, Tennessee
Specification	USCS	**Sampling Method**	Split Spoon

Sample Details

Sample ID	FH18-W00404-S0	FH18-W00404-S0	FH18-W00404-S0	FH18-W00404-S0	FH18-W00404-S0	FH18-W00404-S0
Field Sample ID	GW998-SS1[1]	GW998-SS2[2]	GW998-SS3[3]	GW998-SS4[4]	GW998-SS5[5]	GW998-SS7[6]
Date Sampled	2/14/2018	2/14/2018	2/14/2018	2/14/2018	2/14/2018	2/14/2018

Other Test Results

Description	Method	Results						Limits
Water Content (%)	ASTM D 2216	18.9	22.0	27.4	18.6	26.0	23.8	
Method		B	B	B	B	B	B	
Approximate maximum grain size	ASTM D 4318							
Material retained on 425µm (No. 40) (%)								
Method of Removal								
Grooving Tool Type		Metal						
Specimen preparation method		Wet						
Drying Method		Air						
Special selection process		Quartering						
Rolling Method for PL		Hand						
As Received Water Content (%)		27.4						
Liquid Limit Device Type		Manual						
Liquid Limit		38						
Plastic Limit		22						
Plasticity Index		16						
Liquid Limit Procedure		Multipoint (A)						
Method	ASTM D 6913				Method B			
Sample Obtained While					Air-Dried			
Group Name								
Group Symbol								
Composite Sieving Used					No			
Dispersion Method					Dispersant by hand			
Prior Testing					Moisture			

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: ASM:FH18-W00404

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

AASHTO ACCREDITATION PROGRAM

Reviewed By: Timothy A. Moore, Jr.

Material Details

Source	Geotechnical Drilling Samples	**Sampled From**	Split Spoon
Description	Native Existing Material	**Location**	Oak Ridge, Tennessee
Specification	USCS	**Sampling Method**	Split Spoon

Sample Details

Sample ID	FH18-W00404-S07
Field Sample ID	GW998-SS9
Date Sampled	2/14/2018

Other Test Results

Description	Method	Results	Limits
Water Content (%)	ASTM D 2216	15.4	
Method		B	

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00404-S04

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.


Sample Details

Sample ID	FH18-W00404-S04
Field Sample ID	GW998-SS4
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/14/2018
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A

Sample Description:

Brown clayey sand

Particle Size Distribution



Grading: ASTM D 6913

Drying by: Oven
Date Tested: 3/2/2018
Tested By: David Cook

Sieve Size	% Passing	Limits
½in	100.0	
3/8in	99.9	
No.4	95.7	
No.8	84.9	
No.10	82.9	
No.16	73.3	
No.30	63.2	
No.40	58.5	
No.50	53.6	
No.100	44.3	
No.200	37.3	

COBBLES	GRAVEL		SAND			FINES (37.3%)	
	Coarse	Fine	Coarse	Medium	Fine		
(0.0%)	(0.0%)	(4.3%)	(12.8%)	(24.4%)	(21.2%)	Silt	Clay

D85: 2.3753 **D60:** 0.4744 **D50:** 0.2294
D30: N/A **D15:** N/A **D10:** N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00404-S04

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Timothy A. Moore, Jr.

Sample Details

Sample ID	FH18-W00404-S04
Field Sample ID	GW998-SS4
Location	Oak Ridge, Tennessee
Sampled By	Mike Partenio
Date Sampled	2/14/2018
Date Completed	
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	USCS
Sampling Method	Split Spoon
Contractor	N/A
Dispersion Method	

Other Test Results

Description	Method	Result	Limits
Water Content (%)	ASTM D 2216	18.6	
Method		B	
Date Tested		3/13/2018	
Method	ASTM D 6913	Method B	
Sample Obtained While		Air-Dried	
Group Name			
Group Symbol			
Composite Sieving Used		No	
Dispersion Method		Dispersant by hand	
Prior Testing		Moisture	

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

Appendix F.2 – Bulk Soil Sample Testing

This Page Intentionally Left Blank.

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Proctor Report

Project No.: 1188070011-05B
ReportNo: PTR:FH18-W00468-S01

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee


This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Peng Lor

Sample Details

Sample ID:	FH18-W00468-S01	**Field Sample ID:**	GW979
Date Sampled:	2/21/2018	**Sampled By:**	Mike Partenio
Sampling Method:	In-Place		
Contractor:	N/A		
Source:	Geotechnical Drilling Samples		
Material:	Native Existing Material		
Specification:	N/A		
Location:	Boring Spoils		
Tested By:	Sheila Bowers	**Date Tested:**	3/16/2018

Dry Unit Weight - Water Content Relationship



Test Results

ASTM D 1557

Maximum Dry Unit Weight (lbf/ft³):	**114.8**
Optimum Water Content (%):	**13.5**
Method:	B
Preparation Method:	Moist
Specific Gravity (Fines):	2.70
Visual Description:	Redish/Brown Clay

Comments

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Proctor Report

Project No.: 1188070011-05B
ReportNo: PTR:FH18-W00468-S02

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee


This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Peng Lor

Sample Details

Sample ID:	FH18-W00468-S02	**Field Sample ID:**	GW981
Date Sampled:	2/23/2018	**Sampled By:**	Mike Partenio
Sampling Method:	In-Place		
Contractor:	N/A		
Source:	Geotechnical Drilling Samples		
Material:	Native Existing Material		
Specification:	N/A		
Location:	Boring Spoils		
Tested By:	Sheila Bowers	**Date Tested:**	3/16/2018

Dry Unit Weight - Water Content Relationship



Test Results

ASTM D 1557

Maximum Dry Unit Weight (lbf/ft³):	**120.7**
Optimum Water Content (%):	**13.9**
Method:	B
Preparation Method:	Moist
Specific Gravity (Fines):	2.70
Visual Description:	Brown Clay

Comments

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00468-S03

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Peng Lor


Sample Details

Sample ID	FH18-W00468-S03
Field Sample ID	GW983
Location	Boring Spoils
Sampled By	Mike Partenio
Date Sampled	2/21/2018
Date Completed	3/13/2018
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	N/A
Sampling Method	In-Place
Contractor	N/A

Sample Description:

Brown Sandy Clay

Particle Size Distribution



COBBLES	GRAVEL		SAND			FINES	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
(0.0%)	(0.0%)	(4.0%)	(9.0%)	(13.0%)	(15.0%)	(38.9%)	(20.1%)

Grading: ASTM D 422

Drying by: Oven
Date Tested: 3/22/2018
Tested By: David Cook

Sieve Size	% Passing	Limits
½in	100	
3/8in	99	
No.4	96	
No.10	87	
No.40	74	
No.100	67	
No.200	59	
28.0 µm	41.8	
18.7 µm	33.4	
11.3 µm	27.4	
8.1 µm	23.8	
5.8 µm	21.4	
2.9 µm	16.8	
1.2 µm	13.2	

D85: 1.5760 **D60:** 0.0818 **D50:** 0.0448
D30: 0.0141 **D15:** 0.0019 **D10:** N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00468-S03

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Peng Lor

Sample Details

Sample ID	FH18-W00468-S03
Field Sample ID	GW983
Location	Boring Spoils
Sampled By	Mike Partenio
Date Sampled	2/21/2018
Date Completed	3/13/2018
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	N/A
Sampling Method	In-Place
Contractor	N/A
Dispersion Method	

Other Test Results

Description	Method	Result	Limits
Maximum Dry Unit Weight (lbf/ft³)	ASTM D 1557	120.2	
Corrected Maximum Dry Unit Weight (lbf/ft³)		120.2	
Optimum Water Content (%)		11.3	
Corrected Optimum Water Content (%)		11.3	
Method		B	
Preparation Method		Moist	
Visual Description		Brown Sandy Clay	
Specific Gravity (Fines)		2.70	
Date Tested		3/20/2018	
Dispersion device	ASTM D 422	Soil Dispersion Cup and Mixer	
Dispersion time (min)		1	
Shape			
Hardness			
Maximum Dry Unit Weight (lbf/ft³)	ASTM D 698	112.2	
Corrected Maximum Dry Unit Weight (lbf/ft³)		112.2	
Optimum Water Content (%)		11.7	
Corrected Optimum Water Content (%)		11.7	
Method		B	
Preparation Method		Moist	
Visual Description		Brown Sandy Clay	
Retained Sieve 3/8" (9.5mm) (%)		0	
Specific Gravity (Fines)		2.70	
Date Tested		3/20/2018	

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Proctor Report

Project No.: 1188070011-05B
ReportNo: PTR:FH18-W00468-S03

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee


This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Peng Lor

Sample Details

Sample ID:	FH18-W00468-S03	**Field Sample ID:**	GW983
Date Sampled:	2/21/2018	**Sampled By:**	Mike Partenio
Sampling Method:	In-Place		
Contractor:	N/A		
Source:	Geotechnical Drilling Samples		
Material:	Native Existing Material		
Specification:	N/A		
Location:	Boring Spoils		
Tested By:	Sheila Bowers	**Date Tested:**	3/20/2018

Dry Unit Weight - Water Content Relationship



Test Results

ASTM D 1557

Maximum Dry Unit Weight (lbf/ft³):	**120.2**
Optimum Water Content (%):	**11.3**
Method:	B
Preparation Method:	Moist
Specific Gravity (Fines):	2.70
Visual Description:	Brown Sandy Clay

Comments

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Proctor Report

Project No.: 1188070011-05B
ReportNo: PTR:FH18-W00468-S03

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee


This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Peng Lor

Sample Details

Sample ID:	FH18-W00468-S03	**Field Sample ID:**	GW983
Date Sampled:	2/21/2018	**Sampled By:**	Mike Partenio
Sampling Method:	In-Place		
Contractor:	N/A		
Source:	Geotechnical Drilling Samples		
Material:	Native Existing Material		
Specification:	N/A		
Location:	Boring Spoils		
Tested By:	Sheila Bowers	**Date Tested:**	3/20/2018

Dry Unit Weight - Water Content Relationship



Test Results

ASTM D 698

Maximum Dry Unit Weight (lbf/ft³):	**112.2**
Optimum Water Content (%):	**11.7**
Method:	B
Preparation Method:	Moist
Specific Gravity (Fines):	2.70
Retained Sieve 3/8" (9.5mm) (%):	0
Passing Sieve 3/8" (9.5mm) (%):	100
Visual Description:	Brown Sandy Clay

Comments

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00468-S04

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Peng Lor


Sample Details

Sample ID	FH18-W00468-S04
Field Sample ID	GW989
Location	Boring Spoils
Sampled By	Mike Partenio
Date Sampled	2/27/2018
Date Completed	3/13/2018
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	N/A
Sampling Method	In-Place
Contractor	N/A

Sample Description:

Brown Clay with Sand

Particle Size Distribution



Grading: ASTM D 6913

Drying by: Oven
Date Tested: 3/15/2018
Tested By: Sheila Bowers

Sieve Size	% Passing	Limits
¾in	100.0	
½in	99.5	
3/8in	99.5	
No.4	98.6	
No.8	95.4	
No.10	94.7	
No.16	91.2	
No.30	86.9	
No.40	85.0	
No.50	83.3	
No.100	80.2	
No.200	75.7	

COBBLES	GRAVEL		SAND			FINES (75.7%)	
	Coarse	Fine	Coarse	Medium	Fine		
(0.0%)	(0.0%)	(1.4%)	(3.9%)	(9.7%)	(9.3%)	Silt	Clay

D85: 0.4250 **D60:** N/A **D50:** N/A
D30: N/A **D15:** N/A **D10:** N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00468-S04

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Peng Lor

Sample Details

Sample ID	FH18-W00468-S04
Field Sample ID	GW989
Location	Boring Spoils
Sampled By	Mike Partenio
Date Sampled	2/27/2018
Date Completed	3/13/2018
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	N/A
Sampling Method	In-Place
Contractor	N/A
Dispersion Method	

Other Test Results

Description	Method	Result	Limits
Maximum Dry Unit Weight (lbf/ft³)	ASTM D 1557	107.8	
Corrected Maximum Dry Unit Weight (lbf/ft³)		107.8	
Optimum Water Content (%)		12.5	
Corrected Optimum Water Content (%)		12.5	
Method		B	
Preparation Method		Moist	
Visual Description		Brown Clay with Sand	
Specific Gravity (Fines)		2.70	
Method	ASTM D 6913	Method B	
Sample Obtained While		Oven-Dried	
Group Name			
Group Symbol			
Composite Sieving Used		No	
Dispersion Method		Dispersant by hand	
Prior Testing		Moisture	

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Proctor Report

Project No.: 1188070011-05B
ReportNo: PTR:FH18-W00468-S04

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee


This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Peng Lor

Sample Details

Sample ID:	FH18-W00468-S04	**Field Sample ID:**	GW989
Date Sampled:	2/27/2018	**Sampled By:**	Mike Partenio
Sampling Method:	In-Place		
Contractor:	N/A		
Source:	Geotechnical Drilling Samples		
Material:	Native Existing Material		
Specification:	N/A		
Location:	Boring Spoils		
Tested By:	Sheila Bowers	**Date Tested:**	

Dry Unit Weight - Water Content Relationship



Test Results

ASTM D 1557

Maximum Dry Unit Weight (lbf/ft³):	**107.8**
Optimum Water Content (%):	**12.5**
Method:	B
Preparation Method:	Moist
Specific Gravity (Fines):	2.70
Visual Description:	Brown Clay with Sand

Comments

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00468-S06

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Peng Lor


Sample Details

Sample ID	FH18-W00468-S06
Field Sample ID	GW999
Location	Boring Spoils
Sampled By	Mike Partenio
Date Sampled	2/20/2018
Date Completed	3/13/2018
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	N/A
Sampling Method	In-Place
Contractor	N/A

Sample Description:

Brown Sandy Clay

Particle Size Distribution



COBBLES	GRAVEL		SAND			FINES (61.1%)	
(0.0%)	Coarse (0.0%)	Fine (3.5%)	Coarse (9.3%)	Medium (14.9%)	Fine (11.2%)	Silt	Clay

Grading: ASTM D 6913

Drying by: Oven
Date Tested: 3/15/2018
Tested By: Sheila Bowers

Sieve Size	% Passing	Limits
½in	100.0	
3/8in	99.5	
No.4	96.5	
No.8	88.6	
No.10	87.2	
No.16	80.7	
No.30	74.7	
No.40	72.3	
No.50	69.8	
No.100	64.9	
No.200	61.1	

D85: 1.6729 **D60:** N/A **D50:** N/A
D30: N/A **D15:** N/A **D10:** N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Material Test Report

Project No.: 1188070011-05B
ReportNo: MAT:FH18-W00468-S06

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee

This report shall not be reproduced (in part or whole) without the written consent of:

Reviewed By: Peng Lor

Sample Details

Sample ID	FH18-W00468-S06
Field Sample ID	GW999
Location	Boring Spoils
Sampled By	Mike Partenio
Date Sampled	2/20/2018
Date Completed	3/13/2018
Source	Geotechnical Drilling Samples
Material	Native Existing Material
Specification	N/A
Sampling Method	In-Place
Contractor	N/A
Dispersion Method	

Other Test Results

Description	Method	Result	Limits
Maximum Dry Unit Weight (lbf/ft³)	ASTM D 1557	110.6	
Corrected Maximum Dry Unit Weight (lbf/ft³)		110.6	
Optimum Water Content (%)		12.1	
Corrected Optimum Water Content (%)		12.1	
Method		B	
Preparation Method		Moist	
Visual Description		Brown Sandy Clay	
Specific Gravity (Fines)		2.70	
Method	ASTM D 6913	Method B	
Sample Obtained While		Oven-Dried	
Group Name			
Group Symbol			
Composite Sieving Used		No	
Dispersion Method		Dispersant by hand	
Prior Testing		Moisture	

Comments

N/A

© 2000-2016 QESTLab by SpectraQEST.com

28001 Cabot Drive, Suite 250
Novi, MI 48377
Phone: (248) 486-5100
Fax: (248) 486-5050

Proctor Report

Project No.: 1188070011-05B
ReportNo: PTR:FH18-W00468-S06

Client: Strata-G, LLC **CC:**

Project: EMDF Site 7c Characterization

Oak Ridge, Tennessee


This report shall not be reproduced (in part or whole) without the written constent of:

Reviewed By: Peng Lor

Sample Details

Sample ID:	FH18-W00468-S06	**Field Sample ID:**	GW999
Date Sampled:	2/20/2018	**Sampled By:**	Mike Partenio
Sampling Method:	In-Place		
Contractor:	N/A		
Source:	Geotechnical Drilling Samples		
Material:	Native Existing Material		
Specification:	N/A		
Location:	Boring Spoils		
Tested By:	Sheila Bowers	**Date Tested:**	

Dry Unit Weight - Water Content Relationship



Test Results

ASTM D 1557

Maximum Dry Unit Weight (lbf/ft³):	**110.6**
Optimum Water Content (%):	**12.1**
Method:	B
Preparation Method:	Moist
Specific Gravity (Fines):	2.70
Visual Description:	Brown Sandy Clay

Comments

© 2000-2016 QESTLab by SpectraQEST.com

Appendix F.3 – Shelby Tube Sample Testing

This Page Intentionally Left Blank.

BOWSER-MORNER, INC.

Delivery Address: 4518 Taylorsville Road • Dayton, Ohio 45424 **Mailing Address**: P. O. Box 51 • Dayton, Ohio 45401

AASHTO/ISO 17025 Accredited • USACE Validated

LABORATORY REPORT

Report To: CTI & Associates, Inc.
Attn: Michael Partenio
28001 Cabot Drive, Ste. 250
Novi, MI 48377

Report Date: April 17, 2018
Job No.: 183923
Report No.: 430211
No. of Pages: 2

Report On: Laboratory Analysis of One Shelby Tube Sample
Project: EMDF Characterization – Project No. 1188070011
Sample ID: GW993 – ST-1, 3.0'-5.0' – Sample Date: 2/22/18
Depth of Test Specimen: 3.5' - 3.8'

On March 5, 2018, one Shelby tube sample was submitted for laboratory determination of permeability. Testing was performed as specified by the client and in accordance with ASTM D 5084, "Measurement of Hydraulic Conductivity of Saturated Porous Materials Using a Flexible Wall Permeameter".

Results are presented in the following table.

Test Parameter	Results
Average Permeability, cm/sec:	**5.5×10^{-7}**

Should you have any questions, or if we may be of further service, please contact me at (937) 236-8805, extension 322.

Respectfully submitted,
BOWSER-MORNER, INC.

Karl A. Fletcher, Manager
Construction Materials and
Geotechnical Laboratories

KAF/blc
430211
1-File
1-mpartenio@cticompanies.com
1-kfoye@cticompanies.com

All Reports Remain The Confidential Property Of BOWSER-MORNER And No Publication Or Distribution Of Reports May Be Made Without Our Express Written Consent, Except As Authorized By Contract. Results Contained In This Report Are Reflective Only of The Items Calibrated or Tested. Unless Otherwise Agreed, Samples Or Specimens Will Be Discarded Or Returned At Bowser-Morner's Discretion. AASHTO/ISO 17025 Accreditation applies only to the parameters included in BOWSER-MORNER'S current scope of accreditation. Go to www.bowser-morner.com/accreditations for reviews.

FALLING HEAD PERMEABILITY TEST

ASTM D 5084, Measurement of Hydraulic Conductivity


UNDISTURBED

Client:	**CTI and Associates, Inc.**
Project:	**EMDF Characterization - Project No. 1188070011**
BMI Work Order Number:	183923
Sample Identification:	GW993 - ST-1, 3.0'-5.0'
Depth, ft:	3.5'-3.8'
Visual Description:	brown clay and silt, little gravel

SPECIMEN DATA:

Dimension, inches	
Height:	2.559
Diameter:	2.82
Mass, lbs:	1.149
Moisture Content,%	
Initial:	26.5
Final:	26.2
Wet Unit Weight, pcf	
Initial:	124.2
Final:	123.9
Initial Dry Unit Weight, pcf:	98.2
Back Pressure Saturation, psi	
Back Pressure, Exit:	60
Back Pressure, Enter:	63
Lateral Pressure:	67

Permeability (k), cm/sec: **5.5×10^{-7}**




			BEFORE TEST	AFTER TEST
OVERBURDEN PRESSURE (t/ft^2)		WATER CONTENT (%)	21.2	18.2
PRECONSOL. PRESSURE (t/ft^2)		DRY DENSITY (lb/ft^3)	99.33	112.37
COMPRESSION INDEX		SATURATION (%)	82.63	98.95
TYPE SPECIMEN	Undisturb	VOID RATIO	0.69	0.49
DIA. (in) 2.500	HT. (in) 1.020	BACK PRESSURE (t/ft^2)	---	---


CLASSIFICATION red/brown silty clay and sand (visual description)

LL ---	PL ---	PI ---	PROJECT EMDF Characterization
GS 2.689	D_{10}		987ST3
REMARKS		BORING NO. GW987-ST-3	SAMPLE NO. GW987-ST-3
Use: Foundation berm/fill		DEPTH 2.8'-3.0'	DATE 3-15-18

Bowser Morner
CONSOLIDATION TEST REPORT


CONSOLIDATION TEST
TIME CURVES (STEP 1 OF 20)
STRESS : 0.06 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW987-ST-3 Sample No : GW987-ST-3
Test Date : 3-15-18 Test No : GW987-ST-3 Depth : 2.8'-3.0'
Description : red/brown silty clay and sand (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 2 OF 20)
STRESS : 0.25 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW987-ST-3 Sample No : GW987-ST-3
Test Date : 3-15-18 Test No : GW987-ST-3 Depth : 2.8'-3.0'
Description : red/brown silty clay and sand (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 3 OF 20)
STRESS : 0.5 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW987-ST-3 Sample No : GW987-ST-3
Test Date : 3-15-18 Test No : GW987-ST-3 Depth : 2.8'-3.0'
Description : red/brown silty clay and sand (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 4 OF 20)
STRESS : 1 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW987-ST-3 Sample No : GW987-ST-3
Test Date : 3-15-18 Test No : GW987-ST-3 Depth : 2.8'-3.0'
Description : red/brown silty clay and sand (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 5 OF 20)
STRESS : 2 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW987-ST-3 Sample No : GW987-ST-3
Test Date : 3-15-18 Test No : GW987-ST-3 Depth : 2.8'-3.0'
Description : red/brown silty clay and sand (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 6 OF 20)
STRESS : 4 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW987-ST-3 Sample No : GW987-ST-3
Test Date : 3-15-18 Test No : GW987-ST-3 Depth : 2.8'-3.0'
Description : red/brown silty clay and sand (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 7 OF 20)
STRESS : 2 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW987-ST-3 Sample No : GW987-ST-3
Test Date : 3-15-18 Test No : GW987-ST-3 Depth : 2.8'-3.0'
Description : red/brown silty clay and sand (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 8 OF 20)
STRESS : 1 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW987-ST-3 Sample No : GW987-ST-3
Test Date : 3-15-18 Test No : GW987-ST-3 Depth : 2.8'-3.0'
Description : red/brown silty clay and sand (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 9 OF 20)
STRESS : 0.5 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW987-ST-3 Sample No : GW987-ST-3
Test Date : 3-15-18 Test No : GW987-ST-3 Depth : 2.8'-3.0'
Description : red/brown silty clay and sand (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 10 OF 20)
STRESS : 1 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW987-ST-3 Sample No : GW987-ST-3
Test Date : 3-15-18 Test No : GW987-ST-3 Depth : 2.8'-3.0'
Description : red/brown silty clay and sand (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 11 OF 20)
STRESS : 2 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW987-ST-3 Sample No : GW987-ST-3
Test Date : 3-15-18 Test No : GW987-ST-3 Depth : 2.8'-3.0'
Description : red/brown silty clay and sand (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 12 OF 20)
STRESS : 4 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW987-ST-3 Sample No : GW987-ST-3
Test Date : 3-15-18 Test No : GW987-ST-3 Depth : 2.8'-3.0'
Description : red/brown silty clay and sand (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 13 OF 20)
STRESS : 8 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW987-ST-3 Sample No : GW987-ST-3
Test Date : 3-15-18 Test No : GW987-ST-3 Depth : 2.8'-3.0'
Description : red/brown silty clay and sand (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 14 OF 20)
STRESS : 16 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW987-ST-3 Sample No : GW987-ST-3
Test Date : 3-15-18 Test No : GW987-ST-3 Depth : 2.8'-3.0'
Description : red/brown silty clay and sand (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 15 OF 20)
STRESS : 32 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW987-ST-3 Sample No : GW987-ST-3
Test Date : 3-15-18 Test No : GW987-ST-3 Depth : 2.8'-3.0'
Description : red/brown silty clay and sand (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 16 OF 20)
STRESS : 16 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW987-ST-3 Sample No : GW987-ST-3
Test Date : 3-15-18 Test No : GW987-ST-3 Depth : 2.8'-3.0'
Description : red/brown silty clay and sand (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 17 OF 20)
STRESS : 8 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW987-ST-3 Sample No : GW987-ST-3
Test Date : 3-15-18 Test No : GW987-ST-3 Depth : 2.8'-3.0'
Description : red/brown silty clay and sand (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 18 OF 20)
STRESS : 4 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW987-ST-3 Sample No : GW987-ST-3
Test Date : 3-15-18 Test No : GW987-ST-3 Depth : 2.8'-3.0'
Description : red/brown silty clay and sand (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 19 OF 20)
STRESS : 2 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW987-ST-3 Sample No : GW987-ST-3
Test Date : 3-15-18 Test No : GW987-ST-3 Depth : 2.8'-3.0'
Description : red/brown silty clay and sand (visual description)

CONSOLIDATION TEST
TIME CURVES (STEP 20 OF 20)
STRESS : 1 (t/ft^2)





Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW987-ST-3 Sample No : GW987-ST-3
Test Date : 3-15-18 Test No : GW987-ST-3 Depth : 2.8'-3.0'
Description : red/brown silty clay and sand (visual description)

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW987-ST-3, 2.0'-4.0'
Project No.: 183923
Boring No.: GW987-ST-3
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW987-ST-3
Test Date : 3-15-18
Depth : 2.8'-3.0'
Test No. : GW987-ST-3
Sample Type: Undisturb

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

	APPLIED PRESSURE (t/ft^2)	FINAL DISPLACEMENT (in)	VOID RATIO	STRAIN AT END (%)	FITTING T50 TIME (min) SQ.RT.	FITTING T50 TIME (min) LOG	COEFFICIENT OF CONSOLIDATION (in^2/s) SQ.RT.	COEFFICIENT OF CONSOLIDATION (in^2/s) LOG	COEFFICIENT OF CONSOLIDATION (in^2/s) AVE
1)	0.06	0.001	0.689	0.05	0.0	0.0	0.00E+000	0.00E+000	0.00E+000
2)	0.25	0.001	0.688	0.10	0.0	0.0	0.00E+000	0.00E+000	0.00E+000
3)	0.50	0.007	0.678	0.70	0.0	0.0	0.00E+000	0.00E+000	0.00E+000
4)	1.00	0.016	0.663	1.60	4.1	0.0	2.05E-004	0.00E+000	2.05E-004
5)	2.00	0.031	0.638	3.05	1.0	0.0	7.94E-004	0.00E+000	7.94E-004
6)	4.00	0.056	0.598	5.45	0.9	0.0	8.76E-004	0.00E+000	8.76E-004
7)	2.00	0.052	0.604	5.11	0.0	0.6	0.00E+000	1.35E-003	1.35E-003
8)	1.00	0.048	0.611	4.70	0.0	0.0	0.00E+000	0.00E+000	0.00E+000
9)	0.50	0.044	0.616	4.36	23.5	0.0	3.31E-005	0.00E+000	3.31E-005
10)	1.00	0.047	0.613	4.56	0.0	0.0	0.00E+000	0.00E+000	0.00E+000
11)	2.00	0.050	0.607	4.90	0.0	0.0	0.00E+000	0.00E+000	0.00E+000
12)	4.00	0.058	0.595	5.65	4.6	0.0	1.67E-004	0.00E+000	1.67E-004
13)	8.00	0.089	0.543	8.71	0.8	0.0	9.37E-004	0.00E+000	9.37E-004
14)	16.00	0.119	0.492	11.70	0.9	0.0	7.96E-004	0.00E+000	7.96E-004
15)	32.00	0.152	0.439	14.86	0.8	0.0	8.06E-004	0.00E+000	8.06E-004
16)	16.00	0.146	0.448	14.31	0.0	0.0	0.00E+000	0.00E+000	0.00E+000
17)	8.00	0.139	0.460	13.60	0.0	0.0	0.00E+000	0.00E+000	0.00E+000
18)	4.00	0.132	0.472	12.90	0.0	0.0	0.00E+000	0.00E+000	0.00E+000
19)	2.00	0.126	0.482	12.31	21.4	0.0	3.05E-005	0.00E+000	3.05E-005
20)	1.00	0.118	0.494	11.60	39.4	0.0	1.68E-005	0.00E+000	1.68E-005

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW987-ST-3, 2.0'-4.0'	Project No.: 183923
Boring No.: GW987-ST-3	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW987-ST-3	Test Date : 3-15-18	Depth : 2.8'-3.0'
Test No. : GW987-ST-3	Sample Type: Undisturb	

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Specific Gravity : 2.69	Liquid Limit : 0	Initial Height : 1.02 (in)
Initial Void Ratio : 0.69	Plastic Limit : 0	Sample Diameter : 2.50 (in)
Final Void Ratio : 0.49	Plasticity Index : 0	

	BEFORE CONSOLIDATION		AFTER CONSOLIDATION	
	TRIMMINGS	SPECIMEN + RING	SPECIMEN + RING	TRIMMINGS
CONTAINER NO.		RING	RING	
WT CONTAINER + WET SOIL (gm)	158.23	158.23	154.28	154.28
WT CONTAINER + DRY SOIL (gm)	130.55	130.55	130.55	130.55
WT CONTAINER (gm)	0.00	0.00	0.00	0.00
WT DRY SOIL (gm)	130.55	130.55	130.55	130.55
WATER CONTENT (%)	21.20	21.20	18.18	18.18
VOID RATIO	------	0.69	0.49	------
DEGREE OF SATURATION (%)	------	82.63	98.95	------
DRY DENSITY (lb/ft^3)	------	99.33	112.37	------

Note: Specific Gravity and Void Ratios are calculated assuming the degree of saturation equals 100% at the end of the test. Therefor values may not represent actual values for the specimen.

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW987-ST-3, 2.0'-4.0'	Project No.: 183923
Boring No.: GW987-ST-3	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW987-ST-3	Test Date : 3-15-18	Depth : 2.8'-3.0'
Test No. : GW987-ST-3	Sample Type: Undisturb	

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 1 of 20
Stress increment from 0.00 (t/ft^2) to 0.06 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.15	0.39	0.0000	0.690	0.00
2)	0.90	0.95	0.0000	0.690	0.00
3)	2.88	1.70	0.0005	0.689	0.05
4)	3.92	1.98	0.0000	0.690	0.00
5)	5.90	2.43	0.0005	0.689	0.05

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW987-ST-3, 2.0'-4.0'
Project No.: 183923
Boring No.: GW987-ST-3
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW987-ST-3
Test Date : 3-15-18
Depth : 2.8'-3.0'
Test No. : GW987-ST-3
Sample Type: Undisturb

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 2 of 20
Stress increment from 0.06 (t/ft^2) to 0.25 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0010	0.688	0.10
2)	0.15	0.39	0.0005	0.689	0.05
3)	0.40	0.63	0.0010	0.688	0.10
4)	0.90	0.95	0.0005	0.689	0.05
5)	1.88	1.37	0.0010	0.688	0.10
6)	2.88	1.70	0.0010	0.688	0.10
7)	3.88	1.97	0.0005	0.689	0.05
8)	4.88	2.21	0.0010	0.688	0.10
9)	5.88	2.43	0.0010	0.688	0.10
10)	6.88	2.62	0.0010	0.688	0.10
11)	7.88	2.81	0.0010	0.688	0.10
12)	8.90	2.98	0.0010	0.688	0.10
13)	9.90	3.15	0.0010	0.688	0.10
14)	14.88	3.86	0.0010	0.688	0.10
15)	29.90	5.47	0.0010	0.688	0.10
16)	59.90	7.74	0.0010	0.688	0.10
17)	89.88	9.48	0.0010	0.688	0.10
18)	119.88	10.95	0.0010	0.688	0.10
19)	149.90	12.24	0.0010	0.688	0.10
20)	179.88	13.41	0.0010	0.688	0.10
21)	209.88	14.49	0.0010	0.688	0.10
22)	239.90	15.49	0.0010	0.688	0.10
23)	299.88	17.32	0.0010	0.688	0.10
24)	359.90	18.97	0.0010	0.688	0.10
25)	419.88	20.49	0.0010	0.688	0.10
26)	479.88	21.91	0.0010	0.688	0.10
27)	539.90	23.24	0.0010	0.688	0.10
28)	599.88	24.49	0.0010	0.688	0.10
29)	659.90	25.69	0.0010	0.688	0.10
30)	719.88	26.83	0.0015	0.687	0.15
31)	779.88	27.93	0.0010	0.688	0.10
32)	839.88	28.98	0.0010	0.688	0.10
33)	899.88	30.00	0.0010	0.688	0.10
34)	959.88	30.98	0.0010	0.688	0.10
35)	1019.88	31.94	0.0010	0.688	0.10

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW987-ST-3, 2.0'-4.0'	Project No.: 183923
Boring No.: GW987-ST-3	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW987-ST-3	Test Date : 3-15-18	Depth : 2.8'-3.0'
Test No. : GW987-ST-3	Sample Type: Undisturb	

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 2 of 20
Stress increment from 0.06 (t/ft^2) to 0.25 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.88	32.86	0.0020	0.687	0.20
37)	1139.88	33.76	0.0010	0.688	0.10
38)	1199.90	34.64	0.0010	0.688	0.10
39)	1259.90	35.50	0.0010	0.688	0.10
40)	1319.88	36.33	0.0010	0.688	0.10
41)	1379.88	37.15	0.0015	0.687	0.15
42)	1400.37	37.42	0.0010	0.688	0.10

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW987-ST-3, 2.0'-4.0'
Project No.: 183923
Boring No.: GW987-ST-3
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW987-ST-3
Test Date : 3-15-18
Depth : 2.8'-3.0'
Test No. : GW987-ST-3
Sample Type: Undisturb

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 3 of 20
Stress increment from 0.25 (t/ft^2) to 0.50 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0046	0.682	0.45
2)	0.15	0.39	0.0051	0.682	0.50
3)	0.42	0.65	0.0051	0.682	0.50
4)	0.90	0.95	0.0056	0.681	0.55
5)	1.90	1.38	0.0056	0.681	0.55
6)	2.92	1.71	0.0056	0.681	0.55
7)	3.90	1.97	0.0061	0.680	0.60
8)	4.92	2.22	0.0056	0.681	0.55
9)	5.92	2.43	0.0056	0.681	0.55
10)	6.90	2.63	0.0061	0.680	0.60
11)	7.92	2.81	0.0056	0.681	0.55
12)	8.90	2.98	0.0056	0.681	0.55
13)	9.92	3.15	0.0056	0.681	0.55
14)	14.92	3.86	0.0056	0.681	0.55
15)	29.93	5.47	0.0061	0.680	0.60
16)	59.95	7.74	0.0066	0.679	0.65
17)	89.90	9.48	0.0061	0.680	0.60
18)	119.90	10.95	0.0066	0.679	0.65
19)	149.92	12.24	0.0071	0.678	0.70
20)	179.90	13.41	0.0077	0.677	0.75
21)	209.90	14.49	0.0071	0.678	0.70
22)	239.90	15.49	0.0077	0.677	0.75
23)	299.92	17.32	0.0077	0.677	0.75
24)	359.90	18.97	0.0077	0.677	0.75
25)	419.92	20.49	0.0077	0.677	0.75
26)	479.92	21.91	0.0077	0.677	0.75
27)	539.90	23.24	0.0077	0.677	0.75
28)	599.92	24.49	0.0077	0.677	0.75
29)	659.92	25.69	0.0082	0.676	0.80
30)	719.90	26.83	0.0077	0.677	0.75
31)	779.92	27.93	0.0077	0.677	0.75
32)	839.90	28.98	0.0077	0.677	0.75
33)	899.95	30.00	0.0082	0.676	0.80
34)	959.90	30.98	0.0077	0.677	0.75
35)	1019.90	31.94	0.0077	0.677	0.75

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW987-ST-3, 2.0'-4.0'	Project No.: 183923
Boring No.: GW987-ST-3	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW987-ST-3	Test Date : 3-15-18	Depth : 2.8'-3.0'
Test No. : GW987-ST-3	Sample Type: Undisturb	

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 3 of 20
Stress increment from 0.25 (t/ft^2) to 0.50 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.0071	0.678	0.70
37)	1139.92	33.76	0.0077	0.677	0.75
38)	1199.90	34.64	0.0082	0.676	0.80
39)	1259.92	35.50	0.0077	0.677	0.75
40)	1293.48	35.96	0.0071	0.678	0.70

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW987-ST-3, 2.0'-4.0'
Project No.: 183923
Boring No.: GW987-ST-3
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW987-ST-3
Test Date : 3-15-18
Depth : 2.8'-3.0'
Test No. : GW987-ST-3
Sample Type: Undisturb

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 4 of 20
Stress increment from 0.50 (t/ft^2) to 1.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0138	0.667	1.35
2)	0.15	0.39	0.0138	0.667	1.35
3)	0.40	0.63	0.0143	0.666	1.40
4)	0.90	0.95	0.0143	0.666	1.40
5)	1.90	1.38	0.0148	0.665	1.45
6)	2.90	1.70	0.0148	0.665	1.45
7)	3.90	1.97	0.0148	0.665	1.45
8)	4.92	2.22	0.0153	0.665	1.50
9)	5.92	2.43	0.0153	0.665	1.50
10)	6.92	2.63	0.0153	0.665	1.50
11)	7.93	2.82	0.0153	0.665	1.50
12)	8.90	2.98	0.0153	0.665	1.50
13)	9.90	3.15	0.0158	0.664	1.55
14)	14.90	3.86	0.0158	0.664	1.55
15)	29.90	5.47	0.0158	0.664	1.55
16)	59.90	7.74	0.0163	0.663	1.60
17)	89.92	9.48	0.0163	0.663	1.60
18)	119.92	10.95	0.0163	0.663	1.60
19)	149.92	12.24	0.0163	0.663	1.60
20)	179.92	13.41	0.0163	0.663	1.60
21)	209.90	14.49	0.0163	0.663	1.60
22)	239.92	15.49	0.0163	0.663	1.60
23)	299.90	17.32	0.0163	0.663	1.60
24)	359.92	18.97	0.0163	0.663	1.60
25)	419.90	20.49	0.0168	0.662	1.65
26)	479.90	21.91	0.0168	0.662	1.65
27)	539.90	23.24	0.0168	0.662	1.65
28)	599.90	24.49	0.0163	0.663	1.60
29)	659.92	25.69	0.0168	0.662	1.65
30)	719.90	26.83	0.0168	0.662	1.65
31)	779.93	27.93	0.0168	0.662	1.65
32)	839.92	28.98	0.0163	0.663	1.60
33)	899.93	30.00	0.0168	0.662	1.65
34)	959.88	30.98	0.0168	0.662	1.65
35)	1019.90	31.94	0.0168	0.662	1.65

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW987-ST-3, 2.0'-4.0'	Project No.: 183923
Boring No.: GW987-ST-3	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW987-ST-3	Test Date : 3-15-18	Depth : 2.8'-3.0'
Test No. : GW987-ST-3	Sample Type: Undisturb	

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 4 of 20
Stress increment from 0.50 (t/ft^2) to 1.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.0168	0.662	1.65
37)	1139.90	33.76	0.0168	0.662	1.65
38)	1199.90	34.64	0.0168	0.662	1.65
39)	1259.90	35.50	0.0163	0.663	1.60
40)	1313.87	36.25	0.0163	0.663	1.60

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW987-ST-3, 2.0'-4.0'
Project No.: 183923
Boring No.: GW987-ST-3
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW987-ST-3
Test Date : 3-15-18
Depth : 2.8'-3.0'
Test No. : GW987-ST-3
Sample Type: Undisturb

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 5 of 20
Stress increment from 1.00 (t/ft^2) to 2.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0275	0.644	2.70
2)	0.15	0.39	0.0281	0.644	2.75
3)	0.40	0.63	0.0286	0.643	2.80
4)	0.92	0.96	0.0291	0.642	2.85
5)	1.93	1.39	0.0296	0.641	2.90
6)	2.90	1.70	0.0296	0.641	2.90
7)	3.92	1.98	0.0296	0.641	2.90
8)	4.90	2.21	0.0296	0.641	2.90
9)	5.90	2.43	0.0301	0.640	2.95
10)	6.90	2.63	0.0301	0.640	2.95
11)	7.92	2.81	0.0306	0.639	3.00
12)	8.92	2.99	0.0301	0.640	2.95
13)	9.93	3.15	0.0301	0.640	2.95
14)	14.90	3.86	0.0301	0.640	2.95
15)	29.92	5.47	0.0301	0.640	2.95
16)	59.92	7.74	0.0306	0.639	3.00
17)	89.90	9.48	0.0306	0.639	3.00
18)	119.92	10.95	0.0306	0.639	3.00
19)	149.90	12.24	0.0311	0.638	3.05
20)	179.92	13.41	0.0306	0.639	3.00
21)	209.90	14.49	0.0311	0.638	3.05
22)	239.90	15.49	0.0311	0.638	3.05
23)	299.90	17.32	0.0311	0.638	3.05
24)	359.92	18.97	0.0311	0.638	3.05
25)	419.90	20.49	0.0311	0.638	3.05
26)	479.90	21.91	0.0311	0.638	3.05
27)	539.92	23.24	0.0311	0.638	3.05
28)	599.90	24.49	0.0311	0.638	3.05
29)	659.88	25.69	0.0311	0.638	3.05
30)	719.90	26.83	0.0311	0.638	3.05
31)	779.90	27.93	0.0311	0.638	3.05
32)	839.90	28.98	0.0311	0.638	3.05
33)	899.90	30.00	0.0311	0.638	3.05
34)	959.92	30.98	0.0311	0.638	3.05
35)	1019.90	31.94	0.0316	0.638	3.10

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW987-ST-3, 2.0'-4.0'	Project No.: 183923
Boring No.: GW987-ST-3	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW987-ST-3	Test Date : 3-15-18	Depth : 2.8'-3.0'
Test No. : GW987-ST-3	Sample Type: Undisturb	

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 5 of 20
Stress increment from 1.00 (t/ft^2) to 2.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.88	32.86	0.0311	0.638	3.05
37)	1139.90	33.76	0.0316	0.638	3.10
38)	1199.90	34.64	0.0311	0.638	3.05
39)	1259.90	35.50	0.0311	0.638	3.05
40)	1319.92	36.33	0.0316	0.638	3.10
41)	1379.90	37.15	0.0316	0.638	3.10
42)	1439.90	37.95	0.0316	0.638	3.10
43)	1499.88	38.73	0.0316	0.638	3.10
44)	1559.88	39.50	0.0311	0.638	3.05
45)	1619.90	40.25	0.0311	0.638	3.05
46)	1628.88	40.36	0.0311	0.638	3.05

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW987-ST-3, 2.0'-4.0'
Project No.: 183923
Boring No.: GW987-ST-3
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW987-ST-3
Test Date : 3-15-18
Depth : 2.8'-3.0'
Test No. : GW987-ST-3
Sample Type: Undisturb

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 6 of 20
Stress increment from 2.00 (t/ft^2) to 4.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0495	0.608	4.85
2)	0.13	0.37	0.0505	0.606	4.95
3)	0.37	0.61	0.0510	0.605	5.00
4)	0.87	0.93	0.0520	0.604	5.10
5)	1.87	1.37	0.0525	0.603	5.15
6)	2.87	1.69	0.0530	0.602	5.20
7)	3.87	1.97	0.0530	0.602	5.20
8)	4.87	2.21	0.0530	0.602	5.20
9)	5.87	2.42	0.0536	0.601	5.25
10)	6.88	2.62	0.0541	0.600	5.30
11)	7.88	2.81	0.0536	0.601	5.25
12)	8.88	2.98	0.0536	0.601	5.25
13)	9.87	3.14	0.0536	0.601	5.25
14)	14.87	3.86	0.0541	0.600	5.30
15)	29.87	5.47	0.0541	0.600	5.30
16)	59.90	7.74	0.0551	0.599	5.40
17)	89.88	9.48	0.0541	0.600	5.30
18)	119.87	10.95	0.0551	0.599	5.40
19)	149.87	12.24	0.0546	0.600	5.35
20)	179.87	13.41	0.0551	0.599	5.40
21)	209.92	14.49	0.0546	0.600	5.35
22)	239.87	15.49	0.0551	0.599	5.40
23)	299.88	17.32	0.0551	0.599	5.40
24)	359.87	18.97	0.0551	0.599	5.40
25)	419.87	20.49	0.0556	0.598	5.45
26)	479.87	21.91	0.0556	0.598	5.45
27)	539.87	23.24	0.0556	0.598	5.45
28)	599.87	24.49	0.0556	0.598	5.45
29)	659.87	25.69	0.0556	0.598	5.45
30)	719.88	26.83	0.0556	0.598	5.45
31)	779.87	27.93	0.0556	0.598	5.45
32)	839.87	28.98	0.0561	0.597	5.50
33)	899.87	30.00	0.0556	0.598	5.45
34)	959.87	30.98	0.0561	0.597	5.50
35)	1019.88	31.94	0.0556	0.598	5.45

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW987-ST-3, 2.0'-4.0'
Project No.: 183923
Boring No.: GW987-ST-3
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW987-ST-3
Test Date : 3-15-18
Depth : 2.8'-3.0'
Test No. : GW987-ST-3
Sample Type: Undisturb

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 6 of 20
Stress increment from 2.00 (t/ft^2) to 4.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.85	32.86	0.0561	0.597	5.50
37)	1139.88	33.76	0.0556	0.598	5.45
38)	1199.87	34.64	0.0556	0.598	5.45
39)	1259.85	35.49	0.0561	0.597	5.50
40)	1319.85	36.33	0.0561	0.597	5.50
41)	1325.73	36.41	0.0556	0.598	5.45

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW987-ST-3, 2.0'-4.0'
Project No.: 183923
Boring No.: GW987-ST-3
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW987-ST-3
Test Date : 3-15-18
Depth : 2.8'-3.0'
Test No. : GW987-ST-3
Sample Type: Undisturb

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 7 of 20
Stress increment from 4.00 (t/ft^2) to 2.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0536	0.601	5.25
2)	0.15	0.39	0.0530	0.602	5.20
3)	0.40	0.63	0.0530	0.602	5.20
4)	0.90	0.95	0.0525	0.603	5.15
5)	1.88	1.37	0.0525	0.603	5.15
6)	2.88	1.70	0.0525	0.603	5.15
7)	3.90	1.97	0.0525	0.603	5.15
8)	4.88	2.21	0.0530	0.602	5.20
9)	5.88	2.43	0.0525	0.603	5.15
10)	6.88	2.62	0.0525	0.603	5.15
11)	7.88	2.81	0.0525	0.603	5.15
12)	8.88	2.98	0.0525	0.603	5.15
13)	9.88	3.14	0.0525	0.603	5.15
14)	14.90	3.86	0.0525	0.603	5.15
15)	29.88	5.47	0.0530	0.602	5.20
16)	59.90	7.74	0.0525	0.603	5.15
17)	89.90	9.48	0.0530	0.602	5.20
18)	119.88	10.95	0.0525	0.603	5.15
19)	149.92	12.24	0.0530	0.602	5.20
20)	179.90	13.41	0.0520	0.604	5.10
21)	209.88	14.49	0.0530	0.602	5.20
22)	239.88	15.49	0.0520	0.604	5.10
23)	299.88	17.32	0.0525	0.603	5.15
24)	359.88	18.97	0.0520	0.604	5.10
25)	419.88	20.49	0.0520	0.604	5.10
26)	479.93	21.91	0.0520	0.604	5.10
27)	539.88	23.24	0.0520	0.604	5.10
28)	599.88	24.49	0.0520	0.604	5.10
29)	659.88	25.69	0.0520	0.604	5.10
30)	719.90	26.83	0.0525	0.603	5.15
31)	779.93	27.93	0.0525	0.603	5.15
32)	839.87	28.98	0.0520	0.604	5.10
33)	899.88	30.00	0.0520	0.604	5.10
34)	959.88	30.98	0.0525	0.603	5.15
35)	1019.88	31.94	0.0520	0.604	5.10

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW987-ST-3, 2.0'-4.0'
Project No.: 183923
Boring No.: GW987-ST-3
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW987-ST-3
Test Date : 3-15-18
Depth : 2.8'-3.0'
Test No. : GW987-ST-3
Sample Type: Undisturb

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 7 of 20
Stress increment from 4.00 (t/ft^2) to 2.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.88	32.86	0.0520	0.604	5.10
37)	1139.88	33.76	0.0520	0.604	5.10
38)	1199.87	34.64	0.0520	0.604	5.10
39)	1259.90	35.50	0.0520	0.604	5.10
40)	1319.90	36.33	0.0520	0.604	5.10
41)	1379.88	37.15	0.0525	0.603	5.15
42)	1429.40	37.81	0.0520	0.604	5.10

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW987-ST-3, 2.0'-4.0'
Project No.: 183923
Boring No.: GW987-ST-3
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW987-ST-3
Test Date : 3-15-18
Depth : 2.8'-3.0'
Test No. : GW987-ST-3
Sample Type: Undisturb

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 8 of 20
Stress increment from 2.00 (t/ft^2) to 1.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0500	0.607	4.90
2)	0.15	0.39	0.0495	0.608	4.85
3)	0.38	0.62	0.0495	0.608	4.85
4)	0.92	0.96	0.0495	0.608	4.85
5)	1.88	1.37	0.0490	0.609	4.80
6)	2.88	1.70	0.0495	0.608	4.85
7)	3.88	1.97	0.0490	0.609	4.80
8)	4.88	2.21	0.0490	0.609	4.80
9)	5.88	2.43	0.0490	0.609	4.80
10)	6.88	2.62	0.0490	0.609	4.80
11)	7.90	2.81	0.0490	0.609	4.80
12)	8.88	2.98	0.0490	0.609	4.80
13)	9.90	3.15	0.0490	0.609	4.80
14)	14.88	3.86	0.0495	0.608	4.85
15)	29.92	5.47	0.0485	0.610	4.75
16)	59.90	7.74	0.0490	0.609	4.80
17)	89.90	9.48	0.0485	0.610	4.75
18)	119.90	10.95	0.0490	0.609	4.80
19)	149.90	12.24	0.0485	0.610	4.75
20)	179.90	13.41	0.0490	0.609	4.80
21)	209.88	14.49	0.0485	0.610	4.75
22)	239.90	15.49	0.0490	0.609	4.80
23)	299.88	17.32	0.0490	0.609	4.80
24)	359.88	18.97	0.0490	0.609	4.80
25)	419.88	20.49	0.0485	0.610	4.75
26)	479.90	21.91	0.0490	0.609	4.80
27)	539.88	23.24	0.0490	0.609	4.80
28)	599.90	24.49	0.0485	0.610	4.75
29)	659.90	25.69	0.0485	0.610	4.75
30)	719.90	26.83	0.0485	0.610	4.75
31)	779.90	27.93	0.0490	0.609	4.80
32)	839.90	28.98	0.0485	0.610	4.75
33)	899.88	30.00	0.0490	0.609	4.80
34)	959.88	30.98	0.0490	0.609	4.80
35)	1019.88	31.94	0.0485	0.610	4.75

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW987-ST-3, 2.0'-4.0'	Project No.: 183923
Boring No.: GW987-ST-3	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW987-ST-3	Test Date : 3-15-18	Depth : 2.8'-3.0'
Test No. : GW987-ST-3	Sample Type: Undisturb	

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 8 of 20
Stress increment from 2.00 (t/ft^2) to 1.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.88	32.86	0.0490	0.609	4.80
37)	1139.90	33.76	0.0485	0.610	4.75
38)	1199.88	34.64	0.0485	0.610	4.75
39)	1259.88	35.49	0.0485	0.610	4.75
40)	1319.88	36.33	0.0485	0.610	4.75
41)	1379.88	37.15	0.0485	0.610	4.75
42)	1439.88	37.95	0.0479	0.611	4.70
43)	1441.43	37.97	0.0479	0.611	4.70

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW987-ST-3, 2.0'-4.0'
Project No.: 183923
Boring No.: GW987-ST-3
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW987-ST-3
Test Date : 3-15-18
Depth : 2.8'-3.0'
Test No. : GW987-ST-3
Sample Type: Undisturb

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 9 of 20
Stress increment from 1.00 (t/ft^2) to 0.50 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0464	0.613	4.55
2)	0.15	0.39	0.0459	0.614	4.50
3)	0.40	0.63	0.0459	0.614	4.50
4)	0.90	0.95	0.0464	0.613	4.55
5)	1.92	1.38	0.0459	0.614	4.50
6)	2.92	1.71	0.0459	0.614	4.50
7)	3.90	1.97	0.0454	0.615	4.45
8)	4.92	2.22	0.0454	0.615	4.45
9)	5.92	2.43	0.0454	0.615	4.45
10)	6.90	2.63	0.0454	0.615	4.45
11)	7.90	2.81	0.0454	0.615	4.45
12)	8.90	2.98	0.0459	0.614	4.50
13)	9.90	3.15	0.0454	0.615	4.45
14)	14.93	3.86	0.0459	0.614	4.50
15)	29.92	5.47	0.0449	0.616	4.40
16)	59.90	7.74	0.0449	0.616	4.40
17)	89.90	9.48	0.0449	0.616	4.40
18)	119.92	10.95	0.0444	0.616	4.35
19)	149.92	12.24	0.0449	0.616	4.40
20)	179.88	13.41	0.0449	0.616	4.40
21)	209.90	14.49	0.0449	0.616	4.40
22)	239.90	15.49	0.0444	0.616	4.35
23)	299.90	17.32	0.0449	0.616	4.40
24)	359.90	18.97	0.0444	0.616	4.35
25)	419.88	20.49	0.0444	0.616	4.35
26)	479.88	21.91	0.0444	0.616	4.35
27)	539.92	23.24	0.0444	0.616	4.35
28)	599.90	24.49	0.0444	0.616	4.35
29)	659.90	25.69	0.0444	0.616	4.35
30)	719.90	26.83	0.0444	0.616	4.35
31)	779.93	27.93	0.0444	0.616	4.35
32)	839.92	28.98	0.0444	0.616	4.35
33)	899.92	30.00	0.0444	0.616	4.35
34)	959.90	30.98	0.0444	0.616	4.35
35)	1019.88	31.94	0.0444	0.616	4.35

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW987-ST-3, 2.0'-4.0'	Project No.: 183923
Boring No.: GW987-ST-3	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW987-ST-3	Test Date : 3-15-18	Depth : 2.8'-3.0'
Test No. : GW987-ST-3	Sample Type: Undisturb	

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 9 of 20
Stress increment from 1.00 (t/ft^2) to 0.50 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.88	32.86	0.0444	0.616	4.35
37)	1139.90	33.76	0.0444	0.616	4.35
38)	1199.90	34.64	0.0444	0.616	4.35
39)	1259.92	35.50	0.0444	0.616	4.35
40)	1319.90	36.33	0.0444	0.616	4.35
41)	1379.92	37.15	0.0444	0.616	4.35
42)	1439.90	37.95	0.0444	0.616	4.35
43)	1479.32	38.46	0.0444	0.616	4.35

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW987-ST-3, 2.0'-4.0'
Project No.: 183923
Boring No.: GW987-ST-3
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW987-ST-3
Test Date : 3-15-18
Depth : 2.8'-3.0'
Test No. : GW987-ST-3
Sample Type: Undisturb

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 10 of 20
Stress increment from 0.50 (t/ft^2) to 1.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0459	0.614	4.50
2)	0.15	0.39	0.0459	0.614	4.50
3)	0.40	0.63	0.0459	0.614	4.50
4)	0.90	0.95	0.0459	0.614	4.50
5)	1.93	1.39	0.0459	0.614	4.50
6)	2.88	1.70	0.0459	0.614	4.50
7)	3.90	1.97	0.0459	0.614	4.50
8)	4.90	2.21	0.0459	0.614	4.50
9)	5.88	2.43	0.0459	0.614	4.50
10)	6.92	2.63	0.0459	0.614	4.50
11)	7.90	2.81	0.0459	0.614	4.50
12)	8.90	2.98	0.0459	0.614	4.50
13)	9.90	3.15	0.0464	0.613	4.55
14)	14.88	3.86	0.0459	0.614	4.50
15)	29.88	5.47	0.0464	0.613	4.55
16)	59.90	7.74	0.0459	0.614	4.50
17)	89.90	9.48	0.0469	0.612	4.60
18)	119.90	10.95	0.0464	0.613	4.55
19)	149.88	12.24	0.0469	0.612	4.60
20)	179.88	13.41	0.0459	0.614	4.50
21)	209.90	14.49	0.0469	0.612	4.60
22)	239.90	15.49	0.0464	0.613	4.55
23)	299.90	17.32	0.0464	0.613	4.55
24)	359.93	18.97	0.0464	0.613	4.55
25)	419.90	20.49	0.0464	0.613	4.55
26)	479.88	21.91	0.0459	0.614	4.50
27)	539.90	23.24	0.0464	0.613	4.55
28)	599.90	24.49	0.0464	0.613	4.55
29)	659.90	25.69	0.0464	0.613	4.55
30)	719.88	26.83	0.0464	0.613	4.55
31)	779.90	27.93	0.0464	0.613	4.55
32)	839.90	28.98	0.0464	0.613	4.55
33)	899.88	30.00	0.0464	0.613	4.55
34)	959.90	30.98	0.0464	0.613	4.55
35)	1019.90	31.94	0.0464	0.613	4.55

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW987-ST-3, 2.0'-4.0'	Project No.: 183923
Boring No.: GW987-ST-3	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW987-ST-3	Test Date : 3-15-18	Depth : 2.8'-3.0'
Test No. : GW987-ST-3	Sample Type: Undisturb	

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 10 of 20
Stress increment from 0.50 (t/ft^2) to 1.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.0464	0.613	4.55
37)	1139.88	33.76	0.0464	0.613	4.55
38)	1199.88	34.64	0.0464	0.613	4.55
39)	1259.90	35.50	0.0464	0.613	4.55
40)	1319.88	36.33	0.0464	0.613	4.55
41)	1322.27	36.36	0.0464	0.613	4.55

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW987-ST-3, 2.0'-4.0'
Project No.: 183923
Boring No.: GW987-ST-3
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW987-ST-3
Test Date : 3-15-18
Depth : 2.8'-3.0'
Test No. : GW987-ST-3
Sample Type: Undisturb

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 11 of 20
Stress increment from 1.00 (t/ft^2) to 2.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0490	0.609	4.80
2)	0.15	0.39	0.0490	0.609	4.80
3)	0.38	0.62	0.0495	0.608	4.85
4)	0.88	0.94	0.0495	0.608	4.85
5)	1.90	1.38	0.0495	0.608	4.85
6)	2.88	1.70	0.0495	0.608	4.85
7)	3.90	1.97	0.0495	0.608	4.85
8)	4.90	2.21	0.0495	0.608	4.85
9)	5.90	2.43	0.0495	0.608	4.85
10)	6.88	2.62	0.0495	0.608	4.85
11)	7.88	2.81	0.0495	0.608	4.85
12)	8.88	2.98	0.0500	0.607	4.90
13)	9.88	3.14	0.0500	0.607	4.90
14)	14.88	3.86	0.0495	0.608	4.85
15)	29.88	5.47	0.0500	0.607	4.90
16)	59.90	7.74	0.0500	0.607	4.90
17)	89.90	9.48	0.0500	0.607	4.90
18)	119.88	10.95	0.0500	0.607	4.90
19)	149.88	12.24	0.0500	0.607	4.90
20)	179.90	13.41	0.0500	0.607	4.90
21)	209.88	14.49	0.0500	0.607	4.90
22)	239.88	15.49	0.0500	0.607	4.90
23)	299.88	17.32	0.0500	0.607	4.90
24)	359.90	18.97	0.0500	0.607	4.90
25)	419.88	20.49	0.0500	0.607	4.90
26)	479.90	21.91	0.0500	0.607	4.90
27)	539.88	23.24	0.0500	0.607	4.90
28)	599.88	24.49	0.0500	0.607	4.90
29)	659.88	25.69	0.0500	0.607	4.90
30)	719.88	26.83	0.0505	0.606	4.95
31)	779.90	27.93	0.0500	0.607	4.90
32)	839.88	28.98	0.0500	0.607	4.90
33)	899.88	30.00	0.0500	0.607	4.90
34)	959.90	30.98	0.0500	0.607	4.90
35)	1019.88	31.94	0.0505	0.606	4.95

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW987-ST-3, 2.0'-4.0'	Project No.: 183923
Boring No.: GW987-ST-3	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW987-ST-3	Test Date : 3-15-18	Depth : 2.8'-3.0'
Test No. : GW987-ST-3	Sample Type: Undisturb	

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 11 of 20
Stress increment from 1.00 (t/ft^2) to 2.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.88	32.86	0.0505	0.606	4.95
37)	1139.88	33.76	0.0505	0.606	4.95
38)	1199.88	34.64	0.0500	0.607	4.90
39)	1259.88	35.49	0.0500	0.607	4.90
40)	1319.88	36.33	0.0500	0.607	4.90
41)	1379.88	37.15	0.0505	0.606	4.95
42)	1439.88	37.95	0.0505	0.606	4.95
43)	1499.88	38.73	0.0505	0.606	4.95
44)	1507.35	38.82	0.0500	0.607	4.90

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW987-ST-3, 2.0'-4.0'
Project No.: 183923
Boring No.: GW987-ST-3
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW987-ST-3
Test Date : 3-15-18
Depth : 2.8'-3.0'
Test No. : GW987-ST-3
Sample Type: Undisturb

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 12 of 20
Stress increment from 2.00 (t/ft^2) to 4.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0551	0.599	5.40
2)	0.15	0.39	0.0556	0.598	5.45
3)	0.40	0.63	0.0556	0.598	5.45
4)	0.93	0.97	0.0556	0.598	5.45
5)	1.92	1.38	0.0561	0.597	5.50
6)	2.90	1.70	0.0561	0.597	5.50
7)	3.92	1.98	0.0561	0.597	5.50
8)	4.92	2.22	0.0566	0.596	5.55
9)	5.92	2.43	0.0561	0.597	5.50
10)	6.92	2.63	0.0566	0.596	5.55
11)	7.92	2.81	0.0566	0.596	5.55
12)	8.92	2.99	0.0566	0.596	5.55
13)	9.92	3.15	0.0566	0.596	5.55
14)	14.92	3.86	0.0566	0.596	5.55
15)	29.92	5.47	0.0571	0.595	5.60
16)	59.92	7.74	0.0571	0.595	5.60
17)	89.93	9.48	0.0571	0.595	5.60
18)	119.92	10.95	0.0576	0.595	5.65
19)	149.92	12.24	0.0571	0.595	5.60
20)	179.93	13.41	0.0576	0.595	5.65
21)	209.93	14.49	0.0571	0.595	5.60
22)	239.95	15.49	0.0576	0.595	5.65
23)	299.92	17.32	0.0576	0.595	5.65
24)	359.92	18.97	0.0576	0.595	5.65
25)	419.92	20.49	0.0576	0.595	5.65
26)	479.92	21.91	0.0581	0.594	5.70
27)	539.92	23.24	0.0581	0.594	5.70
28)	599.90	24.49	0.0581	0.594	5.70
29)	659.93	25.69	0.0576	0.595	5.65
30)	719.92	26.83	0.0576	0.595	5.65
31)	779.93	27.93	0.0581	0.594	5.70
32)	839.92	28.98	0.0581	0.594	5.70
33)	899.92	30.00	0.0581	0.594	5.70
34)	959.92	30.98	0.0581	0.594	5.70
35)	1019.93	31.94	0.0581	0.594	5.70

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW987-ST-3, 2.0'-4.0'	Project No.: 183923
Boring No.: GW987-ST-3	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW987-ST-3	Test Date : 3-15-18	Depth : 2.8'-3.0'
Test No. : GW987-ST-3	Sample Type: Undisturb	

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 12 of 20
Stress increment from 2.00 (t/ft^2) to 4.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.93	32.86	0.0581	0.594	5.70
37)	1139.90	33.76	0.0581	0.594	5.70
38)	1199.90	34.64	0.0581	0.594	5.70
39)	1259.93	35.50	0.0581	0.594	5.70
40)	1319.90	36.33	0.0581	0.594	5.70
41)	1379.93	37.15	0.0581	0.594	5.70
42)	1439.90	37.95	0.0581	0.594	5.70
43)	1499.92	38.73	0.0576	0.595	5.65
44)	1504.80	38.79	0.0576	0.595	5.65

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW987-ST-3, 2.0'-4.0'
Project No.: 183923
Boring No.: GW987-ST-3
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW987-ST-3
Test Date : 3-15-18
Depth : 2.8'-3.0'
Test No. : GW987-ST-3
Sample Type: Undisturb

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 13 of 20
Stress increment from 4.00 (t/ft^2) to 8.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0785	0.560	7.70
2)	0.15	0.39	0.0806	0.556	7.90
3)	0.40	0.63	0.0821	0.554	8.05
4)	0.90	0.95	0.0831	0.552	8.15
5)	1.88	1.37	0.0852	0.549	8.35
6)	2.90	1.70	0.0852	0.549	8.35
7)	3.90	1.97	0.0852	0.549	8.35
8)	4.90	2.21	0.0857	0.548	8.40
9)	5.90	2.43	0.0862	0.547	8.45
10)	6.93	2.63	0.0862	0.547	8.45
11)	7.88	2.81	0.0862	0.547	8.45
12)	8.93	2.99	0.0862	0.547	8.45
13)	9.92	3.15	0.0862	0.547	8.45
14)	14.88	3.86	0.0872	0.546	8.55
15)	29.88	5.47	0.0877	0.545	8.60
16)	59.93	7.74	0.0872	0.546	8.55
17)	89.90	9.48	0.0877	0.545	8.60
18)	119.88	10.95	0.0877	0.545	8.60
19)	149.90	12.24	0.0882	0.544	8.65
20)	179.90	13.41	0.0877	0.545	8.60
21)	209.90	14.49	0.0882	0.544	8.65
22)	239.90	15.49	0.0877	0.545	8.60
23)	299.92	17.32	0.0877	0.545	8.60
24)	359.88	18.97	0.0877	0.545	8.60
25)	419.90	20.49	0.0882	0.544	8.65
26)	479.88	21.91	0.0882	0.544	8.65
27)	539.88	23.24	0.0882	0.544	8.65
28)	599.95	24.49	0.0882	0.544	8.65
29)	659.90	25.69	0.0882	0.544	8.65
30)	719.88	26.83	0.0882	0.544	8.65
31)	779.90	27.93	0.0882	0.544	8.65
32)	839.90	28.98	0.0882	0.544	8.65
33)	899.90	30.00	0.0882	0.544	8.65
34)	959.88	30.98	0.0882	0.544	8.65
35)	1019.92	31.94	0.0882	0.544	8.65

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW987-ST-3, 2.0'-4.0'	Project No.: 183923
Boring No.: GW987-ST-3	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW987-ST-3	Test Date : 3-15-18	Depth : 2.8'-3.0'
Test No. : GW987-ST-3	Sample Type: Undisturb	

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 13 of 20
Stress increment from 4.00 (t/ft^2) to 8.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.0882	0.544	8.65
37)	1139.90	33.76	0.0882	0.544	8.65
38)	1199.88	34.64	0.0882	0.544	8.65
39)	1259.88	35.49	0.0882	0.544	8.65
40)	1319.90	36.33	0.0882	0.544	8.65
41)	1379.90	37.15	0.0887	0.543	8.70
42)	1387.95	37.26	0.0887	0.543	8.70

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW987-ST-3, 2.0'-4.0'
Project No.: 183923
Boring No.: GW987-ST-3
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW987-ST-3
Test Date : 3-15-18
Depth : 2.8'-3.0'
Test No. : GW987-ST-3
Sample Type: Undisturb

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 14 of 20
Stress increment from 8.00 (t/ft^2) to 16.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.1061	0.514	10.40
2)	0.15	0.39	0.1076	0.512	10.55
3)	0.38	0.62	0.1091	0.509	10.70
4)	0.90	0.95	0.1117	0.505	10.95
5)	1.92	1.38	0.1142	0.501	11.20
6)	2.90	1.70	0.1153	0.499	11.30
7)	3.90	1.97	0.1158	0.498	11.35
8)	4.92	2.22	0.1158	0.498	11.35
9)	5.88	2.43	0.1163	0.497	11.40
10)	6.88	2.62	0.1168	0.496	11.45
11)	7.90	2.81	0.1168	0.496	11.45
12)	8.93	2.99	0.1168	0.496	11.45
13)	9.90	3.15	0.1173	0.496	11.50
14)	14.88	3.86	0.1173	0.496	11.50
15)	29.90	5.47	0.1183	0.494	11.60
16)	59.90	7.74	0.1188	0.493	11.65
17)	89.88	9.48	0.1188	0.493	11.65
18)	119.88	10.95	0.1188	0.493	11.65
19)	149.88	12.24	0.1188	0.493	11.65
20)	179.88	13.41	0.1188	0.493	11.65
21)	209.90	14.49	0.1188	0.493	11.65
22)	239.90	15.49	0.1193	0.492	11.70
23)	299.90	17.32	0.1193	0.492	11.70
24)	359.88	18.97	0.1193	0.492	11.70
25)	419.90	20.49	0.1193	0.492	11.70
26)	479.88	21.91	0.1193	0.492	11.70
27)	539.88	23.24	0.1193	0.492	11.70
28)	599.90	24.49	0.1193	0.492	11.70
29)	659.90	25.69	0.1193	0.492	11.70
30)	719.90	26.83	0.1193	0.492	11.70
31)	779.90	27.93	0.1199	0.491	11.75
32)	839.88	28.98	0.1193	0.492	11.70
33)	899.88	30.00	0.1199	0.491	11.75
34)	959.90	30.98	0.1199	0.491	11.75
35)	1019.90	31.94	0.1199	0.491	11.75

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW987-ST-3, 2.0'-4.0'	Project No.: 183923
Boring No.: GW987-ST-3	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW987-ST-3	Test Date : 3-15-18	Depth : 2.8'-3.0'
Test No. : GW987-ST-3	Sample Type: Undisturb	

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 14 of 20
Stress increment from 8.00 (t/ft^2) to 16.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.88	32.86	0.1199	0.491	11.75
37)	1139.90	33.76	0.1199	0.491	11.75
38)	1199.90	34.64	0.1199	0.491	11.75
39)	1259.88	35.49	0.1199	0.491	11.75
40)	1319.90	36.33	0.1199	0.491	11.75
41)	1379.88	37.15	0.1199	0.491	11.75
42)	1439.90	37.95	0.1199	0.491	11.75
43)	1456.88	38.17	0.1193	0.492	11.70

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW987-ST-3, 2.0'-4.0'
Project No.: 183923
Boring No.: GW987-ST-3
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW987-ST-3
Test Date : 3-15-18
Depth : 2.8'-3.0'
Test No. : GW987-ST-3
Sample Type: Undisturb

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 15 of 20
Stress increment from 16.00 (t/ft^2) to 32.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.1346	0.467	13.20
2)	0.15	0.39	0.1367	0.464	13.40
3)	0.38	0.62	0.1397	0.458	13.70
4)	0.90	0.95	0.1423	0.454	13.95
5)	1.90	1.38	0.1448	0.450	14.20
6)	2.90	1.70	0.1464	0.447	14.35
7)	3.90	1.97	0.1469	0.447	14.40
8)	4.90	2.21	0.1474	0.446	14.45
9)	5.92	2.43	0.1479	0.445	14.50
10)	6.90	2.63	0.1479	0.445	14.50
11)	7.92	2.81	0.1484	0.444	14.55
12)	8.92	2.99	0.1484	0.444	14.55
13)	9.93	3.15	0.1484	0.444	14.55
14)	14.90	3.86	0.1494	0.442	14.65
15)	29.90	5.47	0.1499	0.442	14.70
16)	59.92	7.74	0.1499	0.442	14.70
17)	89.92	9.48	0.1505	0.441	14.75
18)	119.92	10.95	0.1505	0.441	14.75
19)	149.90	12.24	0.1510	0.440	14.80
20)	179.90	13.41	0.1505	0.441	14.75
21)	209.90	14.49	0.1510	0.440	14.80
22)	239.90	15.49	0.1510	0.440	14.80
23)	299.92	17.32	0.1510	0.440	14.80
24)	359.92	18.97	0.1510	0.440	14.80
25)	419.90	20.49	0.1510	0.440	14.80
26)	479.90	21.91	0.1510	0.440	14.80
27)	539.88	23.24	0.1510	0.440	14.80
28)	599.88	24.49	0.1510	0.440	14.80
29)	659.90	25.69	0.1510	0.440	14.80
30)	719.92	26.83	0.1510	0.440	14.80
31)	779.90	27.93	0.1515	0.439	14.85
32)	839.88	28.98	0.1515	0.439	14.85
33)	899.90	30.00	0.1515	0.439	14.85
34)	959.90	30.98	0.1515	0.439	14.85
35)	1019.88	31.94	0.1515	0.439	14.85

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW987-ST-3, 2.0'-4.0'	Project No.: 183923
Boring No.: GW987-ST-3	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW987-ST-3	Test Date : 3-15-18	Depth : 2.8'-3.0'
Test No. : GW987-ST-3	Sample Type: Undisturb	

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 15 of 20
Stress increment from 16.00 (t/ft^2) to 32.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.1515	0.439	14.85
37)	1139.90	33.76	0.1515	0.439	14.85
38)	1199.90	34.64	0.1515	0.439	14.85
39)	1259.90	35.50	0.1520	0.438	14.90
40)	1319.90	36.33	0.1515	0.439	14.85
41)	1379.90	37.15	0.1515	0.439	14.85
42)	1438.68	37.93	0.1515	0.439	14.85

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW987-ST-3, 2.0'-4.0'	Project No.: 183923
Boring No.: GW987-ST-3	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW987-ST-3	Test Date : 3-15-18	Depth : 2.8'-3.0'
Test No. : GW987-ST-3	Sample Type: Undisturb	

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 16 of 20
Stress increment from 32.00 (t/ft^2) to 16.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.1469	0.447	14.40
2)	0.13	0.37	0.1469	0.447	14.40
3)	0.38	0.62	0.1469	0.447	14.40
4)	0.90	0.95	0.1469	0.447	14.40
5)	1.92	1.38	0.1469	0.447	14.40
6)	2.92	1.71	0.1469	0.447	14.40
7)	3.92	1.98	0.1464	0.447	14.35
8)	4.90	2.21	0.1464	0.447	14.35
9)	5.90	2.43	0.1469	0.447	14.40
10)	6.90	2.63	0.1464	0.447	14.35
11)	7.90	2.81	0.1464	0.447	14.35
12)	8.90	2.98	0.1464	0.447	14.35
13)	9.90	3.15	0.1464	0.447	14.35
14)	14.90	3.86	0.1464	0.447	14.35
15)	29.92	5.47	0.1464	0.447	14.35
16)	59.93	7.74	0.1459	0.448	14.30
17)	89.90	9.48	0.1464	0.447	14.35
18)	119.88	10.95	0.1459	0.448	14.30
19)	149.90	12.24	0.1464	0.447	14.35
20)	179.90	13.41	0.1459	0.448	14.30
21)	209.90	14.49	0.1464	0.447	14.35
22)	239.92	15.49	0.1459	0.448	14.30
23)	299.88	17.32	0.1459	0.448	14.30
24)	359.90	18.97	0.1459	0.448	14.30
25)	419.90	20.49	0.1459	0.448	14.30
26)	479.88	21.91	0.1459	0.448	14.30
27)	539.90	23.24	0.1459	0.448	14.30
28)	599.92	24.49	0.1459	0.448	14.30
29)	659.90	25.69	0.1459	0.448	14.30
30)	719.88	26.83	0.1459	0.448	14.30
31)	779.88	27.93	0.1459	0.448	14.30
32)	839.90	28.98	0.1459	0.448	14.30
33)	899.95	30.00	0.1459	0.448	14.30
34)	959.88	30.98	0.1459	0.448	14.30
35)	1019.90	31.94	0.1459	0.448	14.30

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW987-ST-3, 2.0'-4.0'	Project No.: 183923
Boring No.: GW987-ST-3	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW987-ST-3	Test Date : 3-15-18	Depth : 2.8'-3.0'
Test No. : GW987-ST-3	Sample Type: Undisturb	

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 16 of 20
Stress increment from 32.00 (t/ft^2) to 16.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.1459	0.448	14.30
37)	1139.88	33.76	0.1459	0.448	14.30
38)	1199.90	34.64	0.1454	0.449	14.25
39)	1259.88	35.49	0.1459	0.448	14.30
40)	1319.90	36.33	0.1454	0.449	14.25
41)	1379.88	37.15	0.1454	0.449	14.25
42)	1436.52	37.90	0.1459	0.448	14.30

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW987-ST-3, 2.0'-4.0'	Project No.: 183923
Boring No.: GW987-ST-3	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW987-ST-3	Test Date : 3-15-18	Depth : 2.8'-3.0'
Test No. : GW987-ST-3	Sample Type: Undisturb	

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 17 of 20
Stress increment from 16.00 (t/ft^2) to 8.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.1413	0.456	13.85
2)	0.17	0.41	0.1413	0.456	13.85
3)	0.42	0.65	0.1408	0.457	13.80
4)	0.90	0.95	0.1403	0.458	13.75
5)	1.92	1.38	0.1403	0.458	13.75
6)	2.92	1.71	0.1403	0.458	13.75
7)	3.92	1.98	0.1403	0.458	13.75
8)	4.90	2.21	0.1403	0.458	13.75
9)	5.92	2.43	0.1403	0.458	13.75
10)	6.92	2.63	0.1403	0.458	13.75
11)	7.92	2.81	0.1397	0.458	13.70
12)	8.90	2.98	0.1403	0.458	13.75
13)	9.92	3.15	0.1397	0.458	13.70
14)	14.93	3.86	0.1397	0.458	13.70
15)	29.92	5.47	0.1403	0.458	13.75
16)	59.92	7.74	0.1397	0.458	13.70
17)	89.90	9.48	0.1397	0.458	13.70
18)	119.92	10.95	0.1392	0.459	13.65
19)	149.93	12.24	0.1397	0.458	13.70
20)	179.92	13.41	0.1392	0.459	13.65
21)	209.90	14.49	0.1397	0.458	13.70
22)	239.92	15.49	0.1392	0.459	13.65
23)	299.92	17.32	0.1392	0.459	13.65
24)	359.92	18.97	0.1392	0.459	13.65
25)	419.92	20.49	0.1392	0.459	13.65
26)	479.92	21.91	0.1392	0.459	13.65
27)	539.93	23.24	0.1392	0.459	13.65
28)	599.90	24.49	0.1392	0.459	13.65
29)	659.90	25.69	0.1392	0.459	13.65
30)	719.92	26.83	0.1392	0.459	13.65
31)	779.90	27.93	0.1392	0.459	13.65
32)	839.92	28.98	0.1392	0.459	13.65
33)	899.92	30.00	0.1392	0.459	13.65
34)	959.90	30.98	0.1387	0.460	13.60
35)	1019.90	31.94	0.1392	0.459	13.65

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW987-ST-3, 2.0'-4.0'	Project No.: 183923
Boring No.: GW987-ST-3	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW987-ST-3	Test Date : 3-15-18	Depth : 2.8'-3.0'
Test No. : GW987-ST-3	Sample Type: Undisturb	

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 17 of 20
Stress increment from 16.00 (t/ft^2) to 8.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.1387	0.460	13.60
37)	1139.90	33.76	0.1392	0.459	13.65
38)	1199.92	34.64	0.1392	0.459	13.65
39)	1259.90	35.50	0.1387	0.460	13.60
40)	1319.90	36.33	0.1387	0.460	13.60
41)	1379.90	37.15	0.1392	0.459	13.65
42)	1439.92	37.95	0.1387	0.460	13.60
43)	1499.90	38.73	0.1392	0.459	13.65
44)	1538.13	39.22	0.1387	0.460	13.60

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW987-ST-3, 2.0'-4.0'
Project No.: 183923
Boring No.: GW987-ST-3
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW987-ST-3
Test Date : 3-15-18
Depth : 2.8'-3.0'
Test No. : GW987-ST-3
Sample Type: Undisturb

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 18 of 20
Stress increment from 8.00 (t/ft^2) to 4.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.1352	0.466	13.25
2)	0.15	0.39	0.1346	0.467	13.20
3)	0.40	0.63	0.1346	0.467	13.20
4)	0.93	0.97	0.1341	0.468	13.15
5)	1.90	1.38	0.1341	0.468	13.15
6)	2.90	1.70	0.1336	0.469	13.10
7)	3.90	1.97	0.1336	0.469	13.10
8)	4.90	2.21	0.1336	0.469	13.10
9)	5.92	2.43	0.1336	0.469	13.10
10)	6.92	2.63	0.1336	0.469	13.10
11)	7.92	2.81	0.1336	0.469	13.10
12)	8.92	2.99	0.1336	0.469	13.10
13)	9.90	3.15	0.1331	0.469	13.05
14)	14.92	3.86	0.1331	0.469	13.05
15)	29.92	5.47	0.1326	0.470	13.00
16)	59.90	7.74	0.1326	0.470	13.00
17)	89.92	9.48	0.1326	0.470	13.00
18)	119.92	10.95	0.1326	0.470	13.00
19)	149.90	12.24	0.1326	0.470	13.00
20)	179.90	13.41	0.1326	0.470	13.00
21)	209.92	14.49	0.1326	0.470	13.00
22)	239.90	15.49	0.1326	0.470	13.00
23)	299.92	17.32	0.1326	0.470	13.00
24)	359.90	18.97	0.1321	0.471	12.95
25)	419.92	20.49	0.1321	0.471	12.95
26)	479.90	21.91	0.1321	0.471	12.95
27)	539.90	23.24	0.1321	0.471	12.95
28)	599.92	24.49	0.1321	0.471	12.95
29)	659.90	25.69	0.1321	0.471	12.95
30)	719.92	26.83	0.1321	0.471	12.95
31)	779.90	27.93	0.1321	0.471	12.95
32)	839.90	28.98	0.1316	0.472	12.90
33)	899.90	30.00	0.1321	0.471	12.95
34)	959.90	30.98	0.1321	0.471	12.95
35)	1019.92	31.94	0.1321	0.471	12.95

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW987-ST-3, 2.0'-4.0'	Project No.: 183923
Boring No.: GW987-ST-3	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW987-ST-3	Test Date : 3-15-18	Depth : 2.8'-3.0'
Test No. : GW987-ST-3	Sample Type: Undisturb	

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 18 of 20
Stress increment from 8.00 (t/ft^2) to 4.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.1326	0.470	13.00
37)	1139.90	33.76	0.1326	0.470	13.00
38)	1199.90	34.64	0.1321	0.471	12.95
39)	1259.90	35.50	0.1321	0.471	12.95
40)	1319.92	36.33	0.1321	0.471	12.95
41)	1379.90	37.15	0.1326	0.470	13.00
42)	1439.90	37.95	0.1326	0.470	13.00
43)	1499.90	38.73	0.1316	0.472	12.90
44)	1559.90	39.50	0.1321	0.471	12.95
45)	1619.92	40.25	0.1321	0.471	12.95
46)	1679.90	40.99	0.1316	0.472	12.90
47)	1739.90	41.71	0.1321	0.471	12.95
48)	1799.90	42.43	0.1321	0.471	12.95
49)	1859.90	43.13	0.1326	0.470	13.00
50)	1919.90	43.82	0.1321	0.471	12.95
51)	1979.90	44.50	0.1321	0.471	12.95
52)	2039.90	45.17	0.1321	0.471	12.95
53)	2099.90	45.82	0.1326	0.470	13.00
54)	2159.90	46.47	0.1321	0.471	12.95
55)	2219.90	47.12	0.1321	0.471	12.95
56)	2279.90	47.75	0.1326	0.470	13.00
57)	2339.90	48.37	0.1321	0.471	12.95
58)	2399.90	48.99	0.1321	0.471	12.95
59)	2459.90	49.60	0.1321	0.471	12.95
60)	2519.88	50.20	0.1321	0.471	12.95
61)	2579.90	50.79	0.1316	0.472	12.90
62)	2639.88	51.38	0.1316	0.472	12.90
63)	2699.90	51.96	0.1316	0.472	12.90
64)	2759.90	52.53	0.1321	0.471	12.95
65)	2818.38	53.09	0.1316	0.472	12.90

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW987-ST-3, 2.0'-4.0'	Project No.: 183923
Boring No.: GW987-ST-3	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW987-ST-3	Test Date : 3-15-18	Depth : 2.8'-3.0'
Test No. : GW987-ST-3	Sample Type: Undisturb	

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 19 of 20
Stress increment from 4.00 (t/ft^2) to 2.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.1290	0.476	12.65
2)	0.17	0.41	0.1285	0.477	12.60
3)	0.40	0.63	0.1285	0.477	12.60
4)	0.88	0.94	0.1285	0.477	12.60
5)	1.88	1.37	0.1280	0.478	12.55
6)	2.90	1.70	0.1280	0.478	12.55
7)	3.92	1.98	0.1275	0.479	12.50
8)	4.90	2.21	0.1275	0.479	12.50
9)	5.88	2.43	0.1275	0.479	12.50
10)	6.88	2.62	0.1270	0.480	12.45
11)	7.90	2.81	0.1275	0.479	12.50
12)	8.90	2.98	0.1270	0.480	12.45
13)	9.90	3.15	0.1270	0.480	12.45
14)	14.90	3.86	0.1270	0.480	12.45
15)	29.88	5.47	0.1265	0.480	12.40
16)	59.90	7.74	0.1265	0.480	12.40
17)	89.90	9.48	0.1260	0.481	12.35
18)	119.90	10.95	0.1260	0.481	12.35
19)	149.93	12.24	0.1260	0.481	12.35
20)	179.88	13.41	0.1260	0.481	12.35
21)	209.90	14.49	0.1260	0.481	12.35
22)	239.92	15.49	0.1260	0.481	12.35
23)	299.90	17.32	0.1260	0.481	12.35
24)	359.88	18.97	0.1255	0.482	12.30
25)	419.90	20.49	0.1255	0.482	12.30
26)	479.88	21.91	0.1255	0.482	12.30
27)	539.95	23.24	0.1255	0.482	12.30
28)	599.88	24.49	0.1255	0.482	12.30
29)	659.90	25.69	0.1255	0.482	12.30
30)	719.88	26.83	0.1255	0.482	12.30
31)	779.90	27.93	0.1255	0.482	12.30
32)	839.88	28.98	0.1255	0.482	12.30
33)	899.90	30.00	0.1255	0.482	12.30
34)	959.88	30.98	0.1255	0.482	12.30
35)	1019.90	31.94	0.1255	0.482	12.30

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW987-ST-3, 2.0'-4.0'	Project No.: 183923
Boring No.: GW987-ST-3	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW987-ST-3	Test Date : 3-15-18	Depth : 2.8'-3.0'
Test No. : GW987-ST-3	Sample Type: Undisturb	

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 19 of 20
Stress increment from 4.00 (t/ft^2) to 2.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.1255	0.482	12.30
37)	1139.92	33.76	0.1255	0.482	12.30
38)	1199.88	34.64	0.1255	0.482	12.30
39)	1259.90	35.50	0.1255	0.482	12.30
40)	1319.88	36.33	0.1250	0.483	12.25
41)	1379.90	37.15	0.1255	0.482	12.30
42)	1410.45	37.56	0.1255	0.482	12.30

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW987-ST-3, 2.0'-4.0'	Project No.: 183923
Boring No.: GW987-ST-3	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW987-ST-3	Test Date : 3-15-18	Depth : 2.8'-3.0'
Test No. : GW987-ST-3	Sample Type: Undisturb	

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 20 of 20
Stress increment from 2.00 (t/ft^2) to 1.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.1234	0.486	12.10
2)	0.17	0.41	0.1229	0.486	12.05
3)	0.42	0.65	0.1229	0.486	12.05
4)	0.92	0.96	0.1224	0.487	12.00
5)	1.90	1.38	0.1224	0.487	12.00
6)	2.92	1.71	0.1224	0.487	12.00
7)	3.92	1.98	0.1219	0.488	11.95
8)	4.92	2.22	0.1219	0.488	11.95
9)	5.90	2.43	0.1214	0.489	11.90
10)	6.90	2.63	0.1214	0.489	11.90
11)	7.92	2.81	0.1214	0.489	11.90
12)	8.92	2.99	0.1219	0.488	11.95
13)	9.92	3.15	0.1214	0.489	11.90
14)	14.92	3.86	0.1214	0.489	11.90
15)	29.92	5.47	0.1209	0.490	11.85
16)	59.92	7.74	0.1204	0.491	11.80
17)	89.93	9.48	0.1204	0.491	11.80
18)	119.90	10.95	0.1199	0.491	11.75
19)	149.90	12.24	0.1204	0.491	11.80
20)	179.90	13.41	0.1193	0.492	11.70
21)	209.93	14.49	0.1199	0.491	11.75
22)	239.95	15.49	0.1199	0.491	11.75
23)	299.93	17.32	0.1199	0.491	11.75
24)	359.92	18.97	0.1199	0.491	11.75
25)	419.92	20.49	0.1199	0.491	11.75
26)	479.92	21.91	0.1193	0.492	11.70
27)	539.92	23.24	0.1193	0.492	11.70
28)	599.92	24.49	0.1193	0.492	11.70
29)	659.92	25.69	0.1193	0.492	11.70
30)	719.90	26.83	0.1193	0.492	11.70
31)	779.95	27.93	0.1193	0.492	11.70
32)	839.90	28.98	0.1193	0.492	11.70
33)	899.92	30.00	0.1193	0.492	11.70
34)	959.90	30.98	0.1193	0.492	11.70
35)	1019.93	31.94	0.1193	0.492	11.70

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW987-ST-3, 2.0'-4.0'	Project No.: 183923
Boring No.: GW987-ST-3	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW987-ST-3	Test Date : 3-15-18	Depth : 2.8'-3.0'
Test No. : GW987-ST-3	Sample Type: Undisturb	

Soil Description : red/brown silty clay and sand (visual description)
Remarks : Use: Foundation berm/fill

Load Increment : 20 of 20
Stress increment from 2.00 (t/ft^2) to 1.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.92	32.86	0.1193	0.492	11.70
37)	1139.92	33.76	0.1193	0.492	11.70
38)	1199.92	34.64	0.1193	0.492	11.70
39)	1259.92	35.50	0.1193	0.492	11.70
40)	1319.90	36.33	0.1193	0.492	11.70
41)	1379.93	37.15	0.1193	0.492	11.70
42)	1417.50	37.65	0.1183	0.494	11.60

BOWSER-MORNER, INC.

Delivery Address: 4518 Taylorsville Road • Dayton, Ohio 45424 **Mailing Address**: P. O. Box 51 • Dayton, Ohio 45401

AASHTO/ISO 17025 Accredited • USACE Validated

LABORATORY REPORT

Report To: CTI & Associates, Inc.
Attn: Michael Partenio
28001 Cabot Drive, Ste. 250
Novi, MI 48377

Report Date: April 17, 2018
Job No.: 183923
Report No.: 430213
No. of Pages: 2

Report On: Laboratory Analysis of One Shelby Tube Sample
Project: EMDF Characterization – Project No. 1188070011
Sample ID: GW979 – ST-1, 3.0'-5.0' – Sample Date: 2/21/18

On March 5, 2018, one Shelby tube sample was submitted for determination of atterberg limits from the above referenced project. Testing was performed as specified by the client and in accordance with the following procedures:

ASTM D 1140, "Determining the Amount of Material Finer than 75-μm (No. 200) Sieve in Soils by Washing".

ASTM D 4318, "Liquid Limit, Plastic Limit, and Plasticity Index of Soils".

Results are presented in the following table and detailed on the attached data sheet.

Test Parameter	Results
Liquid Limit:	**48**
Plastic Limit:	**29**
Plasticity Index:	**19**
Percent Finer than No. 200 Sieve:	**73.3**

Should you have any questions, or if we may be of further service, please contact me at (937) 236-8805, extension 322.

Respectfully submitted,


BOWSER-MORNER, INC.

Karl A. Fletcher, Manager
Construction Materials and
Geotechnical Laboratories

KAF/blc
430213
1-File
1-mpartenio@cticompanies.com
1-kfoye@cticompanies.com

All Reports Remain The Confidential Property Of BOWSER-MORNER And No Publication Or Distribution Of Reports May Be Made Without Our Express Written Consent, Except As Authorized By Contract. Results Contained In This Report Are Reflective Only of The Items Calibrated or Tested. Unless Otherwise Agreed, Samples Or Specimens Will Be Discarded Or Returned At Bowser-Morner's Discretion. AASHTO/ISO 17025 Accreditation applies only to the parameters included in BOWSER-MORNER'S current scope of accreditation. Go to www.bowser-morner.com/accreditations for review.

LIQUID AND PLASTIC LIMITS TEST REPORT



	MATERIAL DESCRIPTION	LL	PL	PI	%<#40	%<#200	USCS
●	GW979-ST-1	48	29	19			

Project No. 183923 **Client:** CTI and Associates, Inc.

Project: EMDF Characterization

● **Source of Sample:** GW-979 **Depth:** 3.0' - 5.0' **Sample Number:** ST-1

Remarks:

BOWSER-MORNER, INC.

Dayton, Ohio

BOWSER-MORNER, INC.

Delivery Address: 4518 Taylorsville Road • Dayton, Ohio 45424 **Mailing Address**: P. O. Box 51 • Dayton, Ohio 45401

AASHTO/ISO 17025 Accredited • USACE Validated ACIL INDEPENDENCE

LABORATORY REPORT

Report To: CTI & Associates, Inc.
Attn: Michael Partenio
28001 Cabot Drive, Ste. 250
Novi, MI 48377

Report Date: May 3, 2018
Job No.: 183923
Report No.: 430246
No. of Pages: 2

Report On: Laboratory Analysis of One Shelby Tube Sample
Project: EMDF Characterization – Project No. 1188070011
Sample ID: GW993 – ST-1, 3.0'-5.0' – Sample Date: 2/22/18

On March 5, 2018, one Shelby tube sample was submitted for selected laboratory analysis from the above referenced project. Testing was performed as specified by the client and in accordance with the ASTM D 4318, "Liquid Limit, Plastic Limit, and Plasticity Index of Soils".

Results are presented in the following table and detailed on the attached data sheet.

Test Parameter	Results
Liquid Limit:	**35**
Plastic Limit:	**23**
Plasticity Index:	**12**

Should you have any questions, or if we may be of further service, please contact me at (937) 236-8805, extension 322.

Respectfully submitted,


BOWSER-MORNER, INC.

Karl A. Fletcher, Manager
Construction Materials and
Geotechnical Laboratories

KAF/blc
430246
1-File
1-mpartenio@cticompanies.com
1-kfoye@cticompanies.com

All Reports Remain The Confidential Property Of BOWSER-MORNER And No Publication Or Distribution Of Reports May Be Made Without Our Express Written Consent, Except As Authorized By Contract. Results Contained In This Report Are Reflective Only of The Items Calibrated or Tested. Unless Otherwise Agreed, Samples Or Specimens Will Be Discarded Or Returned At Bowser-Morner's Discretion. AASHTO/ISO 17025 Accreditation applies only to the parameters included in BOWSER-MORNER'S current scope of accreditation. Go to www.bowser-morner.com/accreditations for review.

LIQUID AND PLASTIC LIMITS TEST REPORT



	MATERIAL DESCRIPTION	LL	PL	PI	%<#40	%<#200	USCS
●	brown clay, little gravel (visual description)	35	23	12			

Project No. 183923 **Client:** CTI and Associates, Inc.

Project: EMDF Characterization

● **Source of Sample:** GW-993 **Depth:** 3.0' - 5.0' **Sample Number:** ST-1

Remarks:

● As Received
Moisture Content: 25.4%

BOWSER-MORNER, INC.

Dayton, Ohio F-136

BOWSER-MORNER, INC.

Delivery Address: 4518 Taylorsville Road • Dayton, Ohio 45424 **Mailing Address**: P. O. Box 51 • Dayton, Ohio 45401

AASHTO/ISO 17025 Accredited • USACE Validated

LABORATORY REPORT

Report To: CTI & Associates, Inc.
Attn: Michael Partenio
28001 Cabot Drive, Ste. 250
Novi, MI 48377

Report Date: May 22, 2018
Job No.: 183923
Report No.: 430273
No. of Pages: 2

Report On: Laboratory Analysis of One Shelby Tube Sample
Project: EMDF Characterization – Project No. 1188070011
Sample ID: GW979 – ST-2, 7.5'-8.75' – Sample Date: 2/21/18
Depth of Test Specimen: 8.2'-8.5'

On March 5, 2018, one Shelby tube sample was submitted for laboratory determination of permeability. Testing was performed as specified by the client and in accordance with ASTM D 5084, "Measurement of Hydraulic Conductivity of Saturated Porous Materials Using a Flexible Wall Permeameter".

Results are presented in the following table.

Test Parameter	Results
Average Permeability, cm/sec:	**1.7×10^{-7}**

Should you have any questions, or if we may be of further service, please contact me at (937) 236-8805, extension 322.

Respectfully submitted,

BOWSER-MORNER, INC.

Karl A. Fletcher, Manager
Construction Materials and
Geotechnical Laboratories

KAF/blc
430273
1-File
1-mpartenio@cticompanies.com
1-kfoye@cticompanies.com

All Reports Remain The Confidential Property Of BOWSER-MORNER And No Publication Or Distribution Of Reports May Be Made Without Our Express Written Consent, Except As Authorized By Contract. Results Contained In This Report Are Reflective Only of The Items Calibrated or Tested. Unless Otherwise Agreed, Samples Or Specimens Will Be Discarded Or Returned At Bowser-Morner's Discretion. AASHTO/ISO 17025 Accreditation applies only to the parameters included in BOWSER-MORNER'S current scope of accreditation. Go to www.bowser-morner.com/accreditations for reviews.

FALLING HEAD PERMEABILITY TEST

ASTM D 5084, Measurement of Hydraulic Conductivity

UNDISTURBED

Client:	**CTI and Associates, Inc.**
Project:	**EMDF Characterization**
BMI Work Order Number:	183923
Sample Identification:	GW979 ST-2, 7.5' - 8.75'
Depth, ft:	8.2' - 8.5'
Visual Description:	brown silty clay

SPECIMEN DATA:

Dimension, inches	
Height:	2.99
Diameter:	2.883
Mass, lbs:	1.428
Moisture Content,%	
Initial:	21.8
Final:	24.4
Wet Unit Weight, pcf	
Initial:	126.4
Final:	129.1
Initial Dry Unit Weight, pcf:	103.8
Back Pressure Saturation, psi	
Back Pressure, Exit:	60
Back Pressure, Enter:	63
Lateral Pressure:	67

Permeability (k), cm/sec: **1.7×10^{-7}**

BOWSER-MORNER, INC.

Delivery Address: 4518 Taylorsville Road • Dayton, Ohio 45424 **Mailing Address**: P. O. Box 51 • Dayton, Ohio 45401

AASHTO/ISO 17025 Accredited • USACE Validated

LABORATORY REPORT

Report To: CTI & Associates, Inc.
Attn: Michael Partenio
28001 Cabot Drive, Ste. 250
Novi, MI 48377

Report Date: May 7, 2018
Job No.: 183923
Report No.: 430253
No. of Pages: 4

Report On: Laboratory Analysis of One Shelby Tube Sample
Project: EMDF Characterization – Project No. 1188070011
Sample ID: GW989-ST-4, 14.5'-16.5' – Sample Date: 2/27/18

On March 5, 2018, one Shelby tube sample was submitted for selected laboratory analysis from the above referenced project. Testing was performed as specified by the client and in accordance with the following procedures:

ASTM D 2216, "Laboratory Determination of Water (Moisture) Content of Soil and Rock".

ASTM D 6913, "Particle-Size Distribution (Gradation) of Soils Using Sieve Analysis".

Results are summarized in Table I and detailed on the attached data sheets.

Should you have any questions, or if we may be of further service, please contact me at (937) 236-8805, extension 322.

Respectfully submitted,

BOWSER-MORNER, INC.

Karl A. Fletcher, Manager
Construction Materials and
Geotechnical Laboratories

KAF/blc
430253
1-File
1-mpartenio@cticompanies.com
1-kfoye@cticompanies.com

All Reports Remain The Confidential Property Of BOWSER-MORNER And No Publication Or Distribution Of Reports May Be Made Without Our Express Written Consent, Except As Authorized By Contract. Results Contained In This Report Are Reflective Only of The Items Calibrated or Tested. Unless Otherwise Agreed, Samples Or Specimens Will Be Discarded Or Returned At Bowser-Morner's Discretion. AASHTO/ISO 17025 Accreditation applies only to the parameters included in BOWSER-MORNER'S current scope of accreditation. Go to www.bowser-morner.com/accreditations for reviews.

Report To: CTI & Associates, Inc.
Project: EMDF Characterization
Sample No.: GW989-ST-4, 14.5'-16.6'

BMI Job No.: 183923
BMI Report No.: 430253
Date Sampled: 02/27/18


Sample ID: GW989-ST-4, 14.5'-16.6'

Description: Saprolite

TABLE I
Summary of Results

Sieve Size	Percent Passing
1/2"	**100.0**
3/8"	**99.1**
No. 4	**77.0**
No. 10	**43.4**
No. 20	**27.6**
No. 40	**22.1**
No. 60	**19.6**
No. 100	**17.8**
No. 200	**15.6**
Gravel, %:	**23.0**
Sand, %:	**61.4**
Fines, %:	**15.6**
As Received Moisture Content, %:	**14.9**

GRAIN SIZE DISTRIBUTION REPORT



	% +3"	% Gravel		% Sand			% Fines	
		Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
○	0.0	0.0	23.0	33.6	21.3	6.5	15.6	

	LL	PL	D_{85}	D_{60}	D_{50}	D_{30}	D_{15}	D_{10}	C_c	C_u
○			5.7655	3.1778	2.4480	1.0368				

Material Description	USCS	AASHTO
○ Saprolite		

Project No. 183923 **Client:** CTI and Associates, Inc.

Project: EMDF Characterization

○ **Source:** GW-989 **Depth:** 14.5' - 16.5' **Sample No.:** ST-4

Remarks:

○ As Received

Moisture Content: 14.9%

BOWSER-MORNER, INC.

Dayton, Ohio

GRAIN SIZE DISTRIBUTION TEST DATA

5/7/2018

Client: CTI and Associates, Inc.
Project: EMDF Characterization
Project Number: 183923
Location: GW-989
Depth: 14.5' - 16.5'
Sample Number: ST-4
Material Description: Saprolite
Testing Remarks: As Received
Moisture Content: 14.9%

Sieve Test Data

Dry Sample and Tare (grams)	Tare (grams)	Cumulative Pan Tare Weight (grams)	Sieve Opening Size	Cumulative Weight Retained (grams)	Percent Finer	Percent Retained
932.90	228.22	0.00	0.50	0.00	100.0	0.0
			0.375	6.60	99.1	0.9
			#4	162.34	77.0	23.0
			#10	398.89	43.4	56.6
			#20	510.01	27.6	72.4
			#40	549.08	22.1	77.9
			#60	566.57	19.6	80.4
			#100	579.07	17.8	82.2
			#200	594.40	15.6	84.4

Fractional Components

Cobbles	Gravel			Sand				Fines		
	Coarse	Fine	Total	Coarse	Medium	Fine	Total	Silt	Clay	Total
0.0	0.0	23.0	23.0	33.6	21.3	6.5	61.4			15.6

D_5	D_{10}	D_{15}	D_{20}	D_{30}	D_{40}	D_{50}	D_{60}	D_{80}	D_{85}	D_{90}	D_{95}
			0.2765	1.0368	1.7678	2.4480	3.1778	5.1031	5.7655	6.5876	7.7351

Fineness Modulus
3.81

BOWSER-MORNER, INC.

Delivery Address: 4518 Taylorsville Road • Dayton, Ohio 45424 **Mailing Address**: P. O. Box 51 • Dayton, Ohio 45401

AASHTO/ISO 17025 Accredited • USACE Validated ACIL INDEPENDENCE

LABORATORY REPORT

Report To: CTI & Associates, Inc.
Attn: Michael Partenio
28001 Cabot Drive, Ste. 250
Novi, MI 48377

Report Date: April 11, 2018
Job No.: 183923
Report No.: 430201
No. of Pages: 1

Report On: Laboratory Analysis of One Shelby Tube Sample
Project: EMDF Characterization – Project No. 1188070011
Sample ID: GW987 – ST-3, 2.0'-4.0' – Sample Date: 2/21/18

On March 5, 2018, one Shelby tube sample was submitted for selected laboratory analysis from the above referenced project. Testing was performed as specified by the client and in accordance with the following procedures:

ASTM D 854, "Specific Gravity of Soils Solids by Water Pycnometer".
ASTM D 2216, "Laboratory Determination of Water (Moisture) Content of Soil and Rock".
ASTM D 7263, "Laboratory Determination of Density (Unit Weight) of Soil Specimens – Method B".

Results are summarized in the following table.

Test Parameter	Results
Depth of Test Specimen:	**2.0'-2.5'**
As Received Moisture Content, %:	**20.7**
Apparent Specific Gravity:	**2.69**
Wet Unit Weight, pcf:	**128.5**
Dry Unit Weight, pcf:	**106.4**
Void Ratio:	**0.5764**
Porosity, %:	**36.6**
Degree of Saturation, %:	**96.5**
Volume of Water, %:	**35.3**
Volume of Solids, %:	**63.4**
Air Filled Voids, %:	**3.5**
Water Filled Voids, %:	**96.5**

Should you have any questions, or if we may be of further service, please contact me at (937) 236-8805, extension 322.

Respectfully submitted,
BOWSER-MORNER, INC.

Karl A. Fletcher, Manager
Construction Materials and
Geotechnical Laboratories

KAF/blc
430201
1-File
1-mpartenio@cticompanies.com
1-kfoye@cticompanies.com

All Reports Remain The Confidential Property Of BOWSER-MORNER And No Publication Or Distribution Of Reports May Be Made Without Our Express Written Consent, Except As Authorized By Contract. Results Contained In This Report Are Reflective Only of The Items Calibrated or Tested. Unless Otherwise Agreed, Samples Or Specimens Will Be Discarded Or Returned At Bowser-Morner's Discretion. AASHTO/ISO 17025 Accreditation applies only to the parameters included in BOWSER-MORNER'S current scope of accreditation. Go to www.bowser-morner.com/accreditations for reviews.

BOWSER-MORNER, INC.

Delivery Address: 4518 Taylorsville Road • Dayton, Ohio 45424 **Mailing Address**: P. O. Box 51 • Dayton, Ohio 45401

AASHTO/ISO 17025 Accredited • USACE Validated

LABORATORY REPORT

Report To: CTI & Associates, Inc.
Attn: Michael Partenio
28001 Cabot Drive, Ste. 250
Novi, MI 48377

Report Date: May 22, 2018
Job No.: 183923
Report No.: 430274
No. of Pages: 2

Report On: Laboratory Analysis of One Shelby Tube Sample
Project: EMDF Characterization – Project No. 1188070011
Sample ID: GW989 – ST-2, 6.5'-8.5' – Sample Date: 2/27/18
Depth of Test Specimen: 7.3'-7.6'

On March 5, 2018, one Shelby tube sample was submitted for laboratory determination of permeability. Testing was performed as specified by the client and in accordance with ASTM D 5084, "Measurement of Hydraulic Conductivity of Saturated Porous Materials Using a Flexible Wall Permeameter".

Results are presented in the following table.

Test Parameter	Results
Average Permeability, cm/sec:	**6.6×10^{-8}**

Should you have any questions, or if we may be of further service, please contact me at (937) 236-8805, extension 322.

Respectfully submitted,
BOWSER-MORNER, INC.

Karl A. Fletcher, Manager
Construction Materials and
Geotechnical Laboratories

KAF/blc
430274
1-File
1-mpartenio@cticompanies.com
1-kfoye@cticompanies.com

All Reports Remain The Confidential Property Of BOWSER-MORNER And No Publication Or Distribution Of Reports May Be Made Without Our Express Written Consent, Except As Authorized By Contract. Results Contained In This Report Are Reflective Only of The Items Calibrated or Tested. Unless Otherwise Agreed, Samples Or Specimens Will Be Discarded Or Returned At Bowser-Morner's Discretion. AASHTO/ISO 17025 Accreditation applies only to the parameters included in BOWSER-MORNER'S current scope of accreditation. Go to www.bowser-morner.com/accreditations for reviews.

FALLING HEAD PERMEABILITY TEST

ASTM D 5084, Measurement of Hydraulic Conductivity


UNDISTURBED

Client:	**CTI and Associates, Inc.**
Project:	**EMDF Characterization**
BMI Work Order Number:	183923
Sample Identification:	GW989 ST-2, 6.5' - 8.5'
Depth, ft:	7.3' - 7.6'
Visual Description:	brown silty clay

SPECIMEN DATA:

Dimension, inches	
Height:	3.008
Diameter:	2.86
Mass, lbs:	1.355
Moisture Content,%	
Initial:	28.0
Final:	30.0
Wet Unit Weight, pcf	
Initial:	121.2
Final:	123.1
Initial Dry Unit Weight, pcf:	94.7
Back Pressure Saturation, psi	
Back Pressure, Exit:	60
Back Pressure, Enter:	63
Lateral Pressure:	67

Permeability (k), cm/sec: **6.6×10^{-8}**




			BEFORE TEST	AFTER TEST
OVERBURDEN PRESSURE (t/ft^2)		WATER CONTENT (%)	26.2	18.0
PRECONSOL. PRESSURE (t/ft^2)		DRY DENSITY (lb/ft^3)	99.50	114.30
COMPRESSION INDEX		SATURATION (%)	100.24	99.61
TYPE SPECIMEN	Undisturb	VOID RATIO	0.72	0.49
DIA. (in) 2.500	HT. (in) 1.020	BACK PRESSURE (t/ft^2)	---	---


CLASSIFICATION brown clayey silt (visual description)

LL ---	PL ---	PI ---	PROJECT EMDF Characterization
GS 2.734	D_{10}		993ST1
REMARKS		BORING NO. GW993-ST-1	SAMPLE NO. GW993-ST-1
Use: Fill, Near foundation/geobuffer layer		DEPTH 3.6'-3.8'	DATE 3-16-18

Bowser Morner
CONSOLIDATION TEST REPORT


CONSOLIDATION TEST
TIME CURVES (STEP 1 OF 20)
STRESS : 0.06 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW993-ST-1 Sample No : GW993-ST-1
Test Date : 3-16-18 Test No : GW993-ST-1 Depth : 3.6'-3.8'
Description : brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 2 OF 20)
STRESS : 0.25 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW993-ST-1 Sample No : GW993-ST-1
Test Date : 3-16-18 Test No : GW993-ST-1 Depth : 3.6'-3.8'
Description : brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 3 OF 20)
STRESS : 0.5 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW993-ST-1 Sample No : GW993-ST-1
Test Date : 3-16-18 Test No : GW993-ST-1 Depth : 3.6'-3.8'
Description : brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 4 OF 20)
STRESS : 1 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW993-ST-1 Sample No : GW993-ST-1
Test Date : 3-16-18 Test No : GW993-ST-1 Depth : 3.6'-3.8'
Description : brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 5 OF 20)
STRESS : 2 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW993-ST-1 Sample No : GW993-ST-1
Test Date : 3-16-18 Test No : GW993-ST-1 Depth : 3.6'-3.8'
Description : brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 6 OF 20)
STRESS : 4 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW993-ST-1 Sample No : GW993-ST-1
Test Date : 3-16-18 Test No : GW993-ST-1 Depth : 3.6'-3.8'
Description : brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 7 OF 20)
STRESS : 2 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW993-ST-1 Sample No : GW993-ST-1
Test Date : 3-16-18 Test No : GW993-ST-1 Depth : 3.6'-3.8'
Description : brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 8 OF 20)
STRESS : 1 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW993-ST-1 Sample No : GW993-ST-1
Test Date : 3-16-18 Test No : GW993-ST-1 Depth : 3.6'-3.8'
Description : brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 9 OF 20)
STRESS : 0.5 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW993-ST-1 Sample No : GW993-ST-1
Test Date : 3-16-18 Test No : GW993-ST-1 Depth : 3.6'-3.8'
Description : brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 10 OF 20)
STRESS : 1 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW993-ST-1 Sample No : GW993-ST-1
Test Date : 3-16-18 Test No : GW993-ST-1 Depth : 3.6'-3.8'
Description : brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 11 OF 20)
STRESS : 2 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW993-ST-1 Sample No : GW993-ST-1
Test Date : 3-16-18 Test No : GW993-ST-1 Depth : 3.6'-3.8'
Description : brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 12 OF 20)
STRESS : 4 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW993-ST-1 Sample No : GW993-ST-1
Test Date : 3-16-18 Test No : GW993-ST-1 Depth : 3.6'-3.8'
Description : brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 13 OF 20)
STRESS : 8 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW993-ST-1 Sample No : GW993-ST-1
Test Date : 3-16-18 Test No : GW993-ST-1 Depth : 3.6'-3.8'
Description : brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 14 OF 20)
STRESS : 16 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW993-ST-1 Sample No : GW993-ST-1
Test Date : 3-16-18 Test No : GW993-ST-1 Depth : 3.6'-3.8'
Description : brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 15 OF 20)
STRESS : 32 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW993-ST-1 Sample No : GW993-ST-1
Test Date : 3-16-18 Test No : GW993-ST-1 Depth : 3.6'-3.8'
Description : brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 16 OF 20)
STRESS : 16 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW993-ST-1 Sample No : GW993-ST-1
Test Date : 3-16-18 Test No : GW993-ST-1 Depth : 3.6'-3.8'
Description : brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 17 OF 20)
STRESS : 8 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW993-ST-1 Sample No : GW993-ST-1
Test Date : 3-16-18 Test No : GW993-ST-1 Depth : 3.6'-3.8'
Description : brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 18 OF 20)
STRESS : 4 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW993-ST-1 Sample No : GW993-ST-1
Test Date : 3-16-18 Test No : GW993-ST-1 Depth : 3.6'-3.8'
Description : brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 19 OF 20)
STRESS : 2 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW993-ST-1 Sample No : GW993-ST-1
Test Date : 3-16-18 Test No : GW993-ST-1 Depth : 3.6'-3.8'
Description : brown clayey silt (visual description)

CONSOLIDATION TEST
TIME CURVES (STEP 20 OF 20)
STRESS : 1 (t/ft^2)





Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW993-ST-1 Sample No : GW993-ST-1
Test Date : 3-16-18 Test No : GW993-ST-1 Depth : 3.6'-3.8'
Description : brown clayey silt (visual description)

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW993-ST-1, 3.0'-5.0'
Project No.: 183923
Boring No.: GW993-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW993-ST-1
Test Date : 3-16-18
Depth : 3.6'-3.8'
Test No. : GW993-ST-1
Sample Type: Undisturb

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

	APPLIED PRESSURE (t/ft^2)	FINAL DISPLACEMENT (in)	VOID RATIO	STRAIN AT END (%)	FITTING T50 TIME (min) SQ.RT.	FITTING T50 TIME (min) LOG	COEFFICIENT OF CONSOLIDATION (in^2/s) SQ.RT.	COEFFICIENT OF CONSOLIDATION (in^2/s) LOG	COEFFICIENT OF CONSOLIDATION (in^2/s) AVE
1)	0.06	0.001	0.715	0.05	0.0	0.0	0.00E+000	0.00E+000	0.00E+000
2)	0.25	0.011	0.697	1.05	12.3	0.0	6.87E-005	0.00E+000	6.87E-005
3)	0.50	0.021	0.680	2.05	14.5	0.0	5.71E-005	0.00E+000	5.71E-005
4)	1.00	0.035	0.656	3.44	6.3	0.0	1.29E-004	0.00E+000	1.29E-004
5)	2.00	0.052	0.627	5.13	3.3	3.2	2.38E-004	2.47E-004	2.43E-004
6)	4.00	0.075	0.590	7.33	3.3	0.0	2.26E-004	0.00E+000	2.26E-004
7)	2.00	0.069	0.599	6.78	0.0	0.0	0.00E+000	0.00E+000	0.00E+000
8)	1.00	0.067	0.603	6.58	0.0	0.0	0.00E+000	0.00E+000	0.00E+000
9)	0.50	0.064	0.609	6.23	8.4	0.0	8.87E-005	0.00E+000	8.87E-005
10)	1.00	0.066	0.605	6.43	0.0	0.0	0.00E+000	0.00E+000	0.00E+000
11)	2.00	0.069	0.599	6.78	0.0	0.0	0.00E+000	0.00E+000	0.00E+000
12)	4.00	0.076	0.587	7.48	0.0	0.0	0.00E+000	0.00E+000	0.00E+000
13)	8.00	0.102	0.544	10.02	7.1	3.0	9.99E-005	2.40E-004	1.70E-004
14)	16.00	0.135	0.489	13.20	1.8	0.0	3.71E-004	0.00E+000	3.71E-004
15)	32.00	0.172	0.426	16.89	1.9	2.1	3.24E-004	3.00E-004	3.12E-004
16)	16.00	0.165	0.439	16.14	9.2	0.0	6.47E-005	0.00E+000	6.47E-005
17)	8.00	0.155	0.455	15.20	0.0	0.0	0.00E+000	0.00E+000	0.00E+000
18)	4.00	0.146	0.469	14.35	7.6	0.0	8.18E-005	0.00E+000	8.18E-005
19)	2.00	0.139	0.482	13.60	10.7	0.0	5.89E-005	0.00E+000	5.89E-005
20)	1.00	0.132	0.493	12.95	39.7	0.0	1.62E-005	0.00E+000	1.62E-005

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Specific Gravity : 2.73	Liquid Limit : 0	Initial Height : 1.02 (in)
Initial Void Ratio : 0.72	Plastic Limit : 0	Sample Diameter : 2.50 (in)
Final Void Ratio : 0.49	Plasticity Index : 0	

	BEFORE CONSOLIDATION		AFTER CONSOLIDATION	
	TRIMMINGS	SPECIMEN + RING	SPECIMEN + RING	TRIMMINGS
CONTAINER NO.		RING	RING	
WT CONTAINER + WET SOIL (gm)	165.07	165.07	154.27	154.27
WT CONTAINER + DRY SOIL (gm)	130.77	130.77	130.77	130.77
WT CONTAINER (gm)	0.00	0.00	0.00	0.00
WT DRY SOIL (gm)	130.77	130.77	130.77	130.77
WATER CONTENT (%)	26.23	26.23	17.97	17.97
VOID RATIO	------	0.72	0.49	------
DEGREE OF SATURATION (%)	------	100.24	99.61	------
DRY DENSITY (lb/ft^3)	------	99.50	114.30	------

Note: Specific Gravity and Void Ratios are calculated assuming the degree of saturation equals 100% at the end of the test. Therefor values may not represent actual values for the specimen.

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 1 of 20
Stress increment from 0.00 (t/ft^2) to 0.06 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.17	0.41	0.0000	0.715	0.00
2)	0.90	0.95	0.0000	0.715	0.00
3)	2.90	1.70	0.0005	0.715	0.05
4)	3.93	1.98	0.0005	0.715	0.05
5)	5.33	2.31	0.0005	0.715	0.05

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW993-ST-1, 3.0'-5.0'
Project No.: 183923
Boring No.: GW993-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW993-ST-1
Test Date : 3-16-18
Depth : 3.6'-3.8'
Test No. : GW993-ST-1
Sample Type: Undisturb

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 2 of 20
Stress increment from 0.06 (t/ft^2) to 0.25 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0020	0.712	0.20
2)	0.13	0.37	0.0020	0.712	0.20
3)	0.38	0.62	0.0025	0.711	0.25
4)	0.88	0.94	0.0030	0.710	0.30
5)	1.87	1.37	0.0030	0.710	0.30
6)	2.87	1.69	0.0036	0.709	0.35
7)	3.87	1.97	0.0041	0.709	0.40
8)	4.88	2.21	0.0041	0.709	0.40
9)	5.88	2.43	0.0046	0.708	0.45
10)	6.87	2.62	0.0046	0.708	0.45
11)	7.90	2.81	0.0051	0.707	0.50
12)	8.88	2.98	0.0051	0.707	0.50
13)	9.90	3.15	0.0056	0.706	0.55
14)	14.88	3.86	0.0061	0.705	0.60
15)	29.88	5.47	0.0076	0.703	0.75
16)	59.88	7.74	0.0091	0.700	0.90
17)	89.92	9.48	0.0097	0.699	0.95
18)	119.88	10.95	0.0097	0.699	0.95
19)	149.90	12.24	0.0102	0.698	1.00
20)	179.88	13.41	0.0102	0.698	1.00
21)	209.87	14.49	0.0102	0.698	1.00
22)	239.87	15.49	0.0102	0.698	1.00
23)	299.88	17.32	0.0102	0.698	1.00
24)	359.88	18.97	0.0107	0.697	1.05
25)	419.88	20.49	0.0107	0.697	1.05
26)	479.87	21.91	0.0107	0.697	1.05
27)	539.87	23.24	0.0107	0.697	1.05
28)	599.88	24.49	0.0107	0.697	1.05
29)	659.90	25.69	0.0107	0.697	1.05
30)	719.88	26.83	0.0112	0.697	1.10
31)	779.87	27.93	0.0112	0.697	1.10
32)	839.88	28.98	0.0112	0.697	1.10
33)	899.87	30.00	0.0107	0.697	1.05
34)	959.88	30.98	0.0112	0.697	1.10
35)	1019.88	31.94	0.0112	0.697	1.10

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 2 of 20
Stress increment from 0.06 (t/ft^2) to 0.25 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.88	32.86	0.0107	0.697	1.05
37)	1139.88	33.76	0.0107	0.697	1.05
38)	1199.90	34.64	0.0112	0.697	1.10
39)	1259.88	35.49	0.0112	0.697	1.10
40)	1303.47	36.10	0.0107	0.697	1.05

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 3 of 20
Stress increment from 0.25 (t/ft^2) to 0.50 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0132	0.693	1.29
2)	0.15	0.39	0.0132	0.693	1.29
3)	0.40	0.63	0.0137	0.692	1.34
4)	0.92	0.96	0.0142	0.691	1.39
5)	1.90	1.38	0.0147	0.691	1.44
6)	2.90	1.70	0.0152	0.690	1.49
7)	3.92	1.98	0.0152	0.690	1.49
8)	4.92	2.22	0.0157	0.689	1.54
9)	5.93	2.44	0.0163	0.688	1.59
10)	6.93	2.63	0.0163	0.688	1.59
11)	7.90	2.81	0.0168	0.687	1.64
12)	8.92	2.99	0.0168	0.687	1.64
13)	9.93	3.15	0.0168	0.687	1.64
14)	14.90	3.86	0.0173	0.686	1.69
15)	29.90	5.47	0.0188	0.684	1.84
16)	59.92	7.74	0.0198	0.682	1.94
17)	89.92	9.48	0.0198	0.682	1.94
18)	119.93	10.95	0.0203	0.681	1.99
19)	149.93	12.24	0.0198	0.682	1.94
20)	179.92	13.41	0.0203	0.681	1.99
21)	209.92	14.49	0.0203	0.681	1.99
22)	239.92	15.49	0.0208	0.680	2.04
23)	299.92	17.32	0.0208	0.680	2.04
24)	359.90	18.97	0.0208	0.680	2.04
25)	419.92	20.49	0.0213	0.680	2.09
26)	479.90	21.91	0.0213	0.680	2.09
27)	539.90	23.24	0.0213	0.680	2.09
28)	599.92	24.49	0.0213	0.680	2.09
29)	659.92	25.69	0.0213	0.680	2.09
30)	719.92	26.83	0.0213	0.680	2.09
31)	779.92	27.93	0.0213	0.680	2.09
32)	839.90	28.98	0.0213	0.680	2.09
33)	899.92	30.00	0.0213	0.680	2.09
34)	959.92	30.98	0.0213	0.680	2.09
35)	1019.95	31.94	0.0213	0.680	2.09

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 3 of 20
Stress increment from 0.25 (t/ft^2) to 0.50 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.92	32.86	0.0213	0.680	2.09
37)	1139.90	33.76	0.0213	0.680	2.09
38)	1199.90	34.64	0.0213	0.680	2.09
39)	1259.92	35.50	0.0208	0.680	2.04
40)	1309.85	36.19	0.0208	0.680	2.04

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 4 of 20
Stress increment from 0.50 (t/ft^2) to 1.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0254	0.673	2.49
2)	0.15	0.39	0.0259	0.672	2.54
3)	0.40	0.63	0.0264	0.671	2.59
4)	0.90	0.95	0.0269	0.670	2.64
5)	1.92	1.38	0.0284	0.668	2.79
6)	2.92	1.71	0.0290	0.667	2.84
7)	3.90	1.97	0.0295	0.666	2.89
8)	4.92	2.22	0.0305	0.664	2.99
9)	5.92	2.43	0.0305	0.664	2.99
10)	6.92	2.63	0.0310	0.663	3.04
11)	7.92	2.81	0.0310	0.663	3.04
12)	8.92	2.99	0.0310	0.663	3.04
13)	9.92	3.15	0.0310	0.663	3.04
14)	14.90	3.86	0.0320	0.662	3.14
15)	29.92	5.47	0.0335	0.659	3.29
16)	59.93	7.74	0.0340	0.658	3.34
17)	89.92	9.48	0.0345	0.657	3.39
18)	119.90	10.95	0.0340	0.658	3.34
19)	149.92	12.24	0.0345	0.657	3.39
20)	179.92	13.41	0.0345	0.657	3.39
21)	209.92	14.49	0.0351	0.656	3.44
22)	239.92	15.49	0.0345	0.657	3.39
23)	299.92	17.32	0.0345	0.657	3.39
24)	359.93	18.97	0.0345	0.657	3.39
25)	419.90	20.49	0.0351	0.656	3.44
26)	479.92	21.91	0.0351	0.656	3.44
27)	539.90	23.24	0.0351	0.656	3.44
28)	599.92	24.49	0.0351	0.656	3.44
29)	659.92	25.69	0.0351	0.656	3.44
30)	719.92	26.83	0.0351	0.656	3.44
31)	779.95	27.93	0.0351	0.656	3.44
32)	839.92	28.98	0.0356	0.656	3.49
33)	899.92	30.00	0.0356	0.656	3.49
34)	959.93	30.98	0.0356	0.656	3.49
35)	1019.92	31.94	0.0351	0.656	3.44

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 4 of 20
Stress increment from 0.50 (t/ft^2) to 1.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.0356	0.656	3.49
37)	1139.92	33.76	0.0356	0.656	3.49
38)	1199.92	34.64	0.0356	0.656	3.49
39)	1259.92	35.50	0.0356	0.656	3.49
40)	1319.90	36.33	0.0356	0.656	3.49
41)	1379.90	37.15	0.0356	0.656	3.49
42)	1439.92	37.95	0.0351	0.656	3.44
43)	1499.90	38.73	0.0356	0.656	3.49
44)	1559.90	39.50	0.0356	0.656	3.49
45)	1619.90	40.25	0.0351	0.656	3.44
46)	1626.50	40.33	0.0351	0.656	3.44

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW993-ST-1, 3.0'-5.0'
Project No.: 183923
Boring No.: GW993-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW993-ST-1
Test Date : 3-16-18
Depth : 3.6'-3.8'
Test No. : GW993-ST-1
Sample Type: Undisturb

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 5 of 20
Stress increment from 1.00 (t/ft^2) to 2.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0401	0.648	3.93
2)	0.15	0.39	0.0411	0.646	4.03
3)	0.40	0.63	0.0417	0.645	4.08
4)	0.90	0.95	0.0427	0.644	4.18
5)	1.90	1.38	0.0437	0.642	4.28
6)	2.92	1.71	0.0447	0.640	4.38
7)	3.90	1.97	0.0452	0.639	4.43
8)	4.90	2.21	0.0457	0.638	4.48
9)	5.92	2.43	0.0462	0.638	4.53
10)	6.90	2.63	0.0467	0.637	4.58
11)	7.90	2.81	0.0467	0.637	4.58
12)	8.90	2.98	0.0467	0.637	4.58
13)	9.90	3.15	0.0472	0.636	4.63
14)	14.90	3.86	0.0488	0.633	4.78
15)	29.90	5.47	0.0493	0.633	4.83
16)	59.90	7.74	0.0503	0.631	4.93
17)	89.92	9.48	0.0503	0.631	4.93
18)	119.90	10.95	0.0508	0.630	4.98
19)	149.90	12.24	0.0508	0.630	4.98
20)	179.93	13.41	0.0513	0.629	5.03
21)	209.90	14.49	0.0508	0.630	4.98
22)	239.90	15.49	0.0513	0.629	5.03
23)	299.90	17.32	0.0518	0.628	5.08
24)	359.90	18.97	0.0518	0.628	5.08
25)	419.93	20.49	0.0518	0.628	5.08
26)	479.93	21.91	0.0518	0.628	5.08
27)	539.90	23.24	0.0518	0.628	5.08
28)	599.90	24.49	0.0523	0.627	5.13
29)	659.90	25.69	0.0523	0.627	5.13
30)	719.92	26.83	0.0523	0.627	5.13
31)	779.90	27.93	0.0523	0.627	5.13
32)	839.88	28.98	0.0523	0.627	5.13
33)	899.90	30.00	0.0523	0.627	5.13
34)	959.90	30.98	0.0528	0.627	5.18
35)	1019.90	31.94	0.0523	0.627	5.13

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 5 of 20
Stress increment from 1.00 (t/ft^2) to 2.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.0528	0.627	5.18
37)	1139.90	33.76	0.0528	0.627	5.18
38)	1199.90	34.64	0.0528	0.627	5.18
39)	1259.88	35.49	0.0528	0.627	5.18
40)	1319.92	36.33	0.0528	0.627	5.18
41)	1327.82	36.44	0.0523	0.627	5.13

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 6 of 20
Stress increment from 2.00 (t/ft^2) to 4.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0599	0.615	5.88
2)	0.17	0.41	0.0610	0.613	5.98
3)	0.40	0.63	0.0620	0.611	6.08
4)	0.90	0.95	0.0635	0.609	6.23
5)	1.90	1.38	0.0650	0.606	6.37
6)	2.90	1.70	0.0660	0.604	6.47
7)	3.90	1.97	0.0665	0.603	6.52
8)	4.90	2.21	0.0671	0.603	6.57
9)	5.93	2.44	0.0681	0.601	6.67
10)	6.90	2.63	0.0686	0.600	6.72
11)	7.90	2.81	0.0686	0.600	6.72
12)	8.90	2.98	0.0691	0.599	6.77
13)	9.90	3.15	0.0691	0.599	6.77
14)	14.90	3.86	0.0706	0.597	6.92
15)	29.90	5.47	0.0716	0.595	7.02
16)	59.90	7.74	0.0721	0.594	7.07
17)	89.92	9.48	0.0726	0.593	7.12
18)	119.90	10.95	0.0726	0.593	7.12
19)	149.92	12.24	0.0732	0.592	7.17
20)	179.93	13.41	0.0732	0.592	7.17
21)	209.90	14.49	0.0732	0.592	7.17
22)	239.90	15.49	0.0732	0.592	7.17
23)	299.92	17.32	0.0732	0.592	7.17
24)	359.90	18.97	0.0737	0.592	7.22
25)	419.92	20.49	0.0737	0.592	7.22
26)	479.93	21.91	0.0737	0.592	7.22
27)	539.90	23.24	0.0742	0.591	7.27
28)	599.90	24.49	0.0737	0.592	7.22
29)	659.90	25.69	0.0737	0.592	7.22
30)	719.92	26.83	0.0742	0.591	7.27
31)	779.90	27.93	0.0742	0.591	7.27
32)	839.92	28.98	0.0742	0.591	7.27
33)	899.90	30.00	0.0742	0.591	7.27
34)	959.90	30.98	0.0742	0.591	7.27
35)	1019.90	31.94	0.0742	0.591	7.27

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 6 of 20
Stress increment from 2.00 (t/ft^2) to 4.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.0742	0.591	7.27
37)	1139.90	33.76	0.0742	0.591	7.27
38)	1199.90	34.64	0.0742	0.591	7.27
39)	1259.88	35.49	0.0742	0.591	7.27
40)	1319.92	36.33	0.0742	0.591	7.27
41)	1379.90	37.15	0.0747	0.590	7.32
42)	1428.78	37.80	0.0747	0.590	7.32

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 7 of 20
Stress increment from 4.00 (t/ft^2) to 2.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0716	0.595	7.02
2)	0.13	0.37	0.0716	0.595	7.02
3)	0.38	0.62	0.0716	0.595	7.02
4)	0.90	0.95	0.0721	0.594	7.07
5)	1.88	1.37	0.0711	0.596	6.97
6)	2.88	1.70	0.0711	0.596	6.97
7)	3.88	1.97	0.0711	0.596	6.97
8)	4.88	2.21	0.0711	0.596	6.97
9)	5.88	2.43	0.0711	0.596	6.97
10)	6.88	2.62	0.0711	0.596	6.97
11)	7.90	2.81	0.0711	0.596	6.97
12)	8.88	2.98	0.0706	0.597	6.92
13)	9.90	3.15	0.0711	0.596	6.97
14)	14.90	3.86	0.0716	0.595	7.02
15)	29.90	5.47	0.0716	0.595	7.02
16)	59.88	7.74	0.0711	0.596	6.97
17)	89.90	9.48	0.0711	0.596	6.97
18)	119.90	10.95	0.0711	0.596	6.97
19)	149.88	12.24	0.0711	0.596	6.97
20)	179.88	13.41	0.0706	0.597	6.92
21)	209.88	14.49	0.0711	0.596	6.97
22)	239.88	15.49	0.0706	0.597	6.92
23)	299.88	17.32	0.0706	0.597	6.92
24)	359.87	18.97	0.0706	0.597	6.92
25)	419.88	20.49	0.0706	0.597	6.92
26)	479.90	21.91	0.0711	0.596	6.97
27)	539.90	23.24	0.0706	0.597	6.92
28)	599.88	24.49	0.0706	0.597	6.92
29)	659.87	25.69	0.0706	0.597	6.92
30)	719.90	26.83	0.0706	0.597	6.92
31)	779.88	27.93	0.0711	0.596	6.97
32)	839.88	28.98	0.0706	0.597	6.92
33)	899.88	30.00	0.0706	0.597	6.92
34)	959.90	30.98	0.0706	0.597	6.92
35)	1019.88	31.94	0.0706	0.597	6.92

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 7 of 20
Stress increment from 4.00 (t/ft^2) to 2.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.0706	0.597	6.92
37)	1139.88	33.76	0.0706	0.597	6.92
38)	1199.88	34.64	0.0706	0.597	6.92
39)	1259.90	35.50	0.0706	0.597	6.92
40)	1319.88	36.33	0.0706	0.597	6.92
41)	1379.87	37.15	0.0706	0.597	6.92
42)	1439.88	37.95	0.0706	0.597	6.92
43)	1441.68	37.97	0.0691	0.599	6.77

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 8 of 20
Stress increment from 2.00 (t/ft^2) to 1.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0681	0.601	6.67
2)	0.15	0.39	0.0686	0.600	6.72
3)	0.40	0.63	0.0686	0.600	6.72
4)	0.90	0.95	0.0681	0.601	6.67
5)	1.90	1.38	0.0681	0.601	6.67
6)	2.90	1.70	0.0681	0.601	6.67
7)	3.90	1.97	0.0676	0.602	6.62
8)	4.90	2.21	0.0676	0.602	6.62
9)	5.90	2.43	0.0676	0.602	6.62
10)	6.92	2.63	0.0676	0.602	6.62
11)	7.92	2.81	0.0676	0.602	6.62
12)	8.92	2.99	0.0676	0.602	6.62
13)	9.88	3.14	0.0676	0.602	6.62
14)	14.92	3.86	0.0671	0.603	6.57
15)	29.90	5.47	0.0681	0.601	6.67
16)	59.90	7.74	0.0681	0.601	6.67
17)	89.90	9.48	0.0676	0.602	6.62
18)	119.92	10.95	0.0676	0.602	6.62
19)	149.90	12.24	0.0676	0.602	6.62
20)	179.92	13.41	0.0676	0.602	6.62
21)	209.92	14.49	0.0676	0.602	6.62
22)	239.93	15.49	0.0676	0.602	6.62
23)	299.92	17.32	0.0676	0.602	6.62
24)	359.92	18.97	0.0671	0.603	6.57
25)	419.88	20.49	0.0676	0.602	6.62
26)	479.90	21.91	0.0671	0.603	6.57
27)	539.92	23.24	0.0676	0.602	6.62
28)	599.90	24.49	0.0676	0.602	6.62
29)	659.92	25.69	0.0676	0.602	6.62
30)	719.90	26.83	0.0671	0.603	6.57
31)	779.92	27.93	0.0676	0.602	6.62
32)	839.90	28.98	0.0676	0.602	6.62
33)	899.90	30.00	0.0676	0.602	6.62
34)	959.88	30.98	0.0676	0.602	6.62
35)	1019.88	31.94	0.0676	0.602	6.62

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 8 of 20
Stress increment from 2.00 (t/ft^2) to 1.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.0676	0.602	6.62
37)	1139.92	33.76	0.0676	0.602	6.62
38)	1199.92	34.64	0.0671	0.603	6.57
39)	1259.88	35.49	0.0676	0.602	6.62
40)	1319.90	36.33	0.0676	0.602	6.62
41)	1379.88	37.15	0.0671	0.603	6.57
42)	1439.88	37.95	0.0676	0.602	6.62
43)	1479.53	38.46	0.0671	0.603	6.57

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW993-ST-1, 3.0'-5.0'
Project No.: 183923
Boring No.: GW993-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW993-ST-1
Test Date : 3-16-18
Depth : 3.6'-3.8'
Test No. : GW993-ST-1
Sample Type: Undisturb

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 9 of 20
Stress increment from 1.00 (t/ft^2) to 0.50 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0655	0.605	6.42
2)	0.13	0.37	0.0655	0.605	6.42
3)	0.38	0.62	0.0650	0.606	6.37
4)	0.88	0.94	0.0650	0.606	6.37
5)	1.90	1.38	0.0650	0.606	6.37
6)	2.90	1.70	0.0645	0.607	6.33
7)	3.90	1.97	0.0645	0.607	6.33
8)	4.88	2.21	0.0645	0.607	6.33
9)	5.90	2.43	0.0645	0.607	6.33
10)	6.90	2.63	0.0645	0.607	6.33
11)	7.90	2.81	0.0645	0.607	6.33
12)	8.92	2.99	0.0640	0.608	6.28
13)	9.88	3.14	0.0645	0.607	6.33
14)	14.90	3.86	0.0645	0.607	6.33
15)	29.88	5.47	0.0640	0.608	6.28
16)	59.90	7.74	0.0645	0.607	6.33
17)	89.88	9.48	0.0640	0.608	6.28
18)	119.90	10.95	0.0640	0.608	6.28
19)	149.93	12.24	0.0640	0.608	6.28
20)	179.88	13.41	0.0640	0.608	6.28
21)	209.88	14.49	0.0635	0.609	6.23
22)	239.88	15.49	0.0640	0.608	6.28
23)	299.90	17.32	0.0640	0.608	6.28
24)	359.90	18.97	0.0640	0.608	6.28
25)	419.92	20.49	0.0640	0.608	6.28
26)	479.88	21.91	0.0640	0.608	6.28
27)	539.88	23.24	0.0640	0.608	6.28
28)	599.92	24.49	0.0640	0.608	6.28
29)	659.90	25.69	0.0640	0.608	6.28
30)	719.90	26.83	0.0640	0.608	6.28
31)	779.92	27.93	0.0640	0.608	6.28
32)	839.88	28.98	0.0640	0.608	6.28
33)	899.88	30.00	0.0640	0.608	6.28
34)	959.90	30.98	0.0640	0.608	6.28
35)	1019.92	31.94	0.0640	0.608	6.28

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 9 of 20
Stress increment from 1.00 (t/ft^2) to 0.50 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.88	32.86	0.0640	0.608	6.28
37)	1139.88	33.76	0.0640	0.608	6.28
38)	1199.93	34.64	0.0640	0.608	6.28
39)	1259.88	35.49	0.0640	0.608	6.28
40)	1319.88	36.33	0.0640	0.608	6.28
41)	1327.25	36.43	0.0635	0.609	6.23

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW993-ST-1, 3.0'-5.0'
Project No.: 183923
Boring No.: GW993-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW993-ST-1
Test Date : 3-16-18
Depth : 3.6'-3.8'
Test No. : GW993-ST-1
Sample Type: Undisturb

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 10 of 20
Stress increment from 0.50 (t/ft^2) to 1.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0650	0.606	6.37
2)	0.15	0.39	0.0650	0.606	6.37
3)	0.40	0.63	0.0645	0.607	6.33
4)	0.92	0.96	0.0650	0.606	6.37
5)	1.90	1.38	0.0650	0.606	6.37
6)	2.90	1.70	0.0650	0.606	6.37
7)	3.90	1.97	0.0650	0.606	6.37
8)	4.90	2.21	0.0650	0.606	6.37
9)	5.90	2.43	0.0650	0.606	6.37
10)	6.90	2.63	0.0650	0.606	6.37
11)	7.92	2.81	0.0650	0.606	6.37
12)	8.90	2.98	0.0650	0.606	6.37
13)	9.90	3.15	0.0650	0.606	6.37
14)	14.92	3.86	0.0650	0.606	6.37
15)	29.90	5.47	0.0650	0.606	6.37
16)	59.90	7.74	0.0650	0.606	6.37
17)	89.90	9.48	0.0650	0.606	6.37
18)	119.92	10.95	0.0655	0.605	6.42
19)	149.90	12.24	0.0650	0.606	6.37
20)	179.90	13.41	0.0660	0.604	6.47
21)	209.90	14.49	0.0655	0.605	6.42
22)	239.90	15.49	0.0660	0.604	6.47
23)	299.90	17.32	0.0660	0.604	6.47
24)	359.90	18.97	0.0660	0.604	6.47
25)	419.92	20.49	0.0660	0.604	6.47
26)	479.90	21.91	0.0660	0.604	6.47
27)	539.90	23.24	0.0660	0.604	6.47
28)	599.90	24.49	0.0660	0.604	6.47
29)	659.90	25.69	0.0660	0.604	6.47
30)	719.90	26.83	0.0655	0.605	6.42
31)	779.90	27.93	0.0655	0.605	6.42
32)	839.90	28.98	0.0660	0.604	6.47
33)	899.88	30.00	0.0660	0.604	6.47
34)	959.90	30.98	0.0660	0.604	6.47
35)	1019.90	31.94	0.0660	0.604	6.47

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 10 of 20
Stress increment from 0.50 (t/ft^2) to 1.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.88	32.86	0.0660	0.604	6.47
37)	1139.90	33.76	0.0660	0.604	6.47
38)	1199.90	34.64	0.0660	0.604	6.47
39)	1259.90	35.50	0.0660	0.604	6.47
40)	1319.90	36.33	0.0660	0.604	6.47
41)	1379.90	37.15	0.0660	0.604	6.47
42)	1439.90	37.95	0.0655	0.605	6.42
43)	1499.88	38.73	0.0660	0.604	6.47
44)	1500.63	38.74	0.0655	0.605	6.42

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW993-ST-1, 3.0'-5.0'
Project No.: 183923
Boring No.: GW993-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW993-ST-1
Test Date : 3-16-18
Depth : 3.6'-3.8'
Test No. : GW993-ST-1
Sample Type: Undisturb

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 11 of 20
Stress increment from 1.00 (t/ft^2) to 2.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0681	0.601	6.67
2)	0.15	0.39	0.0681	0.601	6.67
3)	0.38	0.62	0.0681	0.601	6.67
4)	0.88	0.94	0.0686	0.600	6.72
5)	1.92	1.38	0.0686	0.600	6.72
6)	2.90	1.70	0.0686	0.600	6.72
7)	3.88	1.97	0.0686	0.600	6.72
8)	4.90	2.21	0.0686	0.600	6.72
9)	5.88	2.43	0.0686	0.600	6.72
10)	6.92	2.63	0.0686	0.600	6.72
11)	7.92	2.81	0.0686	0.600	6.72
12)	8.90	2.98	0.0686	0.600	6.72
13)	9.88	3.14	0.0686	0.600	6.72
14)	14.88	3.86	0.0691	0.599	6.77
15)	29.88	5.47	0.0696	0.598	6.82
16)	59.90	7.74	0.0696	0.598	6.82
17)	89.90	9.48	0.0696	0.598	6.82
18)	119.90	10.95	0.0696	0.598	6.82
19)	149.88	12.24	0.0696	0.598	6.82
20)	179.92	13.41	0.0696	0.598	6.82
21)	209.92	14.49	0.0696	0.598	6.82
22)	239.93	15.49	0.0696	0.598	6.82
23)	299.90	17.32	0.0696	0.598	6.82
24)	359.90	18.97	0.0696	0.598	6.82
25)	419.90	20.49	0.0696	0.598	6.82
26)	479.88	21.91	0.0691	0.599	6.77
27)	539.92	23.24	0.0696	0.598	6.82
28)	599.90	24.49	0.0696	0.598	6.82
29)	659.90	25.69	0.0696	0.598	6.82
30)	719.88	26.83	0.0696	0.598	6.82
31)	779.88	27.93	0.0696	0.598	6.82
32)	839.90	28.98	0.0696	0.598	6.82
33)	899.88	30.00	0.0696	0.598	6.82
34)	959.90	30.98	0.0696	0.598	6.82
35)	1019.88	31.94	0.0696	0.598	6.82

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 11 of 20
Stress increment from 1.00 (t/ft^2) to 2.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.88	32.86	0.0696	0.598	6.82
37)	1139.90	33.76	0.0696	0.598	6.82
38)	1199.88	34.64	0.0696	0.598	6.82
39)	1259.88	35.49	0.0696	0.598	6.82
40)	1319.88	36.33	0.0696	0.598	6.82
41)	1379.88	37.15	0.0696	0.598	6.82
42)	1439.90	37.95	0.0696	0.598	6.82
43)	1499.88	38.73	0.0696	0.598	6.82
44)	1505.98	38.81	0.0691	0.599	6.77

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Boring No.: GW993-ST-1
Sample No.: GW993-ST-1
Test No. : GW993-ST-1

Location : GW993-ST-1, 3.0'-5.0'
Tested by : BMI: blc
Test Date : 3-16-18
Sample Type: Undisturb

Project No.: 183923
Checked by : KAF
Depth : 3.6'-3.8'

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 12 of 20
Stress increment from 2.00 (t/ft^2) to 4.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0732	0.592	7.17
2)	0.10	0.32	0.0737	0.592	7.22
3)	0.37	0.61	0.0737	0.592	7.22
4)	0.85	0.92	0.0737	0.592	7.22
5)	1.87	1.37	0.0742	0.591	7.27
6)	2.87	1.69	0.0742	0.591	7.27
7)	3.87	1.97	0.0747	0.590	7.32
8)	4.87	2.21	0.0747	0.590	7.32
9)	5.92	2.43	0.0747	0.590	7.32
10)	6.88	2.62	0.0747	0.590	7.32
11)	7.87	2.80	0.0742	0.591	7.27
12)	8.85	2.97	0.0747	0.590	7.32
13)	9.87	3.14	0.0747	0.590	7.32
14)	14.87	3.86	0.0747	0.590	7.32
15)	29.87	5.47	0.0752	0.589	7.37
16)	59.87	7.74	0.0752	0.589	7.37
17)	89.85	9.48	0.0757	0.588	7.42
18)	119.87	10.95	0.0752	0.589	7.37
19)	149.85	12.24	0.0757	0.588	7.42
20)	179.88	13.41	0.0757	0.588	7.42
21)	209.87	14.49	0.0762	0.587	7.47
22)	239.87	15.49	0.0757	0.588	7.42
23)	299.90	17.32	0.0757	0.588	7.42
24)	359.87	18.97	0.0757	0.588	7.42
25)	419.87	20.49	0.0757	0.588	7.42
26)	479.85	21.91	0.0762	0.587	7.47
27)	539.88	23.24	0.0762	0.587	7.47
28)	599.87	24.49	0.0757	0.588	7.42
29)	659.87	25.69	0.0762	0.587	7.47
30)	719.90	26.83	0.0762	0.587	7.47
31)	779.87	27.93	0.0762	0.587	7.47
32)	839.90	28.98	0.0762	0.587	7.47
33)	899.85	30.00	0.0762	0.587	7.47
34)	959.88	30.98	0.0762	0.587	7.47
35)	1019.85	31.94	0.0762	0.587	7.47

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 13 of 20
Stress increment from 4.00 (t/ft^2) to 8.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0869	0.569	8.52
2)	0.15	0.39	0.0884	0.567	8.67
3)	0.40	0.63	0.0889	0.566	8.72
4)	0.90	0.95	0.0904	0.563	8.87
5)	1.88	1.37	0.0925	0.560	9.06
6)	2.90	1.70	0.0930	0.559	9.11
7)	3.92	1.98	0.0940	0.557	9.21
8)	4.92	2.22	0.0945	0.556	9.26
9)	5.90	2.43	0.0955	0.555	9.36
10)	6.90	2.63	0.0955	0.555	9.36
11)	7.90	2.81	0.0965	0.553	9.46
12)	8.90	2.98	0.0965	0.553	9.46
13)	9.92	3.15	0.0965	0.553	9.46
14)	14.92	3.86	0.0970	0.552	9.51
15)	29.90	5.47	0.0986	0.550	9.66
16)	59.92	7.74	0.0996	0.548	9.76
17)	89.92	9.48	0.1001	0.547	9.81
18)	119.88	10.95	0.1001	0.547	9.81
19)	149.90	12.24	0.1001	0.547	9.81
20)	179.92	13.41	0.1006	0.546	9.86
21)	209.90	14.49	0.1006	0.546	9.86
22)	239.90	15.49	0.1006	0.546	9.86
23)	299.90	17.32	0.1006	0.546	9.86
24)	359.92	18.97	0.1011	0.545	9.91
25)	419.90	20.49	0.1011	0.545	9.91
26)	479.88	21.91	0.1016	0.545	9.96
27)	539.88	23.24	0.1016	0.545	9.96
28)	599.90	24.49	0.1016	0.545	9.96
29)	659.90	25.69	0.1016	0.545	9.96
30)	719.90	26.83	0.1016	0.545	9.96
31)	779.88	27.93	0.1016	0.545	9.96
32)	839.90	28.98	0.1016	0.545	9.96
33)	899.88	30.00	0.1021	0.544	10.01
34)	959.92	30.98	0.1021	0.544	10.01
35)	1019.95	31.94	0.1016	0.545	9.96

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 13 of 20
Stress increment from 4.00 (t/ft^2) to 8.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.92	32.86	0.1016	0.545	9.96
37)	1139.88	33.76	0.1021	0.544	10.01
38)	1199.90	34.64	0.1021	0.544	10.01
39)	1259.90	35.50	0.1021	0.544	10.01
40)	1319.93	36.33	0.1021	0.544	10.01
41)	1379.90	37.15	0.1016	0.545	9.96
42)	1439.88	37.95	0.1016	0.545	9.96
43)	1456.38	38.16	0.1021	0.544	10.01

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW993-ST-1, 3.0'-5.0'
Project No.: 183923
Boring No.: GW993-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW993-ST-1
Test Date : 3-16-18
Depth : 3.6'-3.8'
Test No. : GW993-ST-1
Sample Type: Undisturb

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 14 of 20
Stress increment from 8.00 (t/ft^2) to 16.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.1158	0.521	11.36
2)	0.15	0.39	0.1173	0.518	11.50
3)	0.40	0.63	0.1194	0.515	11.70
4)	0.90	0.95	0.1214	0.511	11.90
5)	1.90	1.38	0.1240	0.507	12.15
6)	2.88	1.70	0.1255	0.504	12.30
7)	3.92	1.98	0.1265	0.503	12.40
8)	4.90	2.21	0.1275	0.501	12.50
9)	5.92	2.43	0.1280	0.500	12.55
10)	6.88	2.62	0.1285	0.499	12.60
11)	7.88	2.81	0.1290	0.498	12.65
12)	8.88	2.98	0.1290	0.498	12.65
13)	9.90	3.15	0.1295	0.498	12.70
14)	14.88	3.86	0.1306	0.496	12.80
15)	29.92	5.47	0.1321	0.493	12.95
16)	59.88	7.74	0.1326	0.492	13.00
17)	89.88	9.48	0.1331	0.492	13.05
18)	119.90	10.95	0.1331	0.492	13.05
19)	149.88	12.24	0.1331	0.492	13.05
20)	179.90	13.41	0.1336	0.491	13.10
21)	209.88	14.49	0.1336	0.491	13.10
22)	239.92	15.49	0.1336	0.491	13.10
23)	299.88	17.32	0.1341	0.490	13.15
24)	359.90	18.97	0.1341	0.490	13.15
25)	419.88	20.49	0.1341	0.490	13.15
26)	479.88	21.91	0.1346	0.489	13.20
27)	539.90	23.24	0.1346	0.489	13.20
28)	599.90	24.49	0.1346	0.489	13.20
29)	659.90	25.69	0.1346	0.489	13.20
30)	719.90	26.83	0.1346	0.489	13.20
31)	779.90	27.93	0.1346	0.489	13.20
32)	839.90	28.98	0.1351	0.488	13.25
33)	899.88	30.00	0.1351	0.488	13.25
34)	959.90	30.98	0.1351	0.488	13.25
35)	1019.88	31.94	0.1346	0.489	13.20

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW993-ST-1, 3.0'-5.0'
Project No.: 183923
Boring No.: GW993-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW993-ST-1
Test Date : 3-16-18
Depth : 3.6'-3.8'
Test No. : GW993-ST-1
Sample Type: Undisturb

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 14 of 20
Stress increment from 8.00 (t/ft^2) to 16.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.88	32.86	0.1346	0.489	13.20
37)	1139.90	33.76	0.1346	0.489	13.20
38)	1199.88	34.64	0.1351	0.488	13.25
39)	1259.88	35.49	0.1346	0.489	13.20
40)	1319.90	36.33	0.1346	0.489	13.20
41)	1379.88	37.15	0.1351	0.488	13.25
42)	1439.70	37.94	0.1346	0.489	13.20

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 12 of 20
Stress increment from 2.00 (t/ft^2) to 4.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.88	32.86	0.0762	0.587	7.47
37)	1139.87	33.76	0.0762	0.587	7.47
38)	1199.87	34.64	0.0762	0.587	7.47
39)	1259.85	35.49	0.0762	0.587	7.47
40)	1319.85	36.33	0.0762	0.587	7.47
41)	1379.87	37.15	0.0762	0.587	7.47
42)	1387.98	37.26	0.0762	0.587	7.47

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW993-ST-1, 3.0'-5.0'
Project No.: 183923
Boring No.: GW993-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW993-ST-1
Test Date : 3-16-18
Depth : 3.6'-3.8'
Test No. : GW993-ST-1
Sample Type: Undisturb

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 15 of 20
Stress increment from 16.00 (t/ft^2) to 32.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.1494	0.464	14.64
2)	0.17	0.41	0.1514	0.461	14.84
3)	0.43	0.66	0.1534	0.457	15.04
4)	0.93	0.97	0.1560	0.453	15.29
5)	1.90	1.38	0.1595	0.447	15.64
6)	2.92	1.71	0.1615	0.444	15.84
7)	3.93	1.98	0.1631	0.441	15.99
8)	4.93	2.22	0.1641	0.439	16.09
9)	5.93	2.44	0.1646	0.439	16.14
10)	6.90	2.63	0.1651	0.438	16.19
11)	7.92	2.81	0.1661	0.436	16.29
12)	8.92	2.99	0.1656	0.437	16.24
13)	9.92	3.15	0.1661	0.436	16.29
14)	14.92	3.86	0.1671	0.434	16.39
15)	29.92	5.47	0.1681	0.433	16.49
16)	59.90	7.74	0.1692	0.431	16.58
17)	89.92	9.48	0.1697	0.430	16.63
18)	119.90	10.95	0.1697	0.430	16.63
19)	149.92	12.24	0.1697	0.430	16.63
20)	179.92	13.41	0.1702	0.429	16.68
21)	209.93	14.49	0.1702	0.429	16.68
22)	239.90	15.49	0.1702	0.429	16.68
23)	299.92	17.32	0.1707	0.428	16.73
24)	359.90	18.97	0.1712	0.427	16.78
25)	419.90	20.49	0.1712	0.427	16.78
26)	479.92	21.91	0.1712	0.427	16.78
27)	539.92	23.24	0.1712	0.427	16.78
28)	599.90	24.49	0.1712	0.427	16.78
29)	659.90	25.69	0.1717	0.427	16.83
30)	719.92	26.83	0.1712	0.427	16.78
31)	779.92	27.93	0.1717	0.427	16.83
32)	839.90	28.98	0.1717	0.427	16.83
33)	899.93	30.00	0.1717	0.427	16.83
34)	959.93	30.98	0.1717	0.427	16.83
35)	1019.92	31.94	0.1717	0.427	16.83

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 15 of 20
Stress increment from 16.00 (t/ft^2) to 32.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.1722	0.426	16.88
37)	1139.93	33.76	0.1722	0.426	16.88
38)	1199.90	34.64	0.1717	0.427	16.83
39)	1259.90	35.50	0.1722	0.426	16.88
40)	1319.90	36.33	0.1722	0.426	16.88
41)	1379.90	37.15	0.1722	0.426	16.88
42)	1436.83	37.91	0.1722	0.426	16.88

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 16 of 20
Stress increment from 32.00 (t/ft^2) to 16.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.1661	0.436	16.29
2)	0.15	0.39	0.1656	0.437	16.24
3)	0.42	0.65	0.1656	0.437	16.24
4)	0.90	0.95	0.1656	0.437	16.24
5)	1.92	1.38	0.1651	0.438	16.19
6)	2.92	1.71	0.1651	0.438	16.19
7)	3.90	1.97	0.1651	0.438	16.19
8)	4.92	2.22	0.1651	0.438	16.19
9)	5.92	2.43	0.1651	0.438	16.19
10)	6.92	2.63	0.1651	0.438	16.19
11)	7.92	2.81	0.1651	0.438	16.19
12)	8.92	2.99	0.1651	0.438	16.19
13)	9.95	3.15	0.1646	0.439	16.14
14)	14.90	3.86	0.1651	0.438	16.19
15)	29.93	5.47	0.1646	0.439	16.14
16)	59.92	7.74	0.1651	0.438	16.19
17)	89.92	9.48	0.1646	0.439	16.14
18)	119.93	10.95	0.1651	0.438	16.19
19)	149.90	12.24	0.1646	0.439	16.14
20)	179.90	13.41	0.1646	0.439	16.14
21)	209.90	14.49	0.1646	0.439	16.14
22)	239.90	15.49	0.1646	0.439	16.14
23)	299.92	17.32	0.1646	0.439	16.14
24)	359.90	18.97	0.1646	0.439	16.14
25)	419.93	20.49	0.1646	0.439	16.14
26)	479.92	21.91	0.1646	0.439	16.14
27)	539.92	23.24	0.1646	0.439	16.14
28)	599.90	24.49	0.1651	0.438	16.19
29)	659.93	25.69	0.1651	0.438	16.19
30)	719.92	26.83	0.1651	0.438	16.19
31)	779.90	27.93	0.1651	0.438	16.19
32)	839.90	28.98	0.1651	0.438	16.19
33)	899.88	30.00	0.1651	0.438	16.19
34)	959.92	30.98	0.1651	0.438	16.19
35)	1019.90	31.94	0.1646	0.439	16.14

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 16 of 20
Stress increment from 32.00 (t/ft^2) to 16.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.1646	0.439	16.14
37)	1139.90	33.76	0.1651	0.438	16.19
38)	1199.95	34.64	0.1646	0.439	16.14
39)	1259.93	35.50	0.1646	0.439	16.14
40)	1319.93	36.33	0.1646	0.439	16.14
41)	1379.90	37.15	0.1651	0.438	16.19
42)	1439.90	37.95	0.1646	0.439	16.14
43)	1499.95	38.73	0.1646	0.439	16.14
44)	1542.83	39.28	0.1646	0.439	16.14

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 17 of 20
Stress increment from 16.00 (t/ft^2) to 8.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.1575	0.451	15.44
2)	0.15	0.39	0.1575	0.451	15.44
3)	0.40	0.63	0.1570	0.451	15.39
4)	0.90	0.95	0.1570	0.451	15.39
5)	1.90	1.38	0.1565	0.452	15.34
6)	2.92	1.71	0.1565	0.452	15.34
7)	3.92	1.98	0.1565	0.452	15.34
8)	4.90	2.21	0.1565	0.452	15.34
9)	5.90	2.43	0.1565	0.452	15.34
10)	6.90	2.63	0.1565	0.452	15.34
11)	7.90	2.81	0.1565	0.452	15.34
12)	8.90	2.98	0.1560	0.453	15.29
13)	9.92	3.15	0.1560	0.453	15.29
14)	14.90	3.86	0.1560	0.453	15.29
15)	29.90	5.47	0.1560	0.453	15.29
16)	59.92	7.74	0.1554	0.454	15.24
17)	89.90	9.48	0.1554	0.454	15.24
18)	119.90	10.95	0.1554	0.454	15.24
19)	149.92	12.24	0.1554	0.454	15.24
20)	179.90	13.41	0.1560	0.453	15.29
21)	209.90	14.49	0.1554	0.454	15.24
22)	239.92	15.49	0.1560	0.453	15.29
23)	299.90	17.32	0.1560	0.453	15.29
24)	359.92	18.97	0.1560	0.453	15.29
25)	419.90	20.49	0.1560	0.453	15.29
26)	479.90	21.91	0.1554	0.454	15.24
27)	539.90	23.24	0.1549	0.455	15.19
28)	599.90	24.49	0.1554	0.454	15.24
29)	659.92	25.69	0.1554	0.454	15.24
30)	719.90	26.83	0.1549	0.455	15.19
31)	779.90	27.93	0.1549	0.455	15.19
32)	839.90	28.98	0.1554	0.454	15.24
33)	899.90	30.00	0.1554	0.454	15.24
34)	959.92	30.98	0.1554	0.454	15.24
35)	1019.90	31.94	0.1554	0.454	15.24

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 17 of 20
Stress increment from 16.00 (t/ft^2) to 8.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.1554	0.454	15.24
37)	1139.90	33.76	0.1554	0.454	15.24
38)	1199.90	34.64	0.1554	0.454	15.24
39)	1259.90	35.50	0.1554	0.454	15.24
40)	1319.90	36.33	0.1549	0.455	15.19
41)	1379.90	37.15	0.1554	0.454	15.24
42)	1439.90	37.95	0.1554	0.454	15.24
43)	1499.90	38.73	0.1549	0.455	15.19
44)	1559.88	39.50	0.1554	0.454	15.24
45)	1619.90	40.25	0.1554	0.454	15.24
46)	1679.90	40.99	0.1554	0.454	15.24
47)	1739.90	41.71	0.1554	0.454	15.24
48)	1799.90	42.43	0.1549	0.455	15.19
49)	1859.88	43.13	0.1549	0.455	15.19
50)	1919.90	43.82	0.1554	0.454	15.24
51)	1979.90	44.50	0.1554	0.454	15.24
52)	2039.90	45.17	0.1554	0.454	15.24
53)	2099.90	45.82	0.1554	0.454	15.24
54)	2159.88	46.47	0.1554	0.454	15.24
55)	2219.90	47.12	0.1554	0.454	15.24
56)	2279.88	47.75	0.1554	0.454	15.24
57)	2339.90	48.37	0.1554	0.454	15.24
58)	2399.90	48.99	0.1554	0.454	15.24
59)	2459.88	49.60	0.1554	0.454	15.24
60)	2519.90	50.20	0.1554	0.454	15.24
61)	2579.88	50.79	0.1554	0.454	15.24
62)	2639.90	51.38	0.1554	0.454	15.24
63)	2699.90	51.96	0.1554	0.454	15.24
64)	2759.88	52.53	0.1554	0.454	15.24
65)	2813.40	53.04	0.1549	0.455	15.19

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 18 of 20
Stress increment from 8.00 (t/ft^2) to 4.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.1499	0.463	14.69
2)	0.15	0.39	0.1499	0.463	14.69
3)	0.40	0.63	0.1494	0.464	14.64
4)	0.92	0.96	0.1488	0.465	14.59
5)	1.90	1.38	0.1488	0.465	14.59
6)	2.93	1.71	0.1483	0.466	14.54
7)	3.90	1.97	0.1483	0.466	14.54
8)	4.90	2.21	0.1483	0.466	14.54
9)	5.92	2.43	0.1483	0.466	14.54
10)	6.90	2.63	0.1483	0.466	14.54
11)	7.90	2.81	0.1478	0.467	14.49
12)	8.90	2.98	0.1483	0.466	14.54
13)	9.90	3.15	0.1483	0.466	14.54
14)	14.90	3.86	0.1478	0.467	14.49
15)	29.92	5.47	0.1478	0.467	14.49
16)	59.92	7.74	0.1473	0.468	14.44
17)	89.92	9.48	0.1478	0.467	14.49
18)	119.90	10.95	0.1473	0.468	14.44
19)	149.92	12.24	0.1473	0.468	14.44
20)	179.90	13.41	0.1468	0.468	14.39
21)	209.90	14.49	0.1473	0.468	14.44
22)	239.90	15.49	0.1468	0.468	14.39
23)	299.93	17.32	0.1468	0.468	14.39
24)	359.93	18.97	0.1468	0.468	14.39
25)	419.90	20.49	0.1468	0.468	14.39
26)	479.92	21.91	0.1468	0.468	14.39
27)	539.90	23.24	0.1468	0.468	14.39
28)	599.95	24.49	0.1468	0.468	14.39
29)	659.90	25.69	0.1468	0.468	14.39
30)	719.92	26.83	0.1468	0.468	14.39
31)	779.90	27.93	0.1468	0.468	14.39
32)	839.90	28.98	0.1468	0.468	14.39
33)	899.90	30.00	0.1468	0.468	14.39
34)	959.90	30.98	0.1468	0.468	14.39
35)	1019.88	31.94	0.1468	0.468	14.39

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 18 of 20
Stress increment from 8.00 (t/ft^2) to 4.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.1468	0.468	14.39
37)	1139.90	33.76	0.1468	0.468	14.39
38)	1199.90	34.64	0.1468	0.468	14.39
39)	1259.90	35.50	0.1468	0.468	14.39
40)	1319.90	36.33	0.1463	0.469	14.34
41)	1379.88	37.15	0.1463	0.469	14.34
42)	1407.02	37.51	0.1463	0.469	14.34

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW993-ST-1, 3.0'-5.0'
Project No.: 183923
Boring No.: GW993-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW993-ST-1
Test Date : 3-16-18
Depth : 3.6'-3.8'
Test No. : GW993-ST-1
Sample Type: Undisturb

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 19 of 20
Stress increment from 4.00 (t/ft^2) to 2.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.1427	0.475	13.99
2)	0.18	0.43	0.1422	0.476	13.95
3)	0.42	0.65	0.1422	0.476	13.95
4)	0.92	0.96	0.1422	0.476	13.95
5)	1.92	1.38	0.1417	0.477	13.90
6)	2.92	1.71	0.1417	0.477	13.90
7)	3.90	1.97	0.1412	0.478	13.85
8)	4.93	2.22	0.1412	0.478	13.85
9)	5.90	2.43	0.1412	0.478	13.85
10)	6.93	2.63	0.1412	0.478	13.85
11)	7.93	2.82	0.1407	0.479	13.80
12)	8.90	2.98	0.1407	0.479	13.80
13)	9.92	3.15	0.1407	0.479	13.80
14)	14.92	3.86	0.1402	0.480	13.75
15)	29.90	5.47	0.1402	0.480	13.75
16)	59.90	7.74	0.1397	0.480	13.70
17)	89.92	9.48	0.1397	0.480	13.70
18)	119.92	10.95	0.1397	0.480	13.70
19)	149.90	12.24	0.1397	0.480	13.70
20)	179.90	13.41	0.1397	0.480	13.70
21)	209.93	14.49	0.1392	0.481	13.65
22)	239.92	15.49	0.1392	0.481	13.65
23)	299.90	17.32	0.1392	0.481	13.65
24)	359.90	18.97	0.1387	0.482	13.60
25)	419.90	20.49	0.1392	0.481	13.65
26)	479.92	21.91	0.1387	0.482	13.60
27)	539.92	23.24	0.1387	0.482	13.60
28)	599.93	24.49	0.1392	0.481	13.65
29)	659.95	25.69	0.1387	0.482	13.60
30)	719.92	26.83	0.1392	0.481	13.65
31)	779.92	27.93	0.1392	0.481	13.65
32)	839.92	28.98	0.1387	0.482	13.60
33)	899.92	30.00	0.1392	0.481	13.65
34)	959.90	30.98	0.1387	0.482	13.60
35)	1019.90	31.94	0.1387	0.482	13.60

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 19 of 20
Stress increment from 4.00 (t/ft^2) to 2.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.92	32.86	0.1387	0.482	13.60
37)	1139.93	33.76	0.1392	0.481	13.65
38)	1199.93	34.64	0.1387	0.482	13.60
39)	1259.90	35.50	0.1392	0.481	13.65
40)	1319.90	36.33	0.1387	0.482	13.60
41)	1379.90	37.15	0.1387	0.482	13.60
42)	1421.33	37.70	0.1387	0.482	13.60

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 20 of 20
Stress increment from 2.00 (t/ft^2) to 1.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.1372	0.485	13.45
2)	0.15	0.39	0.1367	0.486	13.40
3)	0.40	0.63	0.1361	0.486	13.35
4)	0.88	0.94	0.1367	0.486	13.40
5)	1.90	1.38	0.1356	0.487	13.30
6)	2.90	1.70	0.1356	0.487	13.30
7)	3.90	1.97	0.1356	0.487	13.30
8)	4.90	2.21	0.1351	0.488	13.25
9)	5.92	2.43	0.1351	0.488	13.25
10)	6.88	2.62	0.1351	0.488	13.25
11)	7.90	2.81	0.1351	0.488	13.25
12)	8.92	2.99	0.1346	0.489	13.20
13)	9.88	3.14	0.1346	0.489	13.20
14)	14.88	3.86	0.1346	0.489	13.20
15)	29.92	5.47	0.1341	0.490	13.15
16)	59.90	7.74	0.1336	0.491	13.10
17)	89.88	9.48	0.1336	0.491	13.10
18)	119.88	10.95	0.1336	0.491	13.10
19)	149.92	12.24	0.1331	0.492	13.05
20)	179.88	13.41	0.1331	0.492	13.05
21)	209.90	14.49	0.1331	0.492	13.05
22)	239.90	15.49	0.1331	0.492	13.05
23)	299.90	17.32	0.1326	0.492	13.00
24)	359.93	18.97	0.1331	0.492	13.05
25)	419.88	20.49	0.1326	0.492	13.00
26)	479.90	21.91	0.1326	0.492	13.00
27)	539.88	23.24	0.1326	0.492	13.00
28)	599.88	24.49	0.1326	0.492	13.00
29)	659.92	25.69	0.1326	0.492	13.00
30)	719.88	26.83	0.1326	0.492	13.00
31)	779.88	27.93	0.1326	0.492	13.00
32)	839.92	28.98	0.1326	0.492	13.00
33)	899.88	30.00	0.1326	0.492	13.00
34)	959.88	30.98	0.1326	0.492	13.00
35)	1019.88	31.94	0.1326	0.492	13.00

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW993-ST-1, 3.0'-5.0'	Project No.: 183923
Boring No.: GW993-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW993-ST-1	Test Date : 3-16-18	Depth : 3.6'-3.8'
Test No. : GW993-ST-1	Sample Type: Undisturb	

Soil Description : brown clayey silt (visual description)
Remarks : Use: Fill, Near foundation/geobuffer layer

Load Increment : 20 of 20
Stress increment from 2.00 (t/ft^2) to 1.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.88	32.86	0.1326	0.492	13.00
37)	1139.92	33.76	0.1321	0.493	12.95
38)	1199.90	34.64	0.1321	0.493	12.95
39)	1259.88	35.49	0.1321	0.493	12.95
40)	1319.88	36.33	0.1321	0.493	12.95
41)	1379.88	37.15	0.1321	0.493	12.95
42)	1439.88	37.95	0.1321	0.493	12.95
43)	1444.40	38.01	0.1321	0.493	12.95

BOWSER-MORNER, INC.

Delivery Address: 4518 Taylorsville Road • Dayton, Ohio 45424 **Mailing Address**: P. O. Box 51 • Dayton, Ohio 45401

AASHTO/ISO 17025 Accredited • USACE Validated

LABORATORY REPORT

Report To: CTI & Associates, Inc.
Attn: Michael Partenio
28001 Cabot Drive, Ste. 250
Novi, MI 48377

Report Date: May 3, 2018
Job No.: 183923
Report No.: 430248
No. of Pages: 3

Report On: Laboratory Analysis of One Shelby Tube Sample
Project: EMDF Characterization – Project No. 1188070011
Sample ID: GW993 – ST-1, 3.0'-5.0' – Sample Date: 2/22/18

On March 5, 2018, one Shelby tube sample was submitted for selected laboratory analysis from the above referenced project. Testing was performed as specified by the client and in accordance with ASTM D 4767, "Consolidated-Undrained Triaxial Compression Test on Cohesive Soils".

Results are summarized below and detailed on the attached data sheets.

Test Parameter	Test No.1	Test No. 2	Test No. 3
Dry Density, pcf:	**102.14**	**100.35**	**100.05**
Moisture Content, %:	**22.47**	**25.41**	**25.51**
Minor Principle Stress, psi:	**5.69**	**12.39**	**32.39**
Maximum Deviator Stress, psi:	**21.30**	**24.07**	**22.39**
Cohesion (c'), psi:	**0.0**		
phi Angle (Ø'):	**30.0**		
Apparent Specific Gravity:	**2.73**		

Should you have any questions, or if we may be of further service, please contact me at (937) 236-8805 extension 322.

Respectfully submitted,


BOWSER-MORNER, INC.

Karl A. Fletcher, Manager
Construction Materials and
Geotechnical Laboratories


KAF/blc
430248
1-File
1-mpartenio@cticompanies.com
1-kfoye@cticompanies.com


All Reports Remain The Confidential Property Of BOWSER-MORNER And No Publication Or Distribution Of Reports May Be Made Without Our Express Written Consent, Except As Authorized By Contract. Results Contained In This Report Are Reflective Only of The Items Calibrated or Tested. Unless Otherwise Agreed, Samples Or Specimens Will Be Discarded Or Returned At Bowser-Morner's Discretion. AASHTO/ISO 17025 Accreditation applies only to the parameters included in BOWSER-MORNER'S current scope of accreditation. Go to www.bowser-morner.com/accreditations for reviews.

$Ø' = \sin^{-1} 0.5 = 30.0°$



FAILURE SKETCHES





SYMBOL		O	Δ	□	
TEST NO.		1	2	3	
INITIAL	WATER CONTENT (%)	22.47	25.41	25.51	
	DRY DENSITY (lb/ft^3)	102.14	100.35	100.05	
	SATURATION (%)	91.66	99.23	98.93	
	VOID RATIO	0.670	0.700	0.705	
BEFORE SHEAR	WATER CONTENT (%)	24.01	24.44	22.88	
	DRY DENSITY (lb/ft^3)	102.08	102.03	104.37	
	SATURATION (%)	97.81	99.44	98.58	
	VOID RATIO	0.671	0.672	0.635	
	BACK PRESS. (lb/in^2)	49.31	52.61	47.61	
MINOR PRIN. STRESS (lb/in^2)		5.69	12.39	32.39	
MAX. DEV. STRESS (lb/in^2)		21.30	24.07	22.39	
TIME TO FAILURE (min)		1249	939	891	
RATE OF STRAIN INCR (%/min)		0.02	0.02	0.02	
INITIAL DIAMETER (in)		2.84	2.82	2.84	
INITIAL HEIGHT (in)		5.79	5.78	5.93	

CONTROLLED STRAIN TEST

DESCRIPTION OF SPECIMENS: 1) brown clay, little gravel (visual description) 2) brown clay, little gravel (visual description)
3) brown clay, little gravel (visual description)


LL	PL	PI	GS 2.73	TYPE OF SPECIMEN 1	TYPE OF TEST CU (R)

REMARKS:
1) Client: CTI & Associates, Inc.
2) Use: Fill, Near foundation/ geobuffer layer
3) Sample Date: 2-22-18

PROJECT EMDF Characterization
PROJECT NO.183923

BORING NO. GW993-ST-1	SAMPLE NO.	1	2	3	
TECH. BMI: blc	DEPTH/ELEV	3.0-3.5'	3.9-5.1'	6.5-7.0'	
LABORATORY	DATE	4-20-18	4-23-18	4-24-18	

TRIAXIAL COMPRESSION TEST REPORT



Project Name : EMDF Characterization				
Boring No: Sample No	Depth	Test No	Filename	Symbol
GW993-ST-11	3.0-3.5'	1	c:\geocomp\392311	○
GW993-ST-12	3.9-5.1'	2	c:\geocomp\392312	△
GW993-ST-23	6.5-7.0'	3	c:\geocomp\392313	□

BOWSER-MORNER, INC.

Delivery Address: 4518 Taylorsville Road • Dayton, Ohio 45424 **Mailing Address**: P. O. Box 51 • Dayton, Ohio 45401

AASHTO/ISO 17025 Accredited • USACE Validated ACIL INDEPENDENCE

LABORATORY REPORT

Report To: CTI & Associates, Inc.
Attn: Michael Partenio
28001 Cabot Drive, Ste. 250
Novi, MI 48377

Report Date: May 3, 2018
Job No.: 183923
Report No.: 430245
No. of Pages: 1

Report On: Laboratory Analysis of One Shelby Tube Sample
Project: EMDF Characterization – Project No. 1188070011
Sample ID: GW993 – ST-1, 3.0'-5.0' – Sample Date: 2/22/18

On March 5, 2018, one Shelby tube sample was submitted for selected laboratory analysis from the above referenced project. Testing was performed as specified by the client and in accordance with the following procedures:

ASTM D 854, "Specific Gravity of Soils Solids by Water Pycnometer".
ASTM D 2216, "Laboratory Determination of Water (Moisture) Content of Soil and Rock".
ASTM D 7263, "Laboratory Determination of Density (Unit Weight) of Soil Specimens – Method B".

Results are summarized in the following table.

Test Parameter	Results
Depth of Test Specimen:	**3.9'-5.1'**
As Received Moisture Content, %:	**25.4**
Apparent Specific Gravity:	**2.73**
Wet Unit Weight, pcf:	**125.9**
Dry Unit Weight, pcf:	**100.4**
Void Ratio:	**0.6978**
Porosity, %:	**41.1**
Degree of Saturation, %:	**99.4**
Volume of Water, %:	**40.9**
Volume of Solids, %:	**58.9**
Air Filled Voids, %:	**0.6**
Water Filled Voids, %:	**99.4**


Should you have any questions, or if we may be of further service, please contact me at (937) 236-8805, extension 322.

Respectfully submitted,
BOWSER-MORNER, INC.

Karl A. Fletcher, Manager
Construction Materials and
Geotechnical Laboratories

KAF/blc
430245
1-File
1-mpartenio@cticompanies.com
1-kfoye@cticompanies.com

All Reports Remain The Confidential Property Of BOWSER-MORNER And No Publication Or Distribution Of Reports May Be Made Without Our Express Written Consent, Except As Authorized By Contract. Results Contained In This Report Are Reflective Only of The Items Calibrated or Tested. Unless Otherwise Agreed, Samples Or Specimens Will Be Discarded Or Returned At Bowser-Morner's Discretion. AASHTO/ISO 17025 Accreditation applies only to the parameters included in BOWSER-MORNER'S current scope of accreditation. Go to www.bowser-morner.com/accreditations for reviews.




			BEFORE TEST	AFTER TEST
OVERBURDEN PRESSURE (t/ft^2)		WATER CONTENT (%)	22.2	19.3
PRECONSOL. PRESSURE (t/ft^2)		DRY DENSITY (lb/ft^3)	103.68	110.48
COMPRESSION INDEX		SATURATION (%)	94.56	97.73
TYPE SPECIMEN	Undisturb	VOID RATIO	0.64	0.54
DIA. (in) 2.500	HT. (in) 1.000	BACK PRESSURE (t/ft^2)	---	---


CLASSIFICATION red/brown clayey silt (visual description)

LL ---	PL ---	PI ---	PROJECT EMDF Characterization
GS 2.721	D_{10}		995ST1
REMARKS		BORING NO. GW995-ST-1	SAMPLE NO. GW995-ST-1
Use: Near foundation/geobuffer layer		DEPTH 3.8'-4.0'	DATE 3-15-18

Bowser Morner
CONSOLIDATION TEST REPORT


CONSOLIDATION TEST
TIME CURVES (STEP 1 OF 20)
STRESS : 0.06 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-1 Sample No : GW995-ST-1
Test Date : 3-15-18 Test No : GW995-ST-1 Depth :
Description : red/brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 2 OF 20)
STRESS : 0.25 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-1 Sample No : GW995-ST-1
Test Date : 3-15-18 Test No : GW995-ST-1 Depth :
Description : red/brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 3 OF 20)
STRESS : 0.5 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-1 Sample No : GW995-ST-1
Test Date : 3-15-18 Test No : GW995-ST-1 Depth :
Description : red/brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 4 OF 20)
STRESS : 1 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-1 Sample No : GW995-ST-1
Test Date : 3-15-18 Test No : GW995-ST-1 Depth :
Description : red/brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 5 OF 20)
STRESS : 2 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-1 Sample No : GW995-ST-1
Test Date : 3-15-18 Test No : GW995-ST-1 Depth :
Description : red/brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 6 OF 20)
STRESS : 4 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-1 Sample No : GW995-ST-1
Test Date : 3-15-18 Test No : GW995-ST-1 Depth :
Description : red/brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 7 OF 20)
STRESS : 2 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-1 Sample No : GW995-ST-1
Test Date : 3-15-18 Test No : GW995-ST-1 Depth :
Description : red/brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 8 OF 20)
STRESS : 1 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-1 Sample No : GW995-ST-1
Test Date : 3-15-18 Test No : GW995-ST-1 Depth :
Description : red/brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 9 OF 20)
STRESS : 0.5 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-1 Sample No : GW995-ST-1
Test Date : 3-15-18 Test No : GW995-ST-1 Depth :
Description : red/brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 10 OF 20)
STRESS : 1 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-1 Sample No : GW995-ST-1
Test Date : 3-15-18 Test No : GW995-ST-1 Depth :
Description : red/brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 11 OF 20)
STRESS : 2 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-1 Sample No : GW995-ST-1
Test Date : 3-15-18 Test No : GW995-ST-1 Depth :
Description : red/brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 12 OF 20)
STRESS : 4 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-1 Sample No : GW995-ST-1
Test Date : 3-15-18 Test No : GW995-ST-1 Depth :
Description : red/brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 13 OF 20)
STRESS : 8 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-1 Sample No : GW995-ST-1
Test Date : 3-15-18 Test No : GW995-ST-1 Depth :
Description : red/brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 14 OF 20)
STRESS : 16 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-1 Sample No : GW995-ST-1
Test Date : 3-15-18 Test No : GW995-ST-1 Depth :
Description : red/brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 15 OF 20)
STRESS : 32 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-1 Sample No : GW995-ST-1
Test Date : 3-15-18 Test No : GW995-ST-1 Depth :
Description : red/brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 16 OF 20)
STRESS : 16 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-1 Sample No : GW995-ST-1
Test Date : 3-15-18 Test No : GW995-ST-1 Depth :
Description : red/brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 17 OF 20)
STRESS : 8 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-1 Sample No : GW995-ST-1
Test Date : 3-15-18 Test No : GW995-ST-1 Depth :
Description : red/brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 18 OF 20)
STRESS : 4 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-1 Sample No : GW995-ST-1
Test Date : 3-15-18 Test No : GW995-ST-1 Depth :
Description : red/brown clayey silt (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 19 OF 20)
STRESS : 2 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-1 Sample No : GW995-ST-1
Test Date : 3-15-18 Test No : GW995-ST-1 Depth :
Description : red/brown clayey silt (visual description)

CONSOLIDATION TEST
TIME CURVES (STEP 20 OF 20)
STRESS : 1 (t/ft^2)





Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-1 Sample No : GW995-ST-1
Test Date : 3-15-18 Test No : GW995-ST-1 Depth :
Description : red/brown clayey silt (visual description)

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW995-ST-1, 2.5'-4.5'
Project No.: 183923
Boring No.: GW995-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW995-ST-1
Test Date : 3-15-18
Depth : 3.8'-4.0'
Test No. : GW995-ST-1
Sample Type: Undisturb

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

	APPLIED PRESSURE (t/ft^2)	FINAL DISPLACEMENT (in)	VOID RATIO	STRAIN AT END (%)	FITTING T50 TIME (min) SQ.RT.	FITTING T50 TIME (min) LOG	COEFFICIENT OF CONSOLIDATION (in^2/s) SQ.RT.	COEFFICIENT OF CONSOLIDATION (in^2/s) LOG	COEFFICIENT OF CONSOLIDATION (in^2/s) AVE
1)	0.06	-0.004	0.644	-0.35	0.0	0.0	0.00E+000	0.00E+000	0.00E+000
2)	0.25	-0.004	0.644	-0.35	0.0	0.0	0.00E+000	0.00E+000	0.00E+000
3)	0.50	-0.002	0.642	-0.20	0.0	0.0	0.00E+000	0.00E+000	0.00E+000
4)	1.00	0.002	0.635	0.21	0.0	0.0	0.00E+000	0.00E+000	0.00E+000
5)	2.00	0.012	0.618	1.23	8.1	0.0	1.00E-004	0.00E+000	1.00E-004
6)	4.00	0.029	0.591	2.91	3.6	3.3	2.18E-004	2.40E-004	2.29E-004
7)	2.00	0.025	0.597	2.50	0.0	0.0	0.00E+000	0.00E+000	0.00E+000
8)	1.00	0.018	0.609	1.79	8.8	0.0	8.91E-005	0.00E+000	8.91E-005
9)	0.50	0.012	0.618	1.23	0.0	0.0	0.00E+000	0.00E+000	0.00E+000
10)	1.00	0.014	0.615	1.43	0.0	0.0	0.00E+000	0.00E+000	0.00E+000
11)	2.00	0.021	0.604	2.09	0.9	0.0	9.01E-004	0.00E+000	9.01E-004
12)	4.00	0.031	0.587	3.11	3.0	0.0	2.59E-004	0.00E+000	2.59E-004
13)	8.00	0.052	0.553	5.20	3.5	0.0	2.14E-004	0.00E+000	2.14E-004
14)	16.00	0.080	0.507	8.00	2.2	0.0	3.25E-004	0.00E+000	3.25E-004
15)	32.00	0.116	0.448	11.61	2.2	0.0	3.02E-004	0.00E+000	3.02E-004
16)	16.00	0.107	0.462	10.74	1.2	0.0	5.39E-004	0.00E+000	5.39E-004
17)	8.00	0.097	0.480	9.68	2.9	0.0	2.29E-004	0.00E+000	2.29E-004
18)	4.00	0.086	0.498	8.56	13.4	0.0	5.04E-005	0.00E+000	5.04E-005
19)	2.00	0.073	0.518	7.33	19.8	0.0	3.52E-005	0.00E+000	3.52E-005
20)	1.00	0.062	0.537	6.16	16.0	0.0	4.47E-005	0.00E+000	4.47E-005

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW995-ST-1, 2.5'-4.5'	Project No.: 183923
Boring No.: GW995-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW995-ST-1	Test Date : 3-15-18	Depth : 3.8'-4.0'
Test No. : GW995-ST-1	Sample Type: Undisturb	

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Specific Gravity : 2.72	Liquid Limit : 0	Initial Height : 1.00 (in)
Initial Void Ratio : 0.64	Plastic Limit : 0	Sample Diameter : 2.50 (in)
Final Void Ratio : 0.54	Plasticity Index : 0	

	BEFORE CONSOLIDATION		AFTER CONSOLIDATION	
	TRIMMINGS	SPECIMEN + RING	SPECIMEN + RING	TRIMMINGS
CONTAINER NO.		RING	RING	
WT CONTAINER + WET SOIL (gm)	163.23	163.23	159.38	159.38
WT CONTAINER + DRY SOIL (gm)	133.59	133.59	133.59	133.59
WT CONTAINER (gm)	0.00	0.00	0.00	0.00
WT DRY SOIL (gm)	133.59	133.59	133.59	133.59
WATER CONTENT (%)	22.19	22.19	19.31	19.31
VOID RATIO	------	0.64	0.54	------
DEGREE OF SATURATION (%)	------	94.56	97.73	------
DRY DENSITY (lb/ft^3)	------	103.68	110.48	------

Note: Specific Gravity and Void Ratios are calculated assuming the degree of saturation equals 100% at the end of the test. Therefor values may not represent actual values for the specimen.

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW995-ST-1, 2.5'-4.5'
Project No.: 183923
Boring No.: GW995-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW995-ST-1
Test Date : 3-15-18
Depth : 3.8'-4.0'
Test No. : GW995-ST-1
Sample Type: Undisturb

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 1 of 20
Stress increment from 0.00 (t/ft^2) to 0.06 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.15	0.39	0.0000	0.638	0.00
2)	0.90	0.95	0.0000	0.638	0.00
3)	2.90	1.70	0.0000	0.638	0.00
4)	3.90	1.97	0.0000	0.638	0.00
5)	5.90	2.43	-0.0036	0.644	-0.36

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW995-ST-1, 2.5'-4.5'
Project No.: 183923
Boring No.: GW995-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW995-ST-1
Test Date : 3-15-18
Depth : 3.8'-4.0'
Test No. : GW995-ST-1
Sample Type: Undisturb

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 2 of 20
Stress increment from 0.06 (t/ft^2) to 0.25 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	-0.0031	0.643	-0.31
2)	0.15	0.39	-0.0036	0.644	-0.36
3)	0.40	0.63	-0.0036	0.644	-0.36
4)	0.90	0.95	-0.0036	0.644	-0.36
5)	1.90	1.38	-0.0031	0.643	-0.31
6)	2.92	1.71	-0.0036	0.644	-0.36
7)	3.92	1.98	-0.0036	0.644	-0.36
8)	4.92	2.22	-0.0031	0.643	-0.31
9)	5.90	2.43	-0.0036	0.644	-0.36
10)	6.90	2.63	-0.0036	0.644	-0.36
11)	7.90	2.81	-0.0031	0.643	-0.31
12)	8.90	2.98	-0.0036	0.644	-0.36
13)	9.90	3.15	-0.0036	0.644	-0.36
14)	14.90	3.86	-0.0036	0.644	-0.36
15)	29.90	5.47	-0.0031	0.643	-0.31
16)	59.92	7.74	-0.0031	0.643	-0.31
17)	89.90	9.48	-0.0031	0.643	-0.31
18)	119.90	10.95	-0.0031	0.643	-0.31
19)	149.92	12.24	-0.0036	0.644	-0.36
20)	179.92	13.41	-0.0031	0.643	-0.31
21)	209.90	14.49	-0.0031	0.643	-0.31
22)	239.90	15.49	-0.0031	0.643	-0.31
23)	299.90	17.32	-0.0031	0.643	-0.31
24)	359.92	18.97	-0.0036	0.644	-0.36
25)	419.90	20.49	-0.0031	0.643	-0.31
26)	479.92	21.91	-0.0031	0.643	-0.31
27)	539.90	23.24	-0.0031	0.643	-0.31
28)	599.90	24.49	-0.0031	0.643	-0.31
29)	659.90	25.69	-0.0031	0.643	-0.31
30)	719.90	26.83	-0.0031	0.643	-0.31
31)	779.92	27.93	-0.0031	0.643	-0.31
32)	839.90	28.98	-0.0031	0.643	-0.31
33)	899.90	30.00	-0.0031	0.643	-0.31
34)	959.90	30.98	-0.0031	0.643	-0.31
35)	1019.90	31.94	-0.0031	0.643	-0.31

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW995-ST-1, 2.5'-4.5'
Project No.: 183923
Boring No.: GW995-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW995-ST-1
Test Date : 3-15-18
Depth : 3.8'-4.0'
Test No. : GW995-ST-1
Sample Type: Undisturb

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 2 of 20
Stress increment from 0.06 (t/ft^2) to 0.25 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	-0.0031	0.643	-0.31
37)	1139.90	33.76	-0.0031	0.643	-0.31
38)	1199.92	34.64	-0.0031	0.643	-0.31
39)	1259.90	35.50	-0.0031	0.643	-0.31
40)	1319.90	36.33	-0.0031	0.643	-0.31
41)	1379.90	37.15	-0.0025	0.643	-0.25
42)	1391.47	37.30	-0.0036	0.644	-0.36

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW995-ST-1, 2.5'-4.5'
Project No.: 183923
Boring No.: GW995-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW995-ST-1
Test Date : 3-15-18
Depth : 3.8'-4.0'
Test No. : GW995-ST-1
Sample Type: Undisturb

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 3 of 20
Stress increment from 0.25 (t/ft^2) to 0.50 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	-0.0025	0.643	-0.25
2)	0.13	0.37	-0.0025	0.643	-0.25
3)	0.40	0.63	-0.0025	0.643	-0.25
4)	0.90	0.95	-0.0025	0.643	-0.25
5)	1.88	1.37	-0.0025	0.643	-0.25
6)	2.92	1.71	-0.0020	0.642	-0.20
7)	3.93	1.98	-0.0025	0.643	-0.25
8)	4.93	2.22	-0.0025	0.643	-0.25
9)	5.93	2.44	-0.0020	0.642	-0.20
10)	6.90	2.63	-0.0025	0.643	-0.25
11)	7.90	2.81	-0.0025	0.643	-0.25
12)	8.90	2.98	-0.0025	0.643	-0.25
13)	9.90	3.15	-0.0025	0.643	-0.25
14)	14.90	3.86	-0.0020	0.642	-0.20
15)	29.88	5.47	-0.0015	0.641	-0.15
16)	59.90	7.74	-0.0020	0.642	-0.20
17)	89.90	9.48	-0.0015	0.641	-0.15
18)	119.90	10.95	-0.0020	0.642	-0.20
19)	149.90	12.24	-0.0015	0.641	-0.15
20)	179.90	13.41	-0.0020	0.642	-0.20
21)	209.92	14.49	-0.0015	0.641	-0.15
22)	239.90	15.49	-0.0020	0.642	-0.20
23)	299.90	17.32	-0.0020	0.642	-0.20
24)	359.88	18.97	-0.0020	0.642	-0.20
25)	419.90	20.49	-0.0020	0.642	-0.20
26)	479.92	21.91	-0.0020	0.642	-0.20
27)	539.88	23.24	-0.0020	0.642	-0.20
28)	599.90	24.49	-0.0015	0.641	-0.15
29)	659.90	25.69	-0.0015	0.641	-0.15
30)	719.88	26.83	-0.0020	0.642	-0.20
31)	779.90	27.93	-0.0020	0.642	-0.20
32)	839.88	28.98	-0.0015	0.641	-0.15
33)	899.90	30.00	-0.0020	0.642	-0.20
34)	959.88	30.98	-0.0020	0.642	-0.20
35)	1019.92	31.94	-0.0020	0.642	-0.20

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW995-ST-1, 2.5'-4.5'	Project No.: 183923
Boring No.: GW995-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW995-ST-1	Test Date : 3-15-18	Depth : 3.8'-4.0'
Test No. : GW995-ST-1	Sample Type: Undisturb	

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 3 of 20
Stress increment from 0.25 (t/ft^2) to 0.50 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.88	32.86	-0.0020	0.642	-0.20
37)	1139.88	33.76	-0.0020	0.642	-0.20
38)	1199.88	34.64	-0.0015	0.641	-0.15
39)	1259.90	35.50	-0.0015	0.641	-0.15
40)	1298.28	36.03	-0.0020	0.642	-0.20

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW995-ST-1, 2.5'-4.5'
Project No.: 183923
Boring No.: GW995-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW995-ST-1
Test Date : 3-15-18
Depth : 3.8'-4.0'
Test No. : GW995-ST-1
Sample Type: Undisturb

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 4 of 20
Stress increment from 0.50 (t/ft^2) to 1.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0000	0.638	0.00
2)	0.15	0.39	0.0000	0.638	0.00
3)	0.40	0.63	0.0005	0.638	0.05
4)	0.90	0.95	0.0005	0.638	0.05
5)	1.90	1.38	0.0005	0.638	0.05
6)	2.88	1.70	0.0005	0.638	0.05
7)	3.92	1.98	0.0005	0.638	0.05
8)	4.90	2.21	0.0005	0.638	0.05
9)	5.90	2.43	0.0010	0.637	0.10
10)	6.90	2.63	0.0010	0.637	0.10
11)	7.90	2.81	0.0010	0.637	0.10
12)	8.92	2.99	0.0010	0.637	0.10
13)	9.92	3.15	0.0010	0.637	0.10
14)	14.92	3.86	0.0010	0.637	0.10
15)	29.90	5.47	0.0010	0.637	0.10
16)	59.90	7.74	0.0010	0.637	0.10
17)	89.88	9.48	0.0015	0.636	0.15
18)	119.92	10.95	0.0015	0.636	0.15
19)	149.92	12.24	0.0015	0.636	0.15
20)	179.90	13.41	0.0015	0.636	0.15
21)	209.88	14.49	0.0015	0.636	0.15
22)	239.90	15.49	0.0015	0.636	0.15
23)	299.92	17.32	0.0015	0.636	0.15
24)	359.92	18.97	0.0015	0.636	0.15
25)	419.88	20.49	0.0020	0.635	0.20
26)	479.92	21.91	0.0015	0.636	0.15
27)	539.90	23.24	0.0015	0.636	0.15
28)	599.90	24.49	0.0020	0.635	0.20
29)	659.90	25.69	0.0020	0.635	0.20
30)	719.92	26.83	0.0020	0.635	0.20
31)	779.90	27.93	0.0020	0.635	0.20
32)	839.88	28.98	0.0020	0.635	0.20
33)	899.90	30.00	0.0020	0.635	0.20
34)	959.90	30.98	0.0020	0.635	0.20
35)	1019.88	31.94	0.0020	0.635	0.20

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW995-ST-1, 2.5'-4.5'	Project No.: 183923
Boring No.: GW995-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW995-ST-1	Test Date : 3-15-18	Depth : 3.8'-4.0'
Test No. : GW995-ST-1	Sample Type: Undisturb	

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 4 of 20
Stress increment from 0.50 (t/ft^2) to 1.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.0020	0.635	0.20
37)	1139.90	33.76	0.0020	0.635	0.20
38)	1199.90	34.64	0.0020	0.635	0.20
39)	1259.88	35.49	0.0036	0.633	0.36
40)	1309.58	36.19	0.0020	0.635	0.20

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW995-ST-1, 2.5'-4.5'	Project No.: 183923
Boring No.: GW995-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW995-ST-1	Test Date : 3-15-18	Depth : 3.8'-4.0'
Test No. : GW995-ST-1	Sample Type: Undisturb	

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 5 of 20
Stress increment from 1.00 (t/ft^2) to 2.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0071	0.627	0.71
2)	0.15	0.39	0.0076	0.626	0.76
3)	0.42	0.65	0.0076	0.626	0.76
4)	0.92	0.96	0.0087	0.624	0.87
5)	1.92	1.38	0.0092	0.623	0.92
6)	2.92	1.71	0.0097	0.623	0.97
7)	3.92	1.98	0.0097	0.623	0.97
8)	4.90	2.21	0.0102	0.622	1.02
9)	5.92	2.43	0.0102	0.622	1.02
10)	6.95	2.64	0.0102	0.622	1.02
11)	7.95	2.82	0.0102	0.622	1.02
12)	8.90	2.98	0.0107	0.621	1.07
13)	9.92	3.15	0.0107	0.621	1.07
14)	14.92	3.86	0.0107	0.621	1.07
15)	29.92	5.47	0.0117	0.619	1.17
16)	59.92	7.74	0.0122	0.618	1.22
17)	89.90	9.48	0.0122	0.618	1.22
18)	119.90	10.95	0.0127	0.618	1.27
19)	149.93	12.24	0.0127	0.618	1.27
20)	179.90	13.41	0.0127	0.618	1.27
21)	209.92	14.49	0.0127	0.618	1.27
22)	239.92	15.49	0.0127	0.618	1.27
23)	299.93	17.32	0.0127	0.618	1.27
24)	359.93	18.97	0.0122	0.618	1.22
25)	419.90	20.49	0.0127	0.618	1.27
26)	479.92	21.91	0.0127	0.618	1.27
27)	539.90	23.24	0.0127	0.618	1.27
28)	599.93	24.49	0.0127	0.618	1.27
29)	659.90	25.69	0.0127	0.618	1.27
30)	719.92	26.83	0.0127	0.618	1.27
31)	779.92	27.93	0.0127	0.618	1.27
32)	839.92	28.98	0.0127	0.618	1.27
33)	899.90	30.00	0.0127	0.618	1.27
34)	959.90	30.98	0.0132	0.617	1.32
35)	1019.93	31.94	0.0127	0.618	1.27

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW995-ST-1, 2.5'-4.5'
Project No.: 183923
Boring No.: GW995-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW995-ST-1
Test Date : 3-15-18
Depth : 3.8'-4.0'
Test No. : GW995-ST-1
Sample Type: Undisturb

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 5 of 20
Stress increment from 1.00 (t/ft^2) to 2.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.92	32.86	0.0132	0.617	1.32
37)	1139.90	33.76	0.0132	0.617	1.32
38)	1199.95	34.64	0.0132	0.617	1.32
39)	1259.92	35.50	0.0132	0.617	1.32
40)	1319.90	36.33	0.0132	0.617	1.32
41)	1379.90	37.15	0.0127	0.618	1.27
42)	1439.92	37.95	0.0132	0.617	1.32
43)	1499.92	38.73	0.0132	0.617	1.32
44)	1559.90	39.50	0.0127	0.618	1.27
45)	1619.90	40.25	0.0127	0.618	1.27
46)	1624.45	40.30	0.0122	0.618	1.22

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW995-ST-1, 2.5'-4.5'	Project No.: 183923
Boring No.: GW995-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW995-ST-1	Test Date : 3-15-18	Depth : 3.8'-4.0'
Test No. : GW995-ST-1	Sample Type: Undisturb	

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 6 of 20
Stress increment from 2.00 (t/ft^2) to 4.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0204	0.605	2.04
2)	0.13	0.37	0.0209	0.604	2.09
3)	0.38	0.62	0.0214	0.603	2.14
4)	0.88	0.94	0.0224	0.602	2.24
5)	1.93	1.39	0.0234	0.600	2.34
6)	2.88	1.70	0.0239	0.599	2.39
7)	3.90	1.97	0.0249	0.598	2.49
8)	4.92	2.22	0.0255	0.597	2.55
9)	5.88	2.43	0.0260	0.596	2.60
10)	6.90	2.63	0.0260	0.596	2.60
11)	7.88	2.81	0.0260	0.596	2.60
12)	8.90	2.98	0.0260	0.596	2.60
13)	9.90	3.15	0.0265	0.595	2.65
14)	14.88	3.86	0.0270	0.594	2.70
15)	29.88	5.47	0.0280	0.593	2.80
16)	59.88	7.74	0.0280	0.593	2.80
17)	89.88	9.48	0.0285	0.592	2.85
18)	119.90	10.95	0.0285	0.592	2.85
19)	149.90	12.24	0.0285	0.592	2.85
20)	179.90	13.41	0.0285	0.592	2.85
21)	209.90	14.49	0.0285	0.592	2.85
22)	239.90	15.49	0.0285	0.592	2.85
23)	299.92	17.32	0.0290	0.591	2.90
24)	359.88	18.97	0.0290	0.591	2.90
25)	419.90	20.49	0.0290	0.591	2.90
26)	479.92	21.91	0.0290	0.591	2.90
27)	539.90	23.24	0.0295	0.590	2.95
28)	599.88	24.49	0.0290	0.591	2.90
29)	659.88	25.69	0.0295	0.590	2.95
30)	719.90	26.83	0.0295	0.590	2.95
31)	779.90	27.93	0.0295	0.590	2.95
32)	839.88	28.98	0.0295	0.590	2.95
33)	899.90	30.00	0.0295	0.590	2.95
34)	959.90	30.98	0.0295	0.590	2.95
35)	1019.88	31.94	0.0295	0.590	2.95

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW995-ST-1, 2.5'-4.5'	Project No.: 183923
Boring No.: GW995-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW995-ST-1	Test Date : 3-15-18	Depth : 3.8'-4.0'
Test No. : GW995-ST-1	Sample Type: Undisturb	

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 6 of 20
Stress increment from 2.00 (t/ft^2) to 4.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.88	32.86	0.0295	0.590	2.95
37)	1139.92	33.76	0.0295	0.590	2.95
38)	1199.88	34.64	0.0295	0.590	2.95
39)	1259.90	35.50	0.0295	0.590	2.95
40)	1319.90	36.33	0.0295	0.590	2.95
41)	1329.13	36.46	0.0290	0.591	2.90

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW995-ST-1, 2.5'-4.5'	Project No.: 183923
Boring No.: GW995-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW995-ST-1	Test Date : 3-15-18	Depth : 3.8'-4.0'
Test No. : GW995-ST-1	Sample Type: Undisturb	

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 7 of 20
Stress increment from 4.00 (t/ft^2) to 2.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0260	0.596	2.60
2)	0.13	0.37	0.0260	0.596	2.60
3)	0.40	0.63	0.0260	0.596	2.60
4)	0.88	0.94	0.0255	0.597	2.55
5)	1.90	1.38	0.0255	0.597	2.55
6)	2.90	1.70	0.0249	0.598	2.49
7)	3.90	1.97	0.0249	0.598	2.49
8)	4.90	2.21	0.0249	0.598	2.49
9)	5.90	2.43	0.0249	0.598	2.49
10)	6.90	2.63	0.0249	0.598	2.49
11)	7.88	2.81	0.0249	0.598	2.49
12)	8.90	2.98	0.0244	0.598	2.44
13)	9.88	3.14	0.0249	0.598	2.49
14)	14.90	3.86	0.0249	0.598	2.49
15)	29.88	5.47	0.0249	0.598	2.49
16)	59.88	7.74	0.0249	0.598	2.49
17)	89.88	9.48	0.0249	0.598	2.49
18)	119.88	10.95	0.0249	0.598	2.49
19)	149.90	12.24	0.0249	0.598	2.49
20)	179.88	13.41	0.0249	0.598	2.49
21)	209.88	14.49	0.0249	0.598	2.49
22)	239.90	15.49	0.0249	0.598	2.49
23)	299.88	17.32	0.0249	0.598	2.49
24)	359.88	18.97	0.0244	0.598	2.44
25)	419.88	20.49	0.0249	0.598	2.49
26)	479.90	21.91	0.0249	0.598	2.49
27)	539.88	23.24	0.0249	0.598	2.49
28)	599.90	24.49	0.0244	0.598	2.44
29)	659.90	25.69	0.0249	0.598	2.49
30)	719.90	26.83	0.0249	0.598	2.49
31)	779.92	27.93	0.0244	0.598	2.44
32)	839.88	28.98	0.0249	0.598	2.49
33)	899.88	30.00	0.0249	0.598	2.49
34)	959.90	30.98	0.0249	0.598	2.49
35)	1019.88	31.94	0.0249	0.598	2.49

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW995-ST-1, 2.5'-4.5'	Project No.: 183923
Boring No.: GW995-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW995-ST-1	Test Date : 3-15-18	Depth : 3.8'-4.0'
Test No. : GW995-ST-1	Sample Type: Undisturb	

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 7 of 20
Stress increment from 4.00 (t/ft^2) to 2.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.0249	0.598	2.49
37)	1139.88	33.76	0.0249	0.598	2.49
38)	1199.88	34.64	0.0244	0.598	2.44
39)	1259.88	35.49	0.0244	0.598	2.44
40)	1319.88	36.33	0.0249	0.598	2.49
41)	1379.88	37.15	0.0244	0.598	2.44
42)	1428.52	37.80	0.0249	0.598	2.49

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW995-ST-1, 2.5'-4.5'
Project No.: 183923
Boring No.: GW995-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW995-ST-1
Test Date : 3-15-18
Depth : 3.8'-4.0'
Test No. : GW995-ST-1
Sample Type: Undisturb

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 8 of 20
Stress increment from 2.00 (t/ft^2) to 1.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0219	0.603	2.19
2)	0.13	0.37	0.0214	0.603	2.14
3)	0.40	0.63	0.0214	0.603	2.14
4)	0.88	0.94	0.0209	0.604	2.09
5)	1.90	1.38	0.0209	0.604	2.09
6)	2.90	1.70	0.0204	0.605	2.04
7)	3.88	1.97	0.0204	0.605	2.04
8)	4.90	2.21	0.0199	0.606	1.99
9)	5.88	2.43	0.0199	0.606	1.99
10)	6.92	2.63	0.0199	0.606	1.99
11)	7.88	2.81	0.0199	0.606	1.99
12)	8.90	2.98	0.0193	0.607	1.93
13)	9.90	3.15	0.0193	0.607	1.93
14)	14.90	3.86	0.0193	0.607	1.93
15)	29.88	5.47	0.0193	0.607	1.93
16)	59.90	7.74	0.0193	0.607	1.93
17)	89.90	9.48	0.0193	0.607	1.93
18)	119.90	10.95	0.0188	0.608	1.88
19)	149.88	12.24	0.0188	0.608	1.88
20)	179.90	13.41	0.0188	0.608	1.88
21)	209.92	14.49	0.0188	0.608	1.88
22)	239.90	15.49	0.0188	0.608	1.88
23)	299.88	17.32	0.0188	0.608	1.88
24)	359.90	18.97	0.0188	0.608	1.88
25)	419.88	20.49	0.0188	0.608	1.88
26)	479.88	21.91	0.0188	0.608	1.88
27)	539.88	23.24	0.0188	0.608	1.88
28)	599.90	24.49	0.0188	0.608	1.88
29)	659.88	25.69	0.0188	0.608	1.88
30)	719.88	26.83	0.0188	0.608	1.88
31)	779.88	27.93	0.0188	0.608	1.88
32)	839.90	28.98	0.0183	0.608	1.83
33)	899.90	30.00	0.0188	0.608	1.88
34)	959.88	30.98	0.0183	0.608	1.83
35)	1019.88	31.94	0.0183	0.608	1.83

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW995-ST-1, 2.5'-4.5'	Project No.: 183923
Boring No.: GW995-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW995-ST-1	Test Date : 3-15-18	Depth : 3.8'-4.0'
Test No. : GW995-ST-1	Sample Type: Undisturb	

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 8 of 20
Stress increment from 2.00 (t/ft^2) to 1.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.0188	0.608	1.88
37)	1139.88	33.76	0.0188	0.608	1.88
38)	1199.88	34.64	0.0183	0.608	1.83
39)	1259.88	35.49	0.0183	0.608	1.83
40)	1319.90	36.33	0.0183	0.608	1.83
41)	1379.88	37.15	0.0183	0.608	1.83
42)	1439.90	37.95	0.0183	0.608	1.83
43)	1441.12	37.96	0.0178	0.609	1.78

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW995-ST-1, 2.5'-4.5'
Project No.: 183923
Boring No.: GW995-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW995-ST-1
Test Date : 3-15-18
Depth : 3.8'-4.0'
Test No. : GW995-ST-1
Sample Type: Undisturb

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 9 of 20
Stress increment from 1.00 (t/ft^2) to 0.50 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0163	0.612	1.63
2)	0.12	0.34	0.0163	0.612	1.63
3)	0.37	0.61	0.0163	0.612	1.63
4)	0.88	0.94	0.0158	0.613	1.58
5)	1.88	1.37	0.0158	0.613	1.58
6)	2.87	1.69	0.0153	0.613	1.53
7)	3.88	1.97	0.0153	0.613	1.53
8)	4.87	2.21	0.0148	0.614	1.48
9)	5.88	2.43	0.0148	0.614	1.48
10)	6.87	2.62	0.0148	0.614	1.48
11)	7.88	2.81	0.0143	0.615	1.43
12)	8.90	2.98	0.0143	0.615	1.43
13)	9.90	3.15	0.0148	0.614	1.48
14)	14.90	3.86	0.0137	0.616	1.37
15)	29.90	5.47	0.0143	0.615	1.43
16)	59.88	7.74	0.0137	0.616	1.37
17)	89.92	9.48	0.0132	0.617	1.32
18)	119.90	10.95	0.0132	0.617	1.32
19)	149.87	12.24	0.0127	0.618	1.27
20)	179.90	13.41	0.0127	0.618	1.27
21)	209.87	14.49	0.0127	0.618	1.27
22)	239.88	15.49	0.0127	0.618	1.27
23)	299.87	17.32	0.0127	0.618	1.27
24)	359.88	18.97	0.0127	0.618	1.27
25)	419.90	20.49	0.0122	0.618	1.22
26)	479.88	21.91	0.0122	0.618	1.22
27)	539.88	23.24	0.0122	0.618	1.22
28)	599.90	24.49	0.0122	0.618	1.22
29)	659.88	25.69	0.0122	0.618	1.22
30)	719.88	26.83	0.0122	0.618	1.22
31)	779.90	27.93	0.0122	0.618	1.22
32)	839.88	28.98	0.0122	0.618	1.22
33)	899.88	30.00	0.0117	0.619	1.17
34)	959.87	30.98	0.0122	0.618	1.22
35)	1019.88	31.94	0.0122	0.618	1.22

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW995-ST-1, 2.5'-4.5'	Project No.: 183923
Boring No.: GW995-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW995-ST-1	Test Date : 3-15-18	Depth : 3.8'-4.0'
Test No. : GW995-ST-1	Sample Type: Undisturb	

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 9 of 20
Stress increment from 1.00 (t/ft^2) to 0.50 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.87	32.86	0.0122	0.618	1.22
37)	1139.87	33.76	0.0122	0.618	1.22
38)	1199.88	34.64	0.0122	0.618	1.22
39)	1259.92	35.50	0.0122	0.618	1.22
40)	1319.87	36.33	0.0117	0.619	1.17
41)	1379.87	37.15	0.0117	0.619	1.17
42)	1439.88	37.95	0.0117	0.619	1.17
43)	1479.92	38.47	0.0122	0.618	1.22

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW995-ST-1, 2.5'-4.5'	Project No.: 183923
Boring No.: GW995-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW995-ST-1	Test Date : 3-15-18	Depth : 3.8'-4.0'
Test No. : GW995-ST-1	Sample Type: Undisturb	

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 10 of 20
Stress increment from 0.50 (t/ft^2) to 1.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0127	0.618	1.27
2)	0.15	0.39	0.0127	0.618	1.27
3)	0.40	0.63	0.0127	0.618	1.27
4)	0.92	0.96	0.0132	0.617	1.32
5)	1.90	1.38	0.0137	0.616	1.37
6)	2.90	1.70	0.0132	0.617	1.32
7)	3.92	1.98	0.0137	0.616	1.37
8)	4.92	2.22	0.0137	0.616	1.37
9)	5.90	2.43	0.0137	0.616	1.37
10)	6.92	2.63	0.0137	0.616	1.37
11)	7.90	2.81	0.0137	0.616	1.37
12)	8.90	2.98	0.0137	0.616	1.37
13)	9.90	3.15	0.0143	0.615	1.43
14)	14.90	3.86	0.0137	0.616	1.37
15)	29.95	5.47	0.0143	0.615	1.43
16)	59.92	7.74	0.0143	0.615	1.43
17)	89.90	9.48	0.0143	0.615	1.43
18)	119.92	10.95	0.0148	0.614	1.48
19)	149.92	12.24	0.0143	0.615	1.43
20)	179.92	13.41	0.0143	0.615	1.43
21)	209.92	14.49	0.0143	0.615	1.43
22)	239.92	15.49	0.0143	0.615	1.43
23)	299.90	17.32	0.0148	0.614	1.48
24)	359.92	18.97	0.0148	0.614	1.48
25)	419.92	20.49	0.0148	0.614	1.48
26)	479.90	21.91	0.0148	0.614	1.48
27)	539.92	23.24	0.0148	0.614	1.48
28)	599.93	24.49	0.0148	0.614	1.48
29)	659.90	25.69	0.0148	0.614	1.48
30)	719.90	26.83	0.0148	0.614	1.48
31)	779.90	27.93	0.0148	0.614	1.48
32)	839.92	28.98	0.0148	0.614	1.48
33)	899.90	30.00	0.0148	0.614	1.48
34)	959.90	30.98	0.0148	0.614	1.48
35)	1019.90	31.94	0.0148	0.614	1.48

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW995-ST-1, 2.5'-4.5'
Project No.: 183923
Boring No.: GW995-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW995-ST-1
Test Date : 3-15-18
Depth : 3.8'-4.0'
Test No. : GW995-ST-1
Sample Type: Undisturb

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 10 of 20
Stress increment from 0.50 (t/ft^2) to 1.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.88	32.86	0.0148	0.614	1.48
37)	1139.92	33.76	0.0153	0.613	1.53
38)	1199.92	34.64	0.0148	0.614	1.48
39)	1259.90	35.50	0.0148	0.614	1.48
40)	1319.90	36.33	0.0148	0.614	1.48
41)	1328.40	36.45	0.0143	0.615	1.43

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW995-ST-1, 2.5'-4.5'
Project No.: 183923
Boring No.: GW995-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW995-ST-1
Test Date : 3-15-18
Depth : 3.8'-4.0'
Test No. : GW995-ST-1
Sample Type: Undisturb

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 11 of 20
Stress increment from 1.00 (t/ft^2) to 2.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0173	0.610	1.73
2)	0.15	0.39	0.0178	0.609	1.78
3)	0.40	0.63	0.0183	0.608	1.83
4)	0.88	0.94	0.0188	0.608	1.88
5)	1.90	1.38	0.0188	0.608	1.88
6)	2.90	1.70	0.0193	0.607	1.93
7)	3.90	1.97	0.0193	0.607	1.93
8)	4.90	2.21	0.0193	0.607	1.93
9)	5.90	2.43	0.0199	0.606	1.99
10)	6.88	2.62	0.0199	0.606	1.99
11)	7.88	2.81	0.0199	0.606	1.99
12)	8.90	2.98	0.0199	0.606	1.99
13)	9.90	3.15	0.0199	0.606	1.99
14)	14.88	3.86	0.0204	0.605	2.04
15)	29.90	5.47	0.0204	0.605	2.04
16)	59.90	7.74	0.0204	0.605	2.04
17)	89.90	9.48	0.0214	0.603	2.14
18)	119.88	10.95	0.0209	0.604	2.09
19)	149.90	12.24	0.0214	0.603	2.14
20)	179.90	13.41	0.0209	0.604	2.09
21)	209.88	14.49	0.0209	0.604	2.09
22)	239.90	15.49	0.0209	0.604	2.09
23)	299.88	17.32	0.0209	0.604	2.09
24)	359.90	18.97	0.0209	0.604	2.09
25)	419.88	20.49	0.0209	0.604	2.09
26)	479.90	21.91	0.0209	0.604	2.09
27)	539.90	23.24	0.0209	0.604	2.09
28)	599.88	24.49	0.0209	0.604	2.09
29)	659.90	25.69	0.0209	0.604	2.09
30)	719.88	26.83	0.0209	0.604	2.09
31)	779.90	27.93	0.0209	0.604	2.09
32)	839.90	28.98	0.0209	0.604	2.09
33)	899.88	30.00	0.0209	0.604	2.09
34)	959.90	30.98	0.0209	0.604	2.09
35)	1019.90	31.94	0.0209	0.604	2.09

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW995-ST-1, 2.5'-4.5'	Project No.: 183923
Boring No.: GW995-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW995-ST-1	Test Date : 3-15-18	Depth : 3.8'-4.0'
Test No. : GW995-ST-1	Sample Type: Undisturb	

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 11 of 20
Stress increment from 1.00 (t/ft^2) to 2.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.88	32.86	0.0209	0.604	2.09
37)	1139.88	33.76	0.0209	0.604	2.09
38)	1199.90	34.64	0.0209	0.604	2.09
39)	1259.88	35.49	0.0209	0.604	2.09
40)	1319.88	36.33	0.0209	0.604	2.09
41)	1379.90	37.15	0.0209	0.604	2.09
42)	1439.88	37.95	0.0209	0.604	2.09
43)	1499.88	38.73	0.0209	0.604	2.09
44)	1503.95	38.78	0.0209	0.604	2.09

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW995-ST-1, 2.5'-4.5'
Project No.: 183923
Boring No.: GW995-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW995-ST-1
Test Date : 3-15-18
Depth : 3.8'-4.0'
Test No. : GW995-ST-1
Sample Type: Undisturb

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 12 of 20
Stress increment from 2.00 (t/ft^2) to 4.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0255	0.597	2.55
2)	0.13	0.37	0.0260	0.596	2.60
3)	0.38	0.62	0.0265	0.595	2.65
4)	0.88	0.94	0.0270	0.594	2.70
5)	1.88	1.37	0.0275	0.593	2.75
6)	2.90	1.70	0.0280	0.593	2.80
7)	3.88	1.97	0.0285	0.592	2.85
8)	4.90	2.21	0.0285	0.592	2.85
9)	5.90	2.43	0.0290	0.591	2.90
10)	6.88	2.62	0.0285	0.592	2.85
11)	7.88	2.81	0.0285	0.592	2.85
12)	8.88	2.98	0.0290	0.591	2.90
13)	9.88	3.14	0.0290	0.591	2.90
14)	14.88	3.86	0.0295	0.590	2.95
15)	29.88	5.47	0.0295	0.590	2.95
16)	59.90	7.74	0.0300	0.589	3.00
17)	89.88	9.48	0.0300	0.589	3.00
18)	119.88	10.95	0.0300	0.589	3.00
19)	149.88	12.24	0.0300	0.589	3.00
20)	179.88	13.41	0.0300	0.589	3.00
21)	209.90	14.49	0.0300	0.589	3.00
22)	239.88	15.49	0.0300	0.589	3.00
23)	299.90	17.32	0.0300	0.589	3.00
24)	359.88	18.97	0.0300	0.589	3.00
25)	419.88	20.49	0.0300	0.589	3.00
26)	479.88	21.91	0.0300	0.589	3.00
27)	539.88	23.24	0.0300	0.589	3.00
28)	599.90	24.49	0.0300	0.589	3.00
29)	659.87	25.69	0.0300	0.589	3.00
30)	719.88	26.83	0.0300	0.589	3.00
31)	779.88	27.93	0.0305	0.588	3.05
32)	839.88	28.98	0.0305	0.588	3.05
33)	899.92	30.00	0.0305	0.588	3.05
34)	959.88	30.98	0.0305	0.588	3.05
35)	1019.88	31.94	0.0305	0.588	3.05

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW995-ST-1, 2.5'-4.5'	Project No.: 183923
Boring No.: GW995-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW995-ST-1	Test Date : 3-15-18	Depth : 3.8'-4.0'
Test No. : GW995-ST-1	Sample Type: Undisturb	

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 12 of 20
Stress increment from 2.00 (t/ft^2) to 4.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.0305	0.588	3.05
37)	1139.88	33.76	0.0305	0.588	3.05
38)	1199.88	34.64	0.0305	0.588	3.05
39)	1259.90	35.50	0.0305	0.588	3.05
40)	1319.88	36.33	0.0305	0.588	3.05
41)	1379.88	37.15	0.0305	0.588	3.05
42)	1439.87	37.95	0.0305	0.588	3.05
43)	1499.93	38.73	0.0300	0.589	3.00
44)	1501.02	38.74	0.0310	0.588	3.10

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW995-ST-1, 2.5'-4.5'
Project No.: 183923
Boring No.: GW995-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW995-ST-1
Test Date : 3-15-18
Depth : 3.8'-4.0'
Test No. : GW995-ST-1
Sample Type: Undisturb

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 13 of 20
Stress increment from 4.00 (t/ft^2) to 8.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0392	0.574	3.92
2)	0.12	0.34	0.0397	0.573	3.97
3)	0.37	0.61	0.0407	0.572	4.07
4)	0.87	0.93	0.0422	0.569	4.22
5)	1.87	1.37	0.0438	0.567	4.38
6)	2.85	1.69	0.0448	0.565	4.48
7)	3.87	1.97	0.0458	0.563	4.58
8)	4.85	2.20	0.0463	0.563	4.63
9)	5.87	2.42	0.0468	0.562	4.68
10)	6.87	2.62	0.0473	0.561	4.73
11)	7.85	2.80	0.0473	0.561	4.73
12)	8.85	2.97	0.0478	0.560	4.78
13)	9.87	3.14	0.0478	0.560	4.78
14)	14.85	3.85	0.0489	0.558	4.89
15)	29.87	5.47	0.0499	0.557	4.99
16)	59.85	7.74	0.0504	0.556	5.04
17)	89.87	9.48	0.0509	0.555	5.09
18)	119.85	10.95	0.0509	0.555	5.09
19)	149.87	12.24	0.0509	0.555	5.09
20)	179.87	13.41	0.0509	0.555	5.09
21)	209.87	14.49	0.0509	0.555	5.09
22)	239.88	15.49	0.0514	0.554	5.14
23)	299.90	17.32	0.0509	0.555	5.09
24)	359.87	18.97	0.0514	0.554	5.14
25)	419.87	20.49	0.0514	0.554	5.14
26)	479.85	21.91	0.0514	0.554	5.14
27)	539.85	23.23	0.0514	0.554	5.14
28)	599.85	24.49	0.0519	0.553	5.19
29)	659.87	25.69	0.0519	0.553	5.19
30)	719.87	26.83	0.0519	0.553	5.19
31)	779.87	27.93	0.0519	0.553	5.19
32)	839.85	28.98	0.0519	0.553	5.19
33)	899.85	30.00	0.0519	0.553	5.19
34)	959.85	30.98	0.0519	0.553	5.19
35)	1019.85	31.94	0.0519	0.553	5.19

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW995-ST-1, 2.5'-4.5'	Project No.: 183923
Boring No.: GW995-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW995-ST-1	Test Date : 3-15-18	Depth : 3.8'-4.0'
Test No. : GW995-ST-1	Sample Type: Undisturb	

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 13 of 20
Stress increment from 4.00 (t/ft^2) to 8.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.87	32.86	0.0519	0.553	5.19
37)	1139.87	33.76	0.0519	0.553	5.19
38)	1199.87	34.64	0.0519	0.553	5.19
39)	1259.87	35.49	0.0519	0.553	5.19
40)	1319.87	36.33	0.0519	0.553	5.19
41)	1379.87	37.15	0.0519	0.553	5.19
42)	1388.23	37.26	0.0519	0.553	5.19

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW995-ST-1, 2.5'-4.5'	Project No.: 183923
Boring No.: GW995-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW995-ST-1	Test Date : 3-15-18	Depth : 3.8'-4.0'
Test No. : GW995-ST-1	Sample Type: Undisturb	

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 14 of 20
Stress increment from 8.00 (t/ft^2) to 16.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0616	0.538	6.16
2)	0.15	0.39	0.0626	0.536	6.26
3)	0.40	0.63	0.0636	0.534	6.36
4)	0.90	0.95	0.0657	0.531	6.57
5)	1.90	1.38	0.0682	0.527	6.82
6)	2.90	1.70	0.0702	0.523	7.02
7)	3.90	1.97	0.0713	0.522	7.13
8)	4.90	2.21	0.0723	0.520	7.23
9)	5.90	2.43	0.0733	0.518	7.33
10)	6.90	2.63	0.0738	0.517	7.38
11)	7.90	2.81	0.0743	0.517	7.43
12)	8.90	2.98	0.0748	0.516	7.48
13)	9.92	3.15	0.0753	0.515	7.53
14)	14.90	3.86	0.0769	0.512	7.69
15)	29.90	5.47	0.0779	0.511	7.79
16)	59.93	7.74	0.0784	0.510	7.84
17)	89.92	9.48	0.0784	0.510	7.84
18)	119.92	10.95	0.0789	0.509	7.89
19)	149.90	12.24	0.0789	0.509	7.89
20)	179.90	13.41	0.0794	0.508	7.94
21)	209.90	14.49	0.0794	0.508	7.94
22)	239.92	15.49	0.0789	0.509	7.89
23)	299.90	17.32	0.0789	0.509	7.89
24)	359.90	18.97	0.0794	0.508	7.94
25)	419.90	20.49	0.0794	0.508	7.94
26)	479.90	21.91	0.0794	0.508	7.94
27)	539.92	23.24	0.0799	0.507	7.99
28)	599.93	24.49	0.0794	0.508	7.94
29)	659.90	25.69	0.0794	0.508	7.94
30)	719.92	26.83	0.0794	0.508	7.94
31)	779.90	27.93	0.0799	0.507	7.99
32)	839.90	28.98	0.0799	0.507	7.99
33)	899.90	30.00	0.0799	0.507	7.99
34)	959.88	30.98	0.0799	0.507	7.99
35)	1019.90	31.94	0.0799	0.507	7.99

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW995-ST-1, 2.5'-4.5'	Project No.: 183923
Boring No.: GW995-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW995-ST-1	Test Date : 3-15-18	Depth : 3.8'-4.0'
Test No. : GW995-ST-1	Sample Type: Undisturb	

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 14 of 20
Stress increment from 8.00 (t/ft^2) to 16.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.88	32.86	0.0799	0.507	7.99
37)	1139.92	33.76	0.0794	0.508	7.94
38)	1199.88	34.64	0.0799	0.507	7.99
39)	1259.90	35.50	0.0794	0.508	7.94
40)	1319.90	36.33	0.0799	0.507	7.99
41)	1379.92	37.15	0.0799	0.507	7.99
42)	1439.90	37.95	0.0799	0.507	7.99
43)	1456.82	38.17	0.0799	0.507	7.99

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW995-ST-1, 2.5'-4.5'
Project No.: 183923
Boring No.: GW995-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW995-ST-1
Test Date : 3-15-18
Depth : 3.8'-4.0'
Test No. : GW995-ST-1
Sample Type: Undisturb

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 15 of 20
Stress increment from 16.00 (t/ft^2) to 32.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0896	0.492	8.96
2)	0.15	0.39	0.0911	0.489	9.11
3)	0.40	0.63	0.0931	0.486	9.31
4)	0.92	0.96	0.0962	0.481	9.62
5)	1.90	1.38	0.0998	0.475	9.98
6)	2.90	1.70	0.1018	0.472	10.18
7)	3.90	1.97	0.1038	0.468	10.38
8)	4.90	2.21	0.1054	0.466	10.54
9)	5.92	2.43	0.1064	0.464	10.64
10)	6.92	2.63	0.1074	0.462	10.74
11)	7.90	2.81	0.1084	0.461	10.84
12)	8.92	2.99	0.1089	0.460	10.89
13)	9.90	3.15	0.1099	0.458	10.99
14)	14.90	3.86	0.1110	0.457	11.10
15)	29.92	5.47	0.1130	0.453	11.30
16)	59.90	7.74	0.1135	0.452	11.35
17)	89.90	9.48	0.1140	0.452	11.40
18)	119.92	10.95	0.1140	0.452	11.40
19)	149.92	12.24	0.1145	0.451	11.45
20)	179.90	13.41	0.1145	0.451	11.45
21)	209.88	14.49	0.1145	0.451	11.45
22)	239.90	15.49	0.1150	0.450	11.50
23)	299.90	17.32	0.1150	0.450	11.50
24)	359.93	18.97	0.1150	0.450	11.50
25)	419.90	20.49	0.1150	0.450	11.50
26)	479.90	21.91	0.1150	0.450	11.50
27)	539.90	23.24	0.1155	0.449	11.55
28)	599.90	24.49	0.1155	0.449	11.55
29)	659.90	25.69	0.1155	0.449	11.55
30)	719.93	26.83	0.1155	0.449	11.55
31)	779.92	27.93	0.1161	0.448	11.61
32)	839.88	28.98	0.1161	0.448	11.61
33)	899.90	30.00	0.1155	0.449	11.55
34)	959.93	30.98	0.1161	0.448	11.61
35)	1019.90	31.94	0.1161	0.448	11.61

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW995-ST-1, 2.5'-4.5'	Project No.: 183923
Boring No.: GW995-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW995-ST-1	Test Date : 3-15-18	Depth : 3.8'-4.0'
Test No. : GW995-ST-1	Sample Type: Undisturb	

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 15 of 20
Stress increment from 16.00 (t/ft^2) to 32.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.1161	0.448	11.61
37)	1139.90	33.76	0.1161	0.448	11.61
38)	1199.90	34.64	0.1161	0.448	11.61
39)	1259.88	35.49	0.1161	0.448	11.61
40)	1319.90	36.33	0.1161	0.448	11.61
41)	1379.90	37.15	0.1150	0.450	11.50
42)	1439.48	37.94	0.1161	0.448	11.61

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW995-ST-1, 2.5'-4.5'	Project No.: 183923
Boring No.: GW995-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW995-ST-1	Test Date : 3-15-18	Depth : 3.8'-4.0'
Test No. : GW995-ST-1	Sample Type: Undisturb	

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 16 of 20
Stress increment from 32.00 (t/ft^2) to 16.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.1099	0.458	10.99
2)	0.17	0.41	0.1094	0.459	10.94
3)	0.42	0.65	0.1089	0.460	10.89
4)	0.92	0.96	0.1089	0.460	10.89
5)	1.90	1.38	0.1084	0.461	10.84
6)	2.92	1.71	0.1079	0.462	10.79
7)	3.90	1.97	0.1079	0.462	10.79
8)	4.90	2.21	0.1079	0.462	10.79
9)	5.90	2.43	0.1084	0.461	10.84
10)	6.92	2.63	0.1079	0.462	10.79
11)	7.92	2.81	0.1079	0.462	10.79
12)	8.90	2.98	0.1079	0.462	10.79
13)	9.92	3.15	0.1074	0.462	10.74
14)	14.90	3.86	0.1074	0.462	10.74
15)	29.93	5.47	0.1079	0.462	10.79
16)	59.92	7.74	0.1079	0.462	10.79
17)	89.90	9.48	0.1079	0.462	10.79
18)	119.92	10.95	0.1074	0.462	10.74
19)	149.90	12.24	0.1074	0.462	10.74
20)	179.90	13.41	0.1074	0.462	10.74
21)	209.90	14.49	0.1074	0.462	10.74
22)	239.90	15.49	0.1074	0.462	10.74
23)	299.90	17.32	0.1074	0.462	10.74
24)	359.93	18.97	0.1074	0.462	10.74
25)	419.90	20.49	0.1074	0.462	10.74
26)	479.90	21.91	0.1074	0.462	10.74
27)	539.90	23.24	0.1074	0.462	10.74
28)	599.90	24.49	0.1074	0.462	10.74
29)	659.92	25.69	0.1074	0.462	10.74
30)	719.88	26.83	0.1074	0.462	10.74
31)	779.92	27.93	0.1074	0.462	10.74
32)	839.90	28.98	0.1074	0.462	10.74
33)	899.88	30.00	0.1074	0.462	10.74
34)	959.92	30.98	0.1079	0.462	10.79
35)	1019.90	31.94	0.1074	0.462	10.74

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW995-ST-1, 2.5'-4.5'	Project No.: 183923
Boring No.: GW995-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW995-ST-1	Test Date : 3-15-18	Depth : 3.8'-4.0'
Test No. : GW995-ST-1	Sample Type: Undisturb	

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 16 of 20
Stress increment from 32.00 (t/ft^2) to 16.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.92	32.86	0.1074	0.462	10.74
37)	1139.90	33.76	0.1074	0.462	10.74
38)	1199.90	34.64	0.1074	0.462	10.74
39)	1259.90	35.50	0.1074	0.462	10.74
40)	1319.90	36.33	0.1074	0.462	10.74
41)	1379.90	37.15	0.1074	0.462	10.74
42)	1437.65	37.92	0.1074	0.462	10.74

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW995-ST-1, 2.5'-4.5'
Project No.: 183923
Boring No.: GW995-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW995-ST-1
Test Date : 3-15-18
Depth : 3.8'-4.0'
Test No. : GW995-ST-1
Sample Type: Undisturb

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 17 of 20
Stress increment from 16.00 (t/ft^2) to 8.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.1018	0.472	10.18
2)	0.13	0.37	0.1013	0.472	10.13
3)	0.40	0.63	0.1008	0.473	10.08
4)	0.90	0.95	0.1003	0.474	10.03
5)	1.88	1.37	0.0998	0.475	9.98
6)	2.88	1.70	0.0993	0.476	9.93
7)	3.92	1.98	0.0987	0.477	9.87
8)	4.90	2.21	0.0987	0.477	9.87
9)	5.88	2.43	0.0987	0.477	9.87
10)	6.88	2.62	0.0987	0.477	9.87
11)	7.88	2.81	0.0987	0.477	9.87
12)	8.90	2.98	0.0982	0.477	9.82
13)	9.90	3.15	0.0982	0.477	9.82
14)	14.92	3.86	0.0977	0.478	9.77
15)	29.88	5.47	0.0982	0.477	9.82
16)	59.90	7.74	0.0982	0.477	9.82
17)	89.88	9.48	0.0982	0.477	9.82
18)	119.90	10.95	0.0977	0.478	9.77
19)	149.88	12.24	0.0977	0.478	9.77
20)	179.88	13.41	0.0977	0.478	9.77
21)	209.88	14.49	0.0977	0.478	9.77
22)	239.92	15.49	0.0977	0.478	9.77
23)	299.88	17.32	0.0977	0.478	9.77
24)	359.88	18.97	0.0977	0.478	9.77
25)	419.88	20.49	0.0977	0.478	9.77
26)	479.90	21.91	0.0977	0.478	9.77
27)	539.90	23.24	0.0977	0.478	9.77
28)	599.88	24.49	0.0977	0.478	9.77
29)	659.88	25.69	0.0977	0.478	9.77
30)	719.88	26.83	0.0977	0.478	9.77
31)	779.90	27.93	0.0977	0.478	9.77
32)	839.88	28.98	0.0977	0.478	9.77
33)	899.88	30.00	0.0977	0.478	9.77
34)	959.90	30.98	0.0977	0.478	9.77
35)	1019.88	31.94	0.0977	0.478	9.77

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW995-ST-1, 2.5'-4.5'	Project No.: 183923
Boring No.: GW995-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW995-ST-1	Test Date : 3-15-18	Depth : 3.8'-4.0'
Test No. : GW995-ST-1	Sample Type: Undisturb	

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 17 of 20
Stress increment from 16.00 (t/ft^2) to 8.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.92	32.86	0.0977	0.478	9.77
37)	1139.90	33.76	0.0977	0.478	9.77
38)	1199.88	34.64	0.0972	0.479	9.72
39)	1259.88	35.49	0.0972	0.479	9.72
40)	1319.88	36.33	0.0977	0.478	9.77
41)	1379.90	37.15	0.0977	0.478	9.77
42)	1439.88	37.95	0.0977	0.478	9.77
43)	1499.88	38.73	0.0972	0.479	9.72
44)	1543.13	39.28	0.0967	0.480	9.67

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW995-ST-1, 2.5'-4.5'	Project No.: 183923
Boring No.: GW995-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW995-ST-1	Test Date : 3-15-18	Depth : 3.8'-4.0'
Test No. : GW995-ST-1	Sample Type: Undisturb	

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 18 of 20
Stress increment from 8.00 (t/ft^2) to 4.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0921	0.487	9.21
2)	0.15	0.39	0.0916	0.488	9.16
3)	0.42	0.65	0.0916	0.488	9.16
4)	0.92	0.96	0.0906	0.490	9.06
5)	1.90	1.38	0.0901	0.491	9.01
6)	2.90	1.70	0.0896	0.492	8.96
7)	3.92	1.98	0.0896	0.492	8.96
8)	4.92	2.22	0.0891	0.492	8.91
9)	5.92	2.43	0.0891	0.492	8.91
10)	6.90	2.63	0.0886	0.493	8.86
11)	7.90	2.81	0.0881	0.494	8.81
12)	8.90	2.98	0.0881	0.494	8.81
13)	9.90	3.15	0.0881	0.494	8.81
14)	14.90	3.86	0.0875	0.495	8.75
15)	29.90	5.47	0.0870	0.496	8.70
16)	59.92	7.74	0.0865	0.497	8.65
17)	89.92	9.48	0.0870	0.496	8.70
18)	119.90	10.95	0.0860	0.497	8.60
19)	149.90	12.24	0.0865	0.497	8.65
20)	179.92	13.41	0.0860	0.497	8.60
21)	209.90	14.49	0.0860	0.497	8.60
22)	239.90	15.49	0.0860	0.497	8.60
23)	299.90	17.32	0.0860	0.497	8.60
24)	359.90	18.97	0.0860	0.497	8.60
25)	419.90	20.49	0.0860	0.497	8.60
26)	479.92	21.91	0.0855	0.498	8.55
27)	539.90	23.24	0.0855	0.498	8.55
28)	599.90	24.49	0.0855	0.498	8.55
29)	659.90	25.69	0.0855	0.498	8.55
30)	719.90	26.83	0.0855	0.498	8.55
31)	779.92	27.93	0.0855	0.498	8.55
32)	839.90	28.98	0.0855	0.498	8.55
33)	899.90	30.00	0.0855	0.498	8.55
34)	959.90	30.98	0.0855	0.498	8.55
35)	1019.90	31.94	0.0855	0.498	8.55

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW995-ST-1, 2.5'-4.5'	Project No.: 183923
Boring No.: GW995-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW995-ST-1	Test Date : 3-15-18	Depth : 3.8'-4.0'
Test No. : GW995-ST-1	Sample Type: Undisturb	

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 18 of 20
Stress increment from 8.00 (t/ft^2) to 4.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.92	32.86	0.0855	0.498	8.55
37)	1139.90	33.76	0.0855	0.498	8.55
38)	1199.90	34.64	0.0855	0.498	8.55
39)	1259.90	35.50	0.0855	0.498	8.55
40)	1319.90	36.33	0.0855	0.498	8.55
41)	1379.90	37.15	0.0850	0.499	8.50
42)	1439.90	37.95	0.0855	0.498	8.55
43)	1499.90	38.73	0.0850	0.499	8.50
44)	1559.90	39.50	0.0855	0.498	8.55
45)	1619.90	40.25	0.0855	0.498	8.55
46)	1679.90	40.99	0.0855	0.498	8.55
47)	1739.90	41.71	0.0850	0.499	8.50
48)	1799.90	42.43	0.0850	0.499	8.50
49)	1859.90	43.13	0.0850	0.499	8.50
50)	1919.90	43.82	0.0850	0.499	8.50
51)	1979.90	44.50	0.0855	0.498	8.55
52)	2039.90	45.17	0.0850	0.499	8.50
53)	2099.88	45.82	0.0850	0.499	8.50
54)	2159.90	46.47	0.0855	0.498	8.55
55)	2219.90	47.12	0.0855	0.498	8.55
56)	2279.88	47.75	0.0850	0.499	8.50
57)	2339.90	48.37	0.0855	0.498	8.55
58)	2399.88	48.99	0.0855	0.498	8.55
59)	2459.90	49.60	0.0855	0.498	8.55
60)	2519.90	50.20	0.0855	0.498	8.55
61)	2579.88	50.79	0.0855	0.498	8.55
62)	2639.90	51.38	0.0850	0.499	8.50
63)	2699.88	51.96	0.0855	0.498	8.55
64)	2759.90	52.53	0.0850	0.499	8.50
65)	2812.53	53.03	0.0855	0.498	8.55

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW995-ST-1, 2.5'-4.5'	Project No.: 183923
Boring No.: GW995-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW995-ST-1	Test Date : 3-15-18	Depth : 3.8'-4.0'
Test No. : GW995-ST-1	Sample Type: Undisturb	

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 19 of 20
Stress increment from 4.00 (t/ft^2) to 2.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0819	0.504	8.19
2)	0.15	0.39	0.0814	0.505	8.14
3)	0.40	0.63	0.0809	0.506	8.09
4)	0.90	0.95	0.0809	0.506	8.09
5)	1.90	1.38	0.0799	0.507	7.99
6)	2.90	1.70	0.0794	0.508	7.94
7)	3.90	1.97	0.0794	0.508	7.94
8)	4.90	2.21	0.0789	0.509	7.89
9)	5.90	2.43	0.0789	0.509	7.89
10)	6.92	2.63	0.0784	0.510	7.84
11)	7.90	2.81	0.0789	0.509	7.89
12)	8.90	2.98	0.0779	0.511	7.79
13)	9.90	3.15	0.0779	0.511	7.79
14)	14.90	3.86	0.0774	0.512	7.74
15)	29.90	5.47	0.0764	0.513	7.64
16)	59.90	7.74	0.0758	0.514	7.58
17)	89.92	9.48	0.0753	0.515	7.53
18)	119.90	10.95	0.0748	0.516	7.48
19)	149.90	12.24	0.0748	0.516	7.48
20)	179.90	13.41	0.0743	0.517	7.43
21)	209.93	14.49	0.0743	0.517	7.43
22)	239.90	15.49	0.0743	0.517	7.43
23)	299.92	17.32	0.0743	0.517	7.43
24)	359.90	18.97	0.0743	0.517	7.43
25)	419.90	20.49	0.0743	0.517	7.43
26)	479.90	21.91	0.0738	0.517	7.38
27)	539.88	23.24	0.0743	0.517	7.43
28)	599.90	24.49	0.0743	0.517	7.43
29)	659.90	25.69	0.0743	0.517	7.43
30)	719.90	26.83	0.0743	0.517	7.43
31)	779.88	27.93	0.0738	0.517	7.38
32)	839.90	28.98	0.0738	0.517	7.38
33)	899.88	30.00	0.0738	0.517	7.38
34)	959.90	30.98	0.0738	0.517	7.38
35)	1019.88	31.94	0.0738	0.517	7.38

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW995-ST-1, 2.5'-4.5'
Project No.: 183923
Boring No.: GW995-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW995-ST-1
Test Date : 3-15-18
Depth : 3.8'-4.0'
Test No. : GW995-ST-1
Sample Type: Undisturb

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 19 of 20
Stress increment from 4.00 (t/ft^2) to 2.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.0738	0.517	7.38
37)	1139.88	33.76	0.0738	0.517	7.38
38)	1199.90	34.64	0.0738	0.517	7.38
39)	1259.90	35.50	0.0738	0.517	7.38
40)	1319.90	36.33	0.0738	0.517	7.38
41)	1379.90	37.15	0.0733	0.518	7.33
42)	1407.72	37.52	0.0733	0.518	7.33

CONSOLIDATION TEST DATA

Project : EMDF Characterization
Location : GW995-ST-1, 2.5'-4.5'
Project No.: 183923
Boring No.: GW995-ST-1
Tested by : BMI: blc
Checked by : KAF
Sample No.: GW995-ST-1
Test Date : 3-15-18
Depth : 3.8'-4.0'
Test No. : GW995-ST-1
Sample Type: Undisturb

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 20 of 20
Stress increment from 2.00 (t/ft^2) to 1.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
1)	0.00	0.00	0.0708	0.523	7.08
2)	0.15	0.39	0.0702	0.523	7.02
3)	0.42	0.65	0.0702	0.523	7.02
4)	0.90	0.95	0.0697	0.524	6.97
5)	1.92	1.38	0.0697	0.524	6.97
6)	2.93	1.71	0.0692	0.525	6.92
7)	3.90	1.97	0.0687	0.526	6.87
8)	4.92	2.22	0.0687	0.526	6.87
9)	5.95	2.44	0.0682	0.527	6.82
10)	6.90	2.63	0.0682	0.527	6.82
11)	7.90	2.81	0.0687	0.526	6.87
12)	8.90	2.98	0.0677	0.528	6.77
13)	9.92	3.15	0.0677	0.528	6.77
14)	14.92	3.86	0.0667	0.529	6.67
15)	29.90	5.47	0.0662	0.530	6.62
16)	59.92	7.74	0.0646	0.533	6.46
17)	89.92	9.48	0.0636	0.534	6.36
18)	119.90	10.95	0.0636	0.534	6.36
19)	149.92	12.24	0.0631	0.535	6.31
20)	179.90	13.41	0.0631	0.535	6.31
21)	209.92	14.49	0.0631	0.535	6.31
22)	239.92	15.49	0.0626	0.536	6.26
23)	299.92	17.32	0.0626	0.536	6.26
24)	359.90	18.97	0.0621	0.537	6.21
25)	419.92	20.49	0.0621	0.537	6.21
26)	479.92	21.91	0.0621	0.537	6.21
27)	539.90	23.24	0.0621	0.537	6.21
28)	599.92	24.49	0.0621	0.537	6.21
29)	659.90	25.69	0.0621	0.537	6.21
30)	719.92	26.83	0.0621	0.537	6.21
31)	779.90	27.93	0.0616	0.538	6.16
32)	839.92	28.98	0.0616	0.538	6.16
33)	899.90	30.00	0.0621	0.537	6.21
34)	959.90	30.98	0.0621	0.537	6.21
35)	1019.92	31.94	0.0621	0.537	6.21

CONSOLIDATION TEST DATA

Project : EMDF Characterization	Location : GW995-ST-1, 2.5'-4.5'	Project No.: 183923
Boring No.: GW995-ST-1	Tested by : BMI: blc	Checked by : KAF
Sample No.: GW995-ST-1	Test Date : 3-15-18	Depth : 3.8'-4.0'
Test No. : GW995-ST-1	Sample Type: Undisturb	

Soil Description : red/brown clayey silt (visual description)
Remarks : Use: Near foundation/geobuffer layer

Load Increment : 20 of 20
Stress increment from 2.00 (t/ft^2) to 1.00 (t/ft^2)
Start Date : Start Time :

	ELAPSED TIME (min)	SQRT. OF TIME (min)	CHANGE IN HEIGHT (in)	VOID RATIO	STRAIN (%)
36)	1079.90	32.86	0.0616	0.538	6.16
37)	1139.93	33.76	0.0616	0.538	6.16
38)	1199.92	34.64	0.0621	0.537	6.21
39)	1259.92	35.50	0.0616	0.538	6.16
40)	1319.92	36.33	0.0616	0.538	6.16
41)	1379.90	37.15	0.0616	0.538	6.16
42)	1420.95	37.70	0.0616	0.538	6.16

BOWSER-MORNER, INC.

Delivery Address: 4518 Taylorsville Road • Dayton, Ohio 45424 **Mailing Address**: P. O. Box 51 • Dayton, Ohio 45401

AASHTO/ISO 17025 Accredited • USACE Validated

LABORATORY REPORT

Report To: CTI & Associates, Inc.
Attn: Michael Partenio
28001 Cabot Drive, Ste. 250
Novi, MI 48377

Report Date: May 24, 2018
Job No.: 183923
Report No.: 430281
No. of Pages: 1 + Appendix

Report On: Laboratory Analysis of One Shelby Tube Sample
Project: EMDF Characterization – Project No. 1188070011
Sample ID: GW995 - ST-2, 6.0'-8.0' – Sample Date: 2/20/18
Depth of Test Specimen: 6.3'-6.5'

On March 5, 2018, one shelby tube sample was submitted for selected laboratory analysis from the above referenced project. Testing was performed as specified by the client and in accordance with ASTM D 2435, "One-Dimensional Consolidation Properties of Soils Using Incremental Loading".

Results are summarized in the following table. Consolidation data is detailed in Appendix I.

Test Parameter	Before Test	After Test
Moisture Content, %:	**13.5**	**17.8**
Dry Density, pcf:	**109.66**	**112.65**
Saturation, %:	**68.66**	**98.23**
Void Ratio:	**0.53**	**0.49**
Apparent Specific Gravity:	**2.680**	

Should you have any questions, or if we may be of further service, please contact me at (937) 236-8805, extension 322.

Respectfully submitted,


BOWSER-MORNER, INC.

Karl A. Fletcher, Manager
Construction Materials and
Geotechnical Laboratories

KAF/blc
430281
1-File
1-mpartenio@cticompanies.com
1-kfoye@cticompanies.com

All Reports Remain The Confidential Property Of BOWSER-MORNER And No Publication Or Distribution Of Reports May Be Made Without Our Express Written Consent, Except As Authorized By Contract. Results Contained In This Report Are Reflective Only of The Items Calibrated or Tested. Unless Otherwise Agreed, Samples Or Specimens Will Be Discarded Or Returned At Bowser-Morner's Discretion. AASHTO/ISO 17025 Accreditation applies only to the parameters included in BOWSER-MORNER'S current scope of accreditation. Go to www.bowser-morner.com/accreditations for reviews.

Appendix I




			BEFORE TEST	AFTER TEST
OVERBURDEN PRESSURE (t/ft^2)		WATER CONTENT (%)	13.5	17.8
PRECONSOL. PRESSURE (t/ft^2)		DRY DENSITY (lb/ft^3)	109.66	112.65
COMPRESSION INDEX		SATURATION (%)	68.66	98.23
TYPE SPECIMEN	Undisturb	VOID RATIO	0.53	0.49
DIA. (in) 2.500	HT. (in) 1.000	BACK PRESSURE (t/ft^2)	---	---


CLASSIFICATION brown silty clay (visual description)

LL ---	PL ---	PI ---	PROJECT EMDF Characterization
GS 2.680	D_{10}		995ST2
REMARKS		BORING NO. GW995-ST-2	SAMPLE NO. GW995-ST-2
Use: Near foundation/ geobuffer layer		DEPTH 6.3'-6.5'	DATE 05/09/18

Bowser Morner
CONSOLIDATION TEST REPORT


CONSOLIDATION TEST
TIME CURVES (STEP 1 OF 19)
STRESS : 0.06 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-2 Sample No : GW995-ST-2
Test Date : 05/09/18 Test No : GW995-ST-2 Depth : 6.3'-6.5'
Description : brown silty clay (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 2 OF 19)
STRESS : 0.25 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-2 Sample No : GW995-ST-2
Test Date : 05/09/18 Test No : GW995-ST-2 Depth : 6.3'-6.5'
Description : brown silty clay (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 3 OF 19)
STRESS : 0.5 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-2 Sample No : GW995-ST-2
Test Date : 05/09/18 Test No : GW995-ST-2 Depth : 6.3'-6.5'
Description : brown silty clay (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 4 OF 19)
STRESS : 1 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-2 Sample No : GW995-ST-2
Test Date : 05/09/18 Test No : GW995-ST-2 Depth : 6.3'-6.5'
Description : brown silty clay (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 5 OF 19)
STRESS : 2 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-2 Sample No : GW995-ST-2
Test Date : 05/09/18 Test No : GW995-ST-2 Depth : 6.3'-6.5'
Description : brown silty clay (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 6 OF 19)
STRESS : 4 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-2 Sample No : GW995-ST-2
Test Date : 05/09/18 Test No : GW995-ST-2 Depth : 6.3'-6.5'
Description : brown silty clay (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 7 OF 19)
STRESS : 1 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-2 Sample No : GW995-ST-2
Test Date : 05/09/18 Test No : GW995-ST-2 Depth : 6.3'-6.5'
Description : brown silty clay (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 8 OF 19)
STRESS : 0.25 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-2 Sample No : GW995-ST-2
Test Date : 05/09/18 Test No : GW995-ST-2 Depth : 6.3'-6.5'
Description : brown silty clay (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 9 OF 19)
STRESS : 0.5 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-2 Sample No : GW995-ST-2
Test Date : 05/09/18 Test No : GW995-ST-2 Depth : 6.3'-6.5'
Description : brown silty clay (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 10 OF 19)
STRESS : 1 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-2 Sample No : GW995-ST-2
Test Date : 05/09/18 Test No : GW995-ST-2 Depth : 6.3'-6.5'
Description : brown silty clay (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 11 OF 19)
STRESS : 2 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-2 Sample No : GW995-ST-2
Test Date : 05/09/18 Test No : GW995-ST-2 Depth : 6.3'-6.5'
Description : brown silty clay (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 12 OF 19)
STRESS : 4 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-2 Sample No : GW995-ST-2
Test Date : 05/09/18 Test No : GW995-ST-2 Depth : 6.3'-6.5'
Description : brown silty clay (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 13 OF 19)
STRESS : 8 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-2 Sample No : GW995-ST-2
Test Date : 05/09/18 Test No : GW995-ST-2 Depth : 6.3'-6.5'
Description : brown silty clay (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 14 OF 19)
STRESS : 16 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-2 Sample No : GW995-ST-2
Test Date : 05/09/18 Test No : GW995-ST-2 Depth : 6.3'-6.5'
Description : brown silty clay (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 15 OF 19)
STRESS : 32 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-2 Sample No : GW995-ST-2
Test Date : 05/09/18 Test No : GW995-ST-2 Depth : 6.3'-6.5'
Description : brown silty clay (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 16 OF 19)
STRESS : 8 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-2 Sample No : GW995-ST-2
Test Date : 05/09/18 Test No : GW995-ST-2 Depth : 6.3'-6.5'
Description : brown silty clay (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 17 OF 19)
STRESS : 2 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-2 Sample No : GW995-ST-2
Test Date : 05/09/18 Test No : GW995-ST-2 Depth : 6.3'-6.5'
Description : brown silty clay (visual description)


CONSOLIDATION TEST
TIME CURVES (STEP 18 OF 19)
STRESS : 0.5 (t/ft^2)






Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-2 Sample No : GW995-ST-2
Test Date : 05/09/18 Test No : GW995-ST-2 Depth : 6.3'-6.5'
Description : brown silty clay (visual description)

CONSOLIDATION TEST
TIME CURVES (STEP 19 OF 19)
STRESS : 0.25 (t/ft^2)





Bowser Morner
Project Name : EMDF Characterization
Project No : 183923 Boring No : GW995-ST-2 Sample No : GW995-ST-2
Test Date : 05/09/18 Test No : GW995-ST-2 Depth : 6.3'-6.5'
Description : brown silty clay (visual description)

BOWSER-MORNER, INC.

Delivery Address: 4518 Taylorsville Road • Dayton, Ohio 45424 **Mailing Address**: P. O. Box 51 • Dayton, Ohio 45401

AASHTO/ISO 17025 Accredited • USACE Validated

LABORATORY REPORT

Report To: CTI & Associates, Inc.
Attn: Michael Partenio
28001 Cabot Drive, Ste. 250
Novi, MI 48377

Report Date: May 17, 2018
Job No.: 183923
Report No.: 430272
No. of Pages: 3

Report On: Laboratory Analysis of One Shelby Tube Sample
Project: EMDF Characterization – Project No. 1188070011
Sample ID: GW995 – ST-2, 6.0'-8.0' – Sample Date: 2/22/18

On March 5, 2018, one Shelby tube sample was submitted for selected laboratory analysis from the above referenced project. Testing was performed as specified by the client and in accordance with ASTM D 4767, "Consolidated-Undrained Triaxial Compression Test on Cohesive Soils".

Results are summarized below and detailed on the attached data sheets.

Test Parameter	Test No.1	Test No. 2	Test No. 3
Dry Density, pcf:	**107.9**	**106.05**	**No Test**
Moisture Content, %:	**15.55**	**17.12**	**No Test**
Minor Principle Stress, psi:	**15.46**	**23.65**	**No Test**
Maximum Deviator Stress, psi:	**52.84**	**69.43**	**No Test**
Cohesion (c'), psi:	**0.0**		
phi Angle (Ø'):	**36.9**		
Apparent Specific Gravity:	**2.68**		

Note: Two triaxial points were tested instead of three due to insufficient amount of sample.

Should you have any questions, or if we may be of further service, please contact me at (937) 236-8805 extension 322.

Respectfully submitted,


BOWSER-MORNER, INC.

Karl A. Fletcher, Manager
Construction Materials and
Geotechnical Laboratories


KAF/blc
430272
1-File
1-mpartenio@cticompanies.com
1-kfoye@cticompanies.com


All Reports Remain The Confidential Property Of BOWSER-MORNER And No Publication Or Distribution Of Reports May Be Made Without Our Express Written Consent, Except As Authorized By Contract. Results Contained In This Report Are Reflective Only of The Items Calibrated or Tested. Unless Otherwise Agreed, Samples Or Specimens Will Be Discarded Or Returned At Bowser-Morner's Discretion. AASHTO/ISO 17025 Accreditation applies only to the parameters included in BOWSER-MORNER'S current scope of accreditation. Go to www.bowser-morner.com/accreditations for reviews.

$\phi' = \sin^{-1} 0.60 = 36.9°$



FAILURE SKETCHES






SYMBOL		O	Δ		
TEST NO.		1	2		
INITIAL	WATER CONTENT (%)	15.55	17.12		
	DRY DENSITY (lb/ft^3)	107.49	106.05		
	SATURATION (%)	74.98	79.54		
	VOID RATIO	0.556	0.577		
BEFORE SHEAR	WATER CONTENT (%)	19.84	19.62		
	DRY DENSITY (lb/ft^3)	108.62	108.63		
	SATURATION (%)	98.52	97.49		
	VOID RATIO	0.540	0.539		
	BACK PRESS. (lb/in^2)	59.54	66.35		
MINOR PRIN. STRESS (lb/in^2)		15.46	23.65		
MAX. DEV. STRESS (lb/in^2)		52.84	69.43		
TIME TO FAILURE (min)		1143	1155		
RATE OF STRAIN INCR (%/min)		0.02	0.02		
INITIAL DIAMETER (in)		2.86	2.87		
INITIAL HEIGHT (in)		5.87	5.85		

CONTROLLED STRAIN TEST

DESCRIPTION OF SPECIMENS: 1) brown silty clay (visual description) 2) brown silty clay (visual description)

LL	PL	PI	GS 2.68	TYPE OF SPECIMEN Undisturbed	TYPE OF TEST CU (R)
REMARKS:				PROJECT EMDF Characterization	
1) Client: CTI & Associates, Inc.				PROJECT NO.183923	
2) Use: Near foundation / geobuffer layer				BORING NO. GW995-ST-2 SAMPLE NO.	1 / 2
				TECH. BMI: blc DEPTH/ELEV	6.5'-7.0' / 7.5'-8.0'
				LABORATORY DATE	05-13-18 / 05-14-18

TRIAXIAL COMPRESSION TEST REPORT



Project Name : EMDF Characterization				
Boring No:	Sample No	Depth	Test No	Filename Symbol
GW995-ST-2	1	6.5'-7.0'	1	c:\geocomp\392344 O
GW995-ST-2	2	7.5'-8.0'	2	c:\geocomp\392355 Δ

BOWSER-MORNER, INC.

Delivery Address: 4518 Taylorsville Road • Dayton, Ohio 45424 **Mailing Address**: P. O. Box 51 • Dayton, Ohio 45401

AASHTO/ISO 17025 Accredited • USACE Validated

LABORATORY REPORT

Report To: CTI & Associates, Inc.
Attn: Michael Partenio
28001 Cabot Drive, Ste. 250
Novi, MI 48377

Report Date: May 4, 2018
Job No.: 183923
Report No.: 430252
No. of Pages: 2

Report On: Laboratory Analysis of One Shelby Tube Sample
Project: EMDF Characterization – Project No. 1188070011
Sample ID: GW999 – ST-1, 2.5'-4.5' – Sample Date: 2/20/18

On March 5, 2018, one Shelby tube sample was submitted for selected laboratory analysis from the above referenced project. Testing was performed as specified by the client and in accordance with the ASTM D 4318, "Liquid Limit, Plastic Limit, and Plasticity Index of Soils".

Results are presented in the following table and detailed on the attached data sheet.

Test Parameter	Results
Liquid Limit:	**46**
Plastic Limit:	**31**
Plasticity Index:	**15**

Should you have any questions, or if we may be of further service, please contact me at (937) 236-8805, extension 322.

Respectfully submitted,


BOWSER-MORNER, INC.

Karl A. Fletcher, Manager
Construction Materials and
Geotechnical Laboratories

KAF/blc
430252
1-File
1-mpartenio@cticompanies.com
1-kfoye@cticompanies.com

All Reports Remain The Confidential Property Of BOWSER-MORNER And No Publication Or Distribution Of Reports May Be Made Without Our Express Written Consent, Except As Authorized By Contract. Results Contained In This Report Are Reflective Only of The Items Calibrated or Tested. Unless Otherwise Agreed, Samples Or Specimens Will Be Discarded Or Returned At Bowser-Morner's Discretion. AASHTO/ISO 17025 Accreditation applies only to the parameters included in BOWSER-MORNER'S current scope of accreditation. Go to www.bowser-morner.com/accreditations for review.

LIQUID AND PLASTIC LIMITS TEST REPORT



	MATERIAL DESCRIPTION	LL	PL	PI	%<#40	%<#200	USCS
●	GW999-ST-1 (Visual Description: brown clayey silt)	46	31	15			

Project No. 183923 **Client:** CTI and Associates, Inc.

Project: EMDF Characterization

● **Source of Sample:** GW-999 **Depth:** 2.5' - 4.5' **Sample Number:** ST-1

Remarks:

BOWSER-MORNER, INC.

Dayton, Ohio F-300

BOWSER-MORNER, INC.

Delivery Address: 4518 Taylorsville Road • Dayton, Ohio 45424 **Mailing Address**: P. O. Box 51 • Dayton, Ohio 45401

AASHTO/ISO 17025 Accredited • USACE Validated

LABORATORY REPORT

Report To: CTI & Associates, Inc.
Attn: Michael Partenio
28001 Cabot Drive, Ste. 250
Novi, MI 48377

Report Date: May 3, 2018
Job No.: 183923
Report No.: 430247
No. of Pages: 2

Report On: Laboratory Analysis of One Shelby Tube Sample
Project: EMDF Characterization – Project No. 1188070011
Sample ID: GW999 – ST-2, 5.0'-5.85' – Sample Date: 2/20/18
Depth of Test Specimen: 5.0'-5.3'

On March 5, 2018, one Shelby tube sample was submitted for laboratory determination of permeability. Testing was performed as specified by the client and in accordance with ASTM D 5084, "Measurement of Hydraulic Conductivity of Saturated Porous Materials Using a Flexible Wall Permeameter".

Results are presented in the following table.

Test Parameter	Results
Average Permeability, cm/sec:	**3.9×10^{-8}**

Should you have any questions, or if we may be of further service, please contact me at (937) 236-8805, extension 322.

Respectfully submitted,
BOWSER-MORNER, INC.

Karl A. Fletcher, Manager
Construction Materials and
Geotechnical Laboratories

KAF/blc
430247
1-File
1-mpartenio@cticompanies.com
1-kfoye@cticompanies.com

All Reports Remain The Confidential Property Of BOWSER-MORNER And No Publication Or Distribution Of Reports May Be Made Without Our Express Written Consent, Except As Authorized By Contract. Results Contained In This Report Are Reflective Only of The Items Calibrated or Tested. Unless Otherwise Agreed, Samples Or Specimens Will Be Discarded Or Returned At Bowser-Morner's Discretion. AASHTO/ISO 17025 Accreditation applies only to the parameters included in BOWSER-MORNER'S current scope of accreditation. Go to www.bowser-morner.com/accreditations for reviews.

FALLING HEAD PERMEABILITY TEST

ASTM D 5084, Measurement of Hydraulic Conductivity

UNDISTURBED

Client:	**CTI & Associates, Inc.**
Project:	**EMDF Characterization**
BMI Work Order Number:	183923
Sample Identification:	GW999-ST-2, 5.0'-5.85'
Depth, ft:	5.0'-5.3'
Visual Description:	Saprolite

SPECIMEN DATA:

Dimension, inches	
Height:	3.08
Diameter:	2.863
Mass, lbs:	1.458
Moisture Content,%	
Initial:	21.4
Final:	25.0
Wet Unit Weight, pcf	
Initial:	127.1
Final:	130.9
Initial Dry Unit Weight, pcf:	104.7
Back Pressure Saturation, psi	
Back Pressure, Exit:	60
Back Pressure, Enter:	63
Lateral Pressure:	67

Permeability (k), cm/sec: **3.9×10^{-8}**

Appendix F.4 – Rock Core Specimen Testing

This Page Intentionally Left Blank.

BOWSER-MORNER, INC.

Delivery Address: 4518 Taylorsville Rd • Dayton, Ohio 45424 **Mailing Address:** P.O. Box 51 • Dayton, Ohio 45401

AASHTO/ISO 17025 Accredited • USACE Validated

LABORATORY REPORT

Report To: CTI and Associates
Attn: Kevin Foye
28001 Cabot Drive, Suite 250
Novi, MI 48477

Report Date: 04/18/18
Job No.: 183740
Report No.: 301273
No. of Pages: 8

Source: EMDF Characterization

Date Submitted: 03/01/18

Project No.: 1188070011

Procedure: Compressive Strength of Intact Rock Core Specimens (ASTM D 7012 Method C & D)

Sample Identification:	GW 978-RC-9	GW 988-RC-10	GW 982-RC-10	GW 982-RC-13	GW 978-RC-6	GW 992-RC-4
Length As Cut, Inches:	3.97	2.85	4.33	4.69	4.65	3.38
Diameter, Inches:	2.38	2.38	2.37	2.39	2.35	2.38
Mass, grams:	757.6	599.4	802.9	940.1	868.6	607.6
Maximum Load, lbs:	6,720	32,462	190	107,074	3,241	2,755
Area, Square Inches:	4.45	4.45	4.41	4.49	4.34	4.45
Volume, cubic ft:	0.0102	0.0073	0.0111	0.0122	0.0117	0.0087
L/D Ratio:	1.67	1.20	1.83	1.96	1.98	1.42
Compressive Strength, psi:	**1,510**	**7,290**	**40**	**23,850**	**750**	**620**
Density, pcf:	**163.4**	**180.0**	**160.2**	**170.1**	**164.0**	**153.9**
Young's Modulus (E_{av})	**8.0×10^4**	**2.4×10^5**	**cannot determine**	**4.5×10^5**	**4.4×10^4**	**5.0×10^4**

Note: specimens GW 982-RC-10, GW 982-RC-13, and GW 992-RC-4 all failed along natural planes of weakness contained in the rock core. See attached photos for mode of failure criteria.

Should you have any questions, or if we may be of further service, please contact me at (937) 236-8805, ext. 322.

Respectfully submitted,
BOWSER-MORNER, INC.


Karl A. Fletcher

Karl A. Fletcher, Manager
Construction Materials and
Geotechnical Laboratories


KAF/bk/jd
301273
1-File
1-kfoye@cticompanies.com

This document has been provided in an electronic format to expedite delivery of results and / or recommendations to BOWSER-MORNER's Client. A wet-signed original is maintained at our Dayton office at 4518 Taylorsville Rd., Dayton, OH 45424. Because electronic documents can be altered, if there is any question about the validity of this document, please contact our office to view the file wet signed original.


All Reports Remain The Confidential Property Of BOWSER-MORNER And No Publication Or Distribution Of Reports May Be Made Without Our Express Written Consent, Except As Authorized By Contract. Results Contained In This Report Are Reflective Only Of The Items Calibrated Or Tested. Unless Otherwise Agreed, Samples or Specimens Will Be Discarded Or Returned At Bowser-Morner's Discretion. AASHTO/ISO 17025 Accreditation applies only to the parameters included in BOWSER-MORNER'S current scope of accreditation. Go to www.bowser-morner.com/accreditations for review.




$$E_{av} = \frac{\Delta\sigma}{\Delta E_2} = \frac{800\ psi}{0.01} = 8.0 \times 10^4\ psi$$




$$E_{av} = \frac{\Delta\sigma}{\Delta E_2} = \frac{4000\ psi}{0.017} = 2.4 \times 10^5\ psi$$


GW982-RC-10 (ASTM D 7012)
50
0
-50
Load, psi
0
0.02
0.04
0.06
0.08
0.1
0.12
0.14
Strain




$$E_{av} = \frac{\Delta\sigma}{\Delta E_2} = \frac{20000\,psi}{0.044} = 4.5 \times 10^5\,psi$$



$$E_{av} = \frac{\Delta\sigma}{\Delta E_2} = \frac{400\text{ psi}}{0.009} = 4.4 \times 10^4$$

F-310




$$E_{av} = \frac{\Delta\sigma}{\Delta E_2} = \frac{300\,psi}{0.006} = 5.0 \times 10^4$$

Compressive Strength of Intact Rock Core Specimens (ASTM D 7012 Method C & D)

Before













After











